

TERRY E. BRANSTAD, GOVERNOR KIM REYNOLDS, LT. GOVERNOR

STATE OF IOWA

DEPARTMENT OF NATURAL RESOURCES CHUCK GIPP, DIRECTOR

July 17, 2014

Lamoni Municipal Utilities Attn: Mr. Emil Segebart, Jr. 111 South Chestnut Street Lamoni, IA 50140

Subject: Variance Request from Design Standards Section 13.4.2 LMU Sanitary Sewer Improvements, Lamoni, Iowa IDNR Project No. S2013-0023

Dear Mr. Segebart:

After careful and thorough consideration, the Department has <u>approved</u> your June 19, 2014 request for a variance from Section 13.4.2 of the Iowa Wastewater Facilities Design Standards which requires screens or trash baskets for raw wastewater lift stations. Based on the documentation presented by your Engineer, it is the determination of this Department that satisfactory justification has been presented to warrant the granting of a variance for the construction of a lift station without the installation of screens or trash baskets. The requested variance is deemed to be reasonable and necessary pursuant to the Iowa Code section 455B.181.

The facts presented for the project present unique circumstances and the approved variance is therefore justified to provide the narrowest exception possible to the provisions of the rules in accordance with Rule 561 IAC 10.5. Since the project planning and construction may last more than one year, the variance is considered to be of a permanent nature. The validity of this variance approval shall last for a period of one year from the date of the construction permit in accordance with Rule 561 IAC 10.5.

This decision is based on our review of justification presented to support the request. Our concurrence with the request is based on the Department's finding that the resulting project will provide substantially equivalent effectiveness as would be provided by technical compliance with the design standard on this issue.

If you have any questions, please call Marty Jacobs at 515-242-6148.

Sincerely,

Shelli Grapp Water Quality Bureau Chief

cc: Forrest Aldrich, P.E., Veenstra & Kimm, Inc. DNR Field Office #5 - Tom Atkinson IDNR Sewage File # 6-27-40-0-01 DNR Legal Services - Diana Hansen

| Iowa Department of Natural Resources 1. Date: July 10, 2014 14a. Decision: 2. Reviewer/Engr.: Marty Jacobs Date: Expiration Date 3. Date Received: June 23, 2014 14b. (if any): Permanent 4. Facility Name: City of Lamoni Expiration Date 5. Facility Number: 6-27-40-0-01 6 6. County Number: 7. (Decatur) 15. Appealed: 7. Program Area: CP (Wastewater) Date: 8. Facility Type: C01 (Collection/Transport) 9. 9. Subject Area: 344 (pump clogging protection) 10. 10. Reik Reference: 567-64.2(9)a 114 13. Variance Rule: 567-64.2(9)c 16 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 7. ApplicantryConsulting Engineer's Justification: 17 The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. 17. Applicanetts Justification: If Applicanetts Justification; <t< th=""><th colspan="7">VARIANCE REQUEST</th></t<> | VARIANCE REQUEST | | | | | | |
|--|---|-------------------|----------------------------|------|------------|---------------------------------------|--|
| 2. Reviewer/Engr.: Marty Jacobs Date: 3. Date Received: June 23, 2014 14b. (if any): Permanent 4. Facility Name: City of Lamoni 5 5. Facility Number: 6-27-40-0-01 6 6. County Number: 27 (Decatur) 15. Appealed: 7. Program Area: CP (Wastewater) Date: 8 8. Facility Type: C01 (Collection/Transport) 9 Subject Area: 344 (pump clogging protection) 10. Rule Reference: 567-64.2(9)a 11 14 12 11. Design Std. Ref: 13.4.2 12 12 13.4.2 12. Consulting Engr:: Veenstra & Kimm 13.4.2 (Protection Against Clogging) for installation of a wastewater Iff station with well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station or trash basket. 18. Department's Justification: The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. Th | 4 | Dete | | | | · · · · · · · · · · · · · · · · · · · | |
| Expiration Date 3. Date Received: June 23, 2014 14b. (if any): Permanent 4. Facility Name: City of Lamoni Facility Number: 6:27:40-0-01 6. County Number: 27 (Decatur) 15. Appealed: 7 7. Program Area: CP (Wastewater) Date: 8 8. Facility Type: C01 (Collection/Transport) 9. Subject Area: 344 (pump clogging protection) 10. Rule Reference: 567-64.2(9)a 11. Design Std. Ref: 13.4.2 11. Design Std. Ref:: 13.4.2 (9)c 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 - - Wastewater Pump Stations and Force Mains - 13.4.2 (Protection Against Clogging) for instaliation of a wastewater Pump Station. If trash the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification. Recomment's Justification. Recomment's Justification. Recomment's Justification. Recomments Justification. Recomment's Justification. | | | • | 14a. | | | |
| 3. Date Received: June 23, 2014 14b. (if any): Permanent 4. Facility Name: City of Lamoni 5. 5. Facility Number: 6-27-40-0-01 15. Appealed: 7. Program Area: CP (Wastewater) Date: 8. Facility Type: C01 (Collection/Transport) Date: 9. Subject Area: 344 (pump clogging protection) Date: 10. Rule Reference: 567-64.2(9)a 11. 11. Design Std. Ref.: 13.4.2 12. 2. Consulting Engr:: Veenstra & Kimm 3. 13. Variance Rule: 567-64.2(9)c 16. 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 -Wastewater Pump Stations and Force Mains = 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The lift station without a trash basket or screens. 18. Department's Justification: The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Readition water ween the design standad | Ζ. | Reviewer/Engr.: | Marty Jacobs | | | | |
| 5. Facility Number: 6-27-40-0-01 6. County Number: 27 (Decatur) 15. Appealed: 7. Program Area: CP (Wastewater) Date: 8. Facility Type: C01 (Collection/Transport) 9. Subject Area: 344 (pump clogging protection) 10. Rule Reference: 567-64.2(9)a 11. Design Std. Ref: 13.4.2 12. Consulting Engr.: Veenstra & Kimm 13. Variance Rule: 567-64.2(9)c 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 - Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The Iagoon and lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station is result approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station is an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and one track that was being treated by the lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and one treact babove, any debris passing through the sewer lines is expected to settle out in the lagoon and collection system: Settle end the lift | 3. | Date Received: | June 23, 2014 | 14b. | • | Permanent | |
| 5. Facility Number: 6-27-40-0-01 6. County Number: 27 (Decatur) 15. Appealed: 7. Program Area: CP (Wastewater) Date: 8. Facility Type: C01 (Collection/Transport) 9. Subject Area: 344 (pump clogging protection) 10. Rule Reference: 567-64.2(9)a 11. Design Std. Ref: 13.4.2 12. Consulting Engr.: Veenstra & Kimm 13. Variance Rule: 567-64.2(9)c 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 - Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The Iagoon and lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station is result approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station is an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and one track that was being treated by the lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and one treact babove, any debris passing through the sewer lines is expected to settle out in the lagoon and collection system: Settle end the lift | 4. | Facility Name: | City of Lamoni | | | | |
| 7. Program Area: CP (Wastewater) Date: 8. Facility Type: C01 (Collection/Transport) 9. Subject Area: 344 (pump clogging protection) 10. Rule Reference: 567-64.2(9)a 11. Design Std. Ref.: 13.4.2 12. Consulting Engr.: Veenstra & Kimm 13. Variance Rule: 567-64.2(9)c 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 - Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater Pump Station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treachent lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The iff station pumps w | 5. | | 6-27-40-0-01 | | | | |
| 7. Program Area: CP (Wastewater) Date:: 8. Facility Type: C01 (Collection/Transport) 9. Subject Area: 344 (pump clogging protection) 10. Rule Reference: 567-64.2(9)a 11. Design Std. Ref.: 13.4.2 12. Consulting Engr: Veenstra & Kimm 13. Variance Rule: 567-64.2(9)c 16. Description of Variance Request: The City of Lamoni is requesting variance from the lowa Wastewater Facilities Design Standards Chapter 13 - Wastewater Pump Stations and Force Mans – 13.4.2 (Protection Against Clogging) for installation of a wastewater Pump Stations and Force Mans – 13.4.2 (Protection Against Clogging) for installation of a wastewater Pump Stations and Force Mans – 13.4.2 (Protection Against Clogging) for installation of a wastewater Pump Station and lift station. If the lagoon into a lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: 17. Recommend variance approval. 18. Department's Justification project will on we twee that was being treated by the lagoon to the Lamoni treatment plant. Th | 6. | County Number: | 27 (Decatur) | 15. | Appealed: | | |
| 8. Facility Type: C01 (Collection/Transport) 9. Subject Area: 344 (pump clogging protection) 10. Rule Reference: 567-64.2(9)a 11. Design Std. Ref: 13.4.2 12. Consulting Engr.: Veenstra & Kimm 13. Variance Rule: 567-64.2(9)c 16. Description of Variance Reguest: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 – Vastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon being converted to float or sink rather than be conveyed to the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. Precedents Used: Asburd - 2/7/08 Nashua - 3/20/07 20. Staff Reviewer: Wum for the station. 21. Supervisor: Used: Asburd - 2/7/08 | 7. | Program Area: | CP (Wastewater) | | Date: | | |
| 9. Subject Area: 344 (pump clogging protection) 10. Rule Reference: 567-64.2(9)a 11. Design Std. Ref.: 13.4.2 12. Consulting Engr: Veenstra & Kimm 13. Variance Rule: 567-64.2(9)c 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 - Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification; Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the iff station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. Pr | 8. | | C01 (Collection/Transport) | | | | |
| 10. Rule Reference: 567-64.2(9)a 11. Design Std. Ref.: 13.4.2 12. Consulting Engr.: Veenstra & Kimm 13. Variance Rule: 567-64.2(9)c 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 - Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station or trash basket. 18. Department's Justification: If reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. The readeont subsed: As onted above, any debris passing t | 9. | | | | | | |
| 11. Design Std. Ref.: 13.4.2 12. Consulting Engr.: Veenstra & Kimm 13. Variance Rule: 567-64.2(9)c 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 – Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon the Lamoni treatment plant. The former lagoon and collection system is being treated by the lagoon to Lamoni that incenter the fortive first pass through this lagoon where most are expected to float or sink rather than be conveyed to the line of the lift station. 18. Department's Justification: The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design stand | 10. | | | | | | |
| Consulting Engr.: Veenstra & Kimm Variance Rule: 567-64.2(9)c Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 – Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. Applicant's/Consulting Engineer's Justification: The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. Precedents Used: Asbury - 12/12/07 Staff Reviewer: Muthow Amathematica State Sta | 11. | Desian Std. Ref.: | | | | | |
| 13. Variance Rule: 567-64.2(9)c 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 - Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. 19. Precedents Used: Asbury - 12/12/07 20. Staff Reviewer: Muth Machine Machine Machine Machine Machine Machine Machine Asbury - 12/12/07 20. Staff Reviewer: Muth Machine Machine Machine Machine Machine Machine Machine Machine Machine Machine Mashua - 9/20/07 Date: 7/9/14/10/10/14/ 21. | | · · | | | | | |
| 16. Description of Variance Request: The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The Iagoon and lift station we well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station besides in the lagoon before it reacon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. Precedents Used: Asbury - 12/12/07 20. Staff Reviewer: Math. Am. Am. Am. Am. Date: 79/14, 7/10/14, 20/1 | | | | | | | |
| The City of Lamoni is requesting variance from the Iowa Wastewater Facilities Design Standards Chapter 13 - Wastewater Pump Stations and Force Mains – 13.4.2 (Protection Against Clogging) for installation of a wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon a | | | | | | | |
| wastewater lift station without a trash basket or screens. 17. Applicant's/Consulting Engineer's Justification: The lagoon and lift station well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Mam | | | | | | | |
| 17. Applicant's/Consulting Engineer's Justification: The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. <u>Department's Justification</u>: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: <u>Math American Amer</u> | | | | | | | |
| The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. Precedents Used: Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Math Math Math Math Math Math Math Math | | | | | | | |
| constantly submerged and therefore impractical. The lift station was included in a project that converted a former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Math Amerged, | | | | | | | |
| former treatment lagoon into a lift station. If trash enters the collection system, it settles in the lagoon before it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being retained by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: <u>Math America</u> , with Date: <u>79/14</u> , <u>710/14</u> 21. Supervisor: <u>Jatya</u> <u>Guenny</u> <u>Date</u> : <u>79/14</u> , <u>710/14</u> 21. Supervisor: <u>Jatya</u> <u>Guenny</u> <u>Date</u> : <u>79/14</u> , <u>710/14</u> | | | | | | | |
| it reaches the lift station or trash basket. 18. Department's Justification: Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Mamman Mam | | | | | | | |
| 18. <u>Department's Justification:</u> Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 20. Staff Reviewer: Mamman Mamma | | | | | | | |
| Recommend variance approval. The variance request was evaluated to determine whether unique circumstances provide for substantially equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. Precedents Used: Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Wath Agementation Date: 7/9/14, 7/10/14 21. Supervisor: Gatth Agementation | | | | | | | |
| equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. <u>19. Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Math Math Math Math Math Math Math Math | | | | | | | |
| equivalent effectiveness in comparison to the design standards. This lift station serves an industrial park area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. <u>19. Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Math Math Math Math Math Math Math Math | The verience request use evelopted to determine whether writing simulations are stated for evelopted in the | | | | | | |
| area of Lamoni that previously had its own controlled discharge lagoon treatment system. The lift station project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. <u>19. Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Math Math Math Math Math Math Math Math | | | | | | | |
| project will convey the wastewater that was being treated by the lagoon to the Lamoni treatment plant. The former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Mathematical Action and the sewer base. 21. Supervisor: Cattle Cattle Cattle Cattle Cattle Date: Top/14, Too/14 21. Supervisor: Cattle Cattle Cattle Cattle Cattle Date: Top/14, Too/14 | | | | | | | |
| former lagoon and collection system is being retained and will be used as an equalization basin. Objects likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Mathematical Content of the lagoon bate: 79/14, 7/10/14 21. Supervisor: Cattle Chematical Content of the lagoon bate: 79/14 | | | | | | | |
| likely to clog the lift station pumps will have to first pass through this lagoon where most are expected to float or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Mark for the sewer lines is expected to settle out in 21. Supervisor: Jatua Chemark Date: 7/9/14, 7/10/14 21. Supervisor: Jatua Chemark | | | | | | | |
| or sink rather than be conveyed to the inlet of the lift station. This is unique construction with the former Industrial Park treatment system lagoon being converted to an equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: <u>Mathematication</u> Date: <u>79/14</u> 7/10/14 21. Supervisor: <u>Jatua Chemination</u> Date: <u>715/14</u> | | | | | | | |
| equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Muth for the formation of the sewer lines is expected to settle out in the lagoon and not reach the lift station. 21. Supervisor: Jatua Guennyati Date: 7/9/14, 7/10/14 21. Supervisor: Jatua Guennyati Date: 7/15/14 | | | | | | | |
| the lagoon and not reach the lift station. 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Muth for for fight Date: 7/9/14, 7/10/14 21. Supervisor: Jate Chemination Date: 7/15/14 | | | | | | | |
| 19. <u>Precedents Used:</u> Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Muth for the two that the Date: 7/9/14, 7/10/14 21. Supervisor: Jatya Chemungati Date: 7/15/14 | equalization basin. As noted above, any debris passing through the sewer lines is expected to settle out in | | | | | | |
| Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Muth for the Engle Date: 7/9/14, 7/10/14 21. Supervisor: Gatya Ghennyati Date: 7/15/14 | the lagoon and not reach the lift station. | | | | | | |
| Asbury - 12/12/07 Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Muth for the English Date: 7/9/14, 7/10/14 21. Supervisor: Jatya Ghennyati Date: 7/15/14 | | | | | | | |
| Diamond Head Sanitary District - 2/7/08 Nashua - 9/20/07 20. Staff Reviewer: Muntin for the English Date: 7/9/14, 7/10/14 21. Supervisor: Gateh Chennyath Date: 7/15/14 | | | | | | | |
| Nashua - 9/20/07 20. Staff Reviewer: Muntin for to English Date: 7/9/14, 7/10/14 21. Supervisor: Gatya cheminati Date: 7/15/14 | | | | | | | |
| 20. Staff Reviewer: United for the Date: 7/9/14, 7/10/14 21. Supervisor: Gatya chennyati Date: 7/15/14 | | | | | | | |
| 21. Supervisor: Catya chennyati Date: 7/15/14 | | , | | | | 1 | |
| - Oguga Glennighth FISTIG | 20. Starr Reviewer: Muntin for to Eng & Date: 7/9/14 7/10/14 | | | | | | |
| 22. Authorized by: Juli Stapp Date: 7-17-14 | 21. Supervisor: Jatya chennypath Date: 7/15/14 | | | | | | |
| | 22. | Authorized by: | ulli Drapp | Date | e: 7-17-14 | | |

52013-0023



VEENSTRA & KIMM, INC.

3000 Westown Parkway • West Des Moines, Iowa 50266-1320 515-225-8000 • 515-225-7848(FAX) • 800-241-8000(WATS)

June 6, 2014

Martin Jacobs Iowa DNR Headquarters Wallace State Office Building 502 East 9th Street, 4th Floor Des Moines, IA 50319

LAMONI, IOWA SANITARY SEWER COLLECTION SYSTEM IMPROVEMENTS CONSTRUCTION PERMIT NO. 2013-01555 PETITION FOR VARIANCE

Enclosed is a copy of the Petition for Variance for the improvements previously made to the sanitary sewer collection system.

Lamoni Municipal Utilities would like to omit the use of the trash basket, due to its impracticality.

If you have any questions or comments, please contact us at 515-225-8000.

VEENSTRA & KIMM, INC.

Forrest Aldrich

FSA:kta 138-89 Enclosure cc: Emil Segebart, Lamoni Municipal Utilities w/ enclosure

RECEIVED JUN 1 0 2014

West Des Moines • Coralville • Omaha • Moline • Mason City • Sioux City • Liberty

ORECEIVED JUN 1 0 2014

PETITION FOR VARIANCE

Iowa Administrative Code 561-10.9

10.9(1) - Name of Petitioner: Lamoni Municipal Utilities

10.9(1) – Address & Telephone Number of Petitioner:

Address: Lamoni Municipal Utilities Phone Number: 641-784-6911 111 South Chestnut Street Lamoni. Iowa 50140

10.9(1) - Case Number of Related Contested Case: Not Applicable

10.9(2) - Description/Citation of Specific Rule:

13 Wastewater Pumping Stations and Force Mains 13.4 Pumps and Pneumatic Ejectors 13.4.2 Protection Against Clogging

All Pumping stations handling raw wastewater shall have provisions for screening to protect the pumps from clogging or damage.

Trash baskets constructed of a corrosion resistant material and easily removable for cleaning may be used for small pumping stations.

Bar racks with clear openings not exceeding 2 ½ inches shall be provided for larger stations.

Mechanically cleaned bar screens with manually cleaned bar rack bypasses shall be considered for very large installations.

Unless screenings can be collected at ground level, hoists shall be provided for removing screenings containers from facilities located below ground.

- 10.9(3) Specific Variance Requested: Request variance to allow the omittance of a screening, namely a trash basket.
- 10.9(4) Relevant Facts & Justification: The lagoon and lift station wet well have the same water levels and elevations, so a trash basket would be constantly submerged and therefore impractical.
- 10.9(5) History of Prior Contacts: Construction permit # 2013-01555 issued November 28, 2012.
- 10.9(6) Information Known to Petitioner Regarding IDNR Treatment of Similar Cases: None

- 10.9(7) Name, Address, and Telephone Number of Public Agency, Political Subdivision of the State or Federal Government which also Regulates the Activity in Question, or Might be Affected by the Granting of a Waiver or Variance: None
- 10.9(8) Name, Address, and Telephone Number of any Person or Entity that Would be Adversely Affected by the Granting of the Petition: None
- 10.9(9) Name, Address, and Telephone Number of any Person with Knowledge of Relevant Facts Relating to the Proposed Waiver or Variance:

Name: Veenstra & Kimm, Inc. – Consultant Contact Person: Forrest Aldrich, P.E.

> Address: 3000 Westown Parkway West Des Moines, Iowa 50266

Telephone Number: 515-225-8000

Name: Lamoni Municipal Utilities Contact Person: Emil Segebart

> Address: 111 South Chestnut Street Lamoni, Iowa 50140

Telephone Number: 641-784-6911

10.9(10) - Signed Releases Authorizing Persons with Factual Knowledge of Relevant Facts Concerning the Variance:

IOWA ADMINISTRATIVE CODE 561 – 10.11

10.11(17a, 455A) - Notice by Certified Mail:

This Petition is duly submitted this _____ day of June, 2014 by the Lamoni Municipal Utilities as Petitioner. The Petitioner attests to the accuracy of the facts provided in this Petition and the statements of reasons that the Petitioner believes justify this variance request.

nulle

Lamoni Municipal Utilities

Project Engineer Veenstra & Kimm, Inc.

52013-0023

87525 JUN20'14 PM 3:01



VEENSTRA & KIMM, INC.

3000 Westown Parkway • West Des Moines, Iowa 50266-1320 515-225-8000 • 515-225-7848(FAX) • 800-241-8000(WATS)

June 19, 2014

Martin Jacobs Iowa DNR Headquarters Wallace State Office Building 502 East 9th Street, 4th Floor Des Moines, IA 50319

LAMONI, IOWA SANITARY SEWER COLLECTION SYSTEM IMPROVEMENTS CONSTRUCTION PERMIT NO. 2013-01555 PETITION FOR VARIANCE

As discussed in the Petition of Variance sent June 6, 2014, Lamoni Municipal Utilities would like to omit the use of a trash basket, due to its impracticality. This impracticality can be attributed to two different reasons, discussed below.

The first is that if a trash basket were to be installed, it would be constantly submerged, thus making it inaccessible. The proposed trash basket could not be emptied using reasonable methods.

Secondly, all the trash that does enter the system settles in the lagoon prior to reaching the location of the trash basket. The trash settles in the pond and does not reach the trash basket. See attached sketch.

Due to the inaccessibility of the trash basket and the existence of the lagoon, Lamoni Municipal Utilities would request approval of a variance to omit its use of a trash basket.

If you have any questions or comments, please contact us at 515-225-8000.

VEENSTRA & KIMM, INC.

Forrest Aldrich

FSA:kta 13889 Enclosure cc: Emil Segebart, Lamoni Municipal Utilities w/ enclosure

West Des Moines • Coralville • Omaha • Moline • Mason City • Sioux City • Liberty

RECEIVED JUN 2 3 2014

LAMONI SEWER COLLECTION SYSTEM IMPROVEMENTS

