

**Iowa Department of Natural Resources
Title V Operating Permit**

Name of Permitted Facility: Muscatine Power and Water
Facility Location: 1700 Dick Drake Way
Muscatine, Iowa 52761

Air Quality Operating Permit Number: 98-TV-021R3-M001
Expiration Date: November 2, 2020
Permit Renewal Application Deadline: May 2, 2020

EIQ Number: 92-3726
Facility File Number: 70-01-011

Responsible Official

Name: Mary Jean Brewster
Title: Manager, Environmental Affairs
Mailing Address: 3205 Cedar Street, PO Box 899
Muscatine, Iowa 52761-2204
Phone #: (563) 262-3259

Permit Contact Person for the Facility

Name: Mary Jean Brewster
Title: Manager, Environmental Affairs
Mailing Address: 3205 Cedar Street, PO Box 899
Muscatine, Iowa 52761-2204
Phone #: (563) 262-3259

This permit is issued in accordance with 567 Iowa Administrative Code Chapter 22, and is issued subject to the terms and conditions contained in this permit.

For the Director of the Department of Natural Resources

Lori Hanson, Supervisor of Air Operating Permits Section

Date

Table of Contents

I. Facility Description and Equipment List	4
II. Plant-Wide Conditions.....	9
III. Emission Point Specific Conditions	13
IV. General Conditions.....	222
G1. Duty to Comply	
G2. Permit Expiration	
G3. Certification Requirement for Title V Related Documents	
G4. Annual Compliance Certification	
G5. Semi-Annual Monitoring Report	
G6. Annual Fee	
G7. Inspection of Premises, Records, Equipment, Methods and Discharges	
G8. Duty to Provide Information	
G9. General Maintenance and Repair Duties	
G10. Recordkeeping Requirements for Compliance Monitoring	
G11. Evidence used in establishing that a violation has or is occurring.	
G12. Prevention of Accidental Release: Risk Management Plan Notification and Compliance Certification	
G13. Hazardous Release	
G14. Excess Emissions and Excess Emissions Reporting Requirements	
G15. Permit Deviation Reporting Requirements	
G16. Notification Requirements for Sources That Become Subject to NSPS and NESHAP Regulations	
G17. Requirements for Making Changes to Emission Sources That Do Not Require Title V Permit Modification	
G18. Duty to Modify a Title V Permit	
G19. Duty to Obtain Construction Permits	
G20. Asbestos	
G21. Open Burning	
G22. Acid Rain (Title IV) Emissions Allowances	
G23. Stratospheric Ozone and Climate Protection (Title VI) Requirements	
G24. Permit Reopenings	
G25. Permit Shield	
G26. Severability	
G27. Property Rights	
G28. Transferability	
G29. Disclaimer	
G30. Notification and Reporting Requirements for Stack Tests or Monitor Certification	
G31. Prevention of Air Pollution Emergency Episodes	
G32. Contacts List	
V. Appendix:.....	237
Appendix A: Links to Standards	
Appendix B: Acid Rain Phase II Permit.....	238
Appendix C: Cross-State Air Pollution Rule (CSAPR) Permit	247

Abbreviations

acfm.....	Actual cubic feet per minute
bhp.....	brake horse power
CE	control equipment
CEM.....	continuous emissions monitor
cfm.....	cubic feet per minute
CFR.....	Code of Federal Regulations
dscfm.....	dry standard cubic feet per minute
EIQ.....	Emissions inventory questionnaire
EP	emission point
EU	emission unit
°F.....	Degrees fahrenheit
gr./dscf	Grains per dry standard cubic foot
gal.....	gallon
IAC.....	Iowa Administrative Code
IDNR.....	Iowa Department of Natural Resources
kW.....	kilowatt
lb./hr	Pounds per hour
lb./mmBtu	Pounds per million British thermal units
MVAC.....	Motor vehicle air conditioner
NAICS.....	North American Industry Classification System
NSPS	New source performance standards
SCC.....	Source Classification Codes
scfm.....	standard cubic feet per minute
SIC	Standard Industrial Classification
Tons/hr	Tons per hour
T-R	Transformer-Rectifier (Electrostatic Precipitators)
TPY	Tons per year
USEPA.....	United States Environmental Protection Agency
VMT.....	Vehicle Mile Traveled

Pollutants

PM.....	Particulate matter (equivalent to TSP, total suspended particles)
PM ₁₀	Particulate matter ten microns and less in diameter
SO ₂	Sulfur dioxide
SO _x	Sulfur oxides
NO _x	Nitrogen oxides
VOC	Volatile organic compounds
CO.....	Carbon monoxide
HAP.....	Hazardous air pollutants

I. Facility Description and Equipment List

Facility Name: Muscatine Power and Water
 Permit Number: 98-TV-021R3-M001

Facility Description: Electrical Generation (SIC 4911) and Potable Water Plant (SIC 4941)

Equipment List

Emission Point Number	Emission Unit Number	Emission Unit Description	IDNR Construction Permit Number
15	15	Unleaded Gasoline Storage Tank Vent (1,000 Gallons)	N/A
21	20	Rail Hoppers A, B and C	93-A-288-S4
	21	Feeder Belt A	
	22	Feeder Belt B	
	23	Transfer Conveyor Load	
22	20	Rail Hoppers A, B and C	93-A-289-S4
	21	Feeder Belt A	
23A	24A	Transfer Conveyor Discharge / Radial Stacker Load	93-A-290-S3
24	26	Radial Stacker Discharge	13-A-139
	27	Coal Pile	
	27A	Coal Pile Bulldozing	
	342	G-Conveyor Discharge / Truck Loading and Unloading	
300	300	Barge Coal Unloader	13-A-140
301	305	Coal Reclaim / RC-1 Conveyor Load	80-A-193-S3
	306	Reclaim Feeders	
302	301	Barge Unloader Discharge/UC-1 Conveyor Load	13-A-141
310B	310B	Reclaim Feeder -2 Discharge/Reclaim Conveyor-2 Load	00-A-683-S1
311	312A	RC-1/ UC-1 Conveyor Discharge/Live Storage Coal Silo	80-A-194-S3
311B	311B	Reclaim Conv-2 Discharge / LSCS-2 Load	00-A-684-S1
312	319A	Silo Feeder SF-1 through SF-4 / LSC-1 Conveyor Load	93-A-286-S5
	394	ChemMod Additive Transfer to LSC-1 Conveyor	

Emission Point Number	Emission Unit Number	Emission Unit Description	IDNR Construction Permit Number
312B	312B	LSCS-2 Discharge/Silo Feeder-6 Load	00-A-686-S1
313B	313B	Silo Feeder-6 Discharge / Reclaim Conveyor –3 Load	00-A-687-S1
314	317A	Silo Feeder SF-1 through SF-4 / EPC-1 Conveyor Load	80-A-196-S4
	314B	Reclaim Conveyor-3 Discharge / EPC-1 Conveyor Load	
	315B	Pugmill Product Conv. Disch. / EPC-1 Conv. Load	
320	328	Unit 7 Coal Crusher & Bypass Feeder	01-A-193-S2
	329	Unit 8 Coal Crusher Feeders 8A & 8B	
	320-1	EPC-1 Conveyor Discharge	
	322-1	EPC-1 Conveyor & K-Conveyor Discharge / Unit 7 Surge Bins	
322	323-1	Unit 7 Coal Crusher	80-A-006-S3
	326	7 & 8 Crusher & Coal Bypass Chute Discharge / L-Conveyor Load	
	324A/325A	Unit 8A & 8B Coal Crushers	
330	330	Truck Loading & Unloading Track Hopper A-Conveyor	13-A-153
330A			13-A-154
333	330A	Track Hopper Feeders A & B / A-Conveyor Load	80-A-007- S3
	331	A-Conveyor Discharge / C-Conveyor Load	
	333	C-Conveyor Discharge / K-Conveyor Load	
	336	L-Conveyor Discharge / E-Conveyor Load	
341	340	E-Conveyor Discharge / Unit 8 Coal Bunkers 8A, 8B & 8C	00-A-638-S1
	342	G-Conveyor Discharge / Truck Loading & Unloading	
	343	E-Conveyor Discharge / F-Conveyor Load	
	344	F-Conveyor Discharge / Unit 7 Coal Bunkers 7A & 7B	
351	350A	LSC-1 Conveyer Discharge	06-A-650-S3
	350B	PC-1 Conveyor Load	
	350C	SOC-1 Conveyor Load	
360	361	PSC-9 Conveyor	80-A-197-S2
	366	Coal Silo 9A, 9B, 9C, 9D	
370	370	SOC-1 Conveyor Discharge / RSC-1 Conveyor Load	93-A-283-S2
	372	RSC Conveyor-1 Discharge	
391	391	150-Ton Dry Additive Silo	13-A-341

Emission Point Number	Emission Unit Number	Emission Unit Description	IDNR Construction Permit Number
392	392	Day Bin on EPC Conveyor	13-A-342
393	393	Day Bin on LSC-1 Conveyor	13-A-343
40	40	Limestone Hopper Loading	13-A-155
41	41	Limestone Conveying	80-A-202-S2
	42	Limestone Crushing	
	43A	Limestone Storage Silos	
45	45	Limestone Storage Pile	13-A-142
	45A	Limestone Truck Unloading	
60	60	Auxiliary Boiler	13-A-152
70	70	Unit 7 Traveling Grate Stoker Boiler	74-A-175-S3
80	80	Unit 8 Cyclone Boiler	95-A-373-P2
810	CE810A/ CE810B	Filter / Separator Dust Collector DC-6A	00-A-639-S1
813	810	Fly Ash Silo	N/A
814	810	Fly Ash Silo	01-A-218-S1
	811	Dry Fly Ash Truck Loading	
90	90	Unit 9 Dry Bottom Tangential Fired Boiler	80-A-191-P2
912A	912A	Reversing Conveyor A – Discharge / Load	13-A-157
912B	912B	Reversing Conveyor B – Discharge / Load	13-A-158
916B	916A	Load Out Conveyor Discharge / Radial Stacker Conveyor Load	13-A-159
	916B	Radial Stacker Conveyor Discharge	
919	919	Synthetic Gypsum Storage Pile	13-A-146
	919A	Synthetic Gypsum Truck Traffic	
	919B	Synthetic Gypsum Pile Formation	
920/920C	920	Fly Ash Silo Vent Filter Exhaust and Pressure Valve	80-A-201-S1
920A	CE920	Cyclone Separator Dust Collector DC-13B	80-A-200-S1
	924	Dry Fly Ash Temporary Storage – Truck Unloading	
920B	CE920	Cyclone Separator Dust Collector DC-13B	13-A-147
	924	Dry Fly Ash Temporary Storage – Truck Unloading	
924	924	Dry Fly Ash Truck Loadout	13-A-148
860	860	Ash/Slag Storage Pile Wind Erosion	13-A-143
	860B	Ash/Slag Storage Truck Loading	
	860C	Ash/Slag Storage Truck Unloading	
	860D	Ash/Slag Storage Pile Bulldozing	
925	924	Dry Fly Ash Temporary Storage – Truck Unloading	01-A-456-S1
926	924	Dry Fly Ash Truck Loadout	01-A-457-S5

Emission Point Number	Emission Unit Number	Emission Unit Description	IDNR Construction Permit Number
	926A1	10-Ton Fly Ash Hopper	
	926B	150-Ton Fly Ash Silo	
926A2	926A2	Fly Ash Hopper Loading	04-A-617-S1
926A3	926A3	Fly Ash Pile Formation	04-A-618-S1
926A4	926A4	Vehicle Traffic	04-A-619-S1
927	927	Portable Diesel Tank – Breathing Loss & Working Loss (300 Gallons)	01-A-458
7890	7890	Portable Equipment Gasoline Engines (12 Engines)	13-A-150
7892	7892	Portable Equipment Diesel Engine (105 HP)	13-A-151
50	50	Emergency Generator (227 HP)	N/A
820	820	Unit 8 Fire Protection System Diesel Engine (182 BHP)	N/A
930	930	Unit 9 Fire Protection System Diesel Engine Exhaust (182 BHP)	N/A
V168	V168	Portable Emergency Generator (345 kW)	11-A-562-S1
9999	9999	Facility Haul Roads	13-A-160-S1
Levee	Levee	Mississippi River Levee	13-A-161

Insignificant Activities Equipment List

Insignificant Emission Unit Number	Insignificant Emission Unit Description
10	Fuel Oil Storage Tank 9A (100,000 Gallons)
11	Fuel Oil Storage Tank 9B (100,000 Gallons)
16	Used Oil Storage Tank (1,000 gal)
821	Unit 8 Fire Protection System Diesel Storage Tank Vent (300 Gallons)
880A	Drinking Water Treatment, Hydrogen Fluoride
880B	Drinking Water Treatment, Hydrogen Fluoride
880G	Drinking Water Treatment, Chlorine Gas
880H	Drinking Water Treatment, Chlorine Gas
910A	Vacuum Drum A Exhaust
910B	Vacuum Drum B Exhaust
931	Unit 9 Fire Protection System Diesel Storage Tank Vent (300 Gallons)
1900	Unit 9 Waste Water Treatment Building, Chlorine Gas
1901	Unit 9 Waste Water Treatment Building, Chlorine Gas
1910	Unit 9 Waste Water Treatment Building, Sulfur Dioxide
1991	Unit 9 Waste Water Treatment Building, Sulfur Dioxide
2010	Material Handling Used Oil Storage Tank Vent
3014	Parts Washer, Material Handling Maintenance Building
7890a	Portable Equipment – Gasoline Engines – Tank Vent
7892a	Portable Equipment – Diesel Engines – Tank Vents
8030	Parts Washer, Units 7 and 8
9004	Unit 9 Laboratory Fume Hood
9045	Parts Washer, Unit 9
9060	Stick Welding
9061	MIG Welding
9062	TIG Welding
9084	Parts Washer, Flue Gas Desulfurization Building

II. Plant-Wide Conditions

Facility Name: Muscatine Power and Water
Permit Number: 98-TV-021R3-M001

Permit conditions are established in accord with 567 Iowa Administrative Code rule 22.108

Permit Duration

The term of this permit is: Five (5) years.
Commencing on: November 3, 2015
Ending on: November 2, 2020

Amendments, modifications and reopenings of the permit shall be obtained in accordance with 567 Iowa Administrative Code rules 22.110 - 22.114. Permits may be suspended, terminated, or revoked as specified in 567 Iowa Administrative Code Rules 22.115.

Emission Limits

Unless specified otherwise in the Source Specific Conditions, the following limitations and supporting regulations apply to all emission points at this plant:

Opacity (visible emissions): 40% opacity
Authority for Requirement: 567 IAC 23.3(2)"d"

Sulfur Dioxide (SO₂): 500 parts per million by volume
Authority for Requirement: 567 IAC 23.3(3)"e"

Particulate Matter:

No person shall cause or allow the emission of particulate matter from any source in excess of the emission standards specified in this chapter, except as provided in 567 – Chapter 24. For sources constructed, modified or reconstructed after July 21, 1999, the emission of particulate matter from any process shall not exceed an emission standard of 0.1 grain per dry standard cubic foot of exhaust gas, except as provided in 567 – 21.2(455B), 23.1(455B), 23.4(455B) and 567 – Chapter 24.

For sources constructed, modified or reconstructed prior to July 21, 1999, the emission of particulate matter from any process shall not exceed the amount determined from Table I, or amount specified in a permit if based on an emission standard of 0.1 grain per standard cubic foot of exhaust gas or established from standards provided in 23.1(455B) and 23.4(455B).
Authority for Requirement: 567 IAC 23.3(2)"a"

Fugitive Dust: Attainment and Unclassified Areas - A person shall take reasonable precautions to prevent particulate matter from becoming airborne in quantities sufficient to cause a nuisance as defined in Iowa Code section 657.1 when the person allows, causes or permits any materials to be handled, transported or stored or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, with the exception of farming operations or dust generated by ordinary travel on unpaved roads. Ordinary travel includes routine traffic and road maintenance activities such as scarifying, compacting, transporting road maintenance surfacing material, and scraping of the unpaved public road surface. (the preceding sentence is State Only) All persons, with the above exceptions, shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate. The public highway authority shall be responsible for taking corrective action in those cases where said authority has received complaints of or has actual knowledge of dust conditions which require abatement pursuant to this subrule. Reasonable precautions may include, but not be limited to, the following procedures.

1. Use, where practical, of water or chemicals for control of dusts in the demolition of existing buildings or structures, construction operations, the grading of roads or the clearing of land.
2. Application of suitable materials, such as but not limited to asphalt, oil, water or chemicals on unpaved roads, material stockpiles, race tracks and other surfaces which can give rise to airborne dusts.
3. Installation and use of containment or control equipment, to enclose or otherwise limit the emissions resulting from the handling and transfer of dusty materials, such as but not limited to grain, fertilizer or limestone.
4. Covering, at all times when in motion, open-bodied vehicles transporting materials likely to give rise to airborne dusts.
5. Prompt removal of earth or other material from paved streets or to which earth or other material has been transported by trucking or earth-moving equipment, erosion by water or other means.
6. Reducing the speed of vehicles traveling over on-property surfaces as necessary to minimize the generation of airborne dusts.

Authority for Requirement: 567 IAC 23.3(2)"c"

Agreements between IDNR and MP&W:

Muscatine Power and Water (MP&W) shall comply with all requirements of the PM LAER and offsets agreement signed by MP&W on 12/27/79 and signed by Iowa Department of Environmental Quality (IDEQ, the permitting authority at that time) and the revised SO₂ LAER and offsets agreement signed by MP&W on 12/7/82 and signed by IDEQ on 12/13/82 remain in effect.

Authority for Requirement: 567 IAC 22.108(1)

NSPS and NESHAP Applicability

40 CFR 60 Subpart A Requirements

This facility is an affected source and these *General Provisions* apply to the facility. The affected units are EU21, EU22, EU23A, EU90, EU820, EU930, EU300, EU301, EU302, EU310B, EU311, EU311B, EU312, EU312B, EU313B, EU314, EU320, EU322, EU333, EU341, EU351, EU360, and EU370.

See Appendix A for a link to the Standard.

Authority for Requirements: 40 CFR 60 Subpart A
567 IAC 23.1(2)

40 CFR 60 Subpart Da Requirements

This facility is subject to the Standards of Performance for *Electric Utility Steam Generating Units* for which Construction is Commenced after September 18, 1978. The affected unit is EU90.

See Appendix A for a link to the Standard.

Authority for Requirements: 40 CFR 60 Subpart Da
567 IAC 23.1(2) "z"

40 CFR 60 Subpart Y Requirements

This facility is subject to Standards of Performance for *Coal Preparation Plants*. The affected units are EU21, EU22, EU23A, EU300, EU301, EU302, EU310B, EU311, EU311B, EU312, EU312B, EU313B, EU314, EU320, EU322, EU333, EU341, EU351, EU360, and EU370.

See Appendix A for a link to the Standard.

Authority for Requirements: 40 CFR 60 Subpart Y
567 IAC 23.1(2) "v"

40 CFR 63 Subpart A Requirements

This facility is an affected source and these *General Provisions* apply to the facility. The affected units are EU60, EU70, EU80, EU90, EU50, EU820, and EU930.

See Appendix A for a link to the Standard.

Authority for Requirements: 40 CFR 63 Subpart A
567 IAC 23.1(4) "a"

40 CFR 63 Subpart ZZZZ Requirements

This facility is subject to National Emission Standards for Hazardous Air Pollutants for *Stationary Reciprocating Internal Combustion Engines*. The affected units are EU50, EU820, and EU930.

See Appendix for a link to the Standard.

Authority for Requirements: 40 CFR 63 Subpart ZZZZ
567 IAC 23.1(4) "cz"

40 CFR 63 Subpart DDDDD Requirements

This facility is subject to National Emission Standards For Hazardous Air Pollutants for *Industrial, Commercial, And Institutional Boilers And Process Heaters*. The affected units are EU60 and EU70.

See Appendix A for a link to the Standard.

Authority for Requirements: 40 CFR 60 Subpart DDDDD
567 IAC 23.1(4) "dd"

40 CFR 63 Subpart UUUUU Requirements

This facility is subject to National Emission Standards for Hazardous Air Pollutants from *Coal and Oil-fired Electric Utility Steam Generating Units (EGU-MATS)*. The affected units are EU80 and EU90.

See Appendix A for a link to the Standard.

Authority for Requirements: 40 CFR 60 Subpart UUUUU

III. Emission Point-Specific Conditions

Facility Name: Muscatine Power and Water
Permit Number: 98-TV-021R3-M001

Emission Point ID Number: 15

Associated Equipment

Associated Emission Unit ID Number: 15

Emission Unit vented through this Emission Point: 15
Emission Unit Description: Unleaded Gasoline Storage Tank Vent
Raw Material/Fuel: Unleaded Gasoline
Rated Capacity: 1000 Gallons

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

There are no emission limits at this time.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 21 (Vents Internally)

Associated Equipment

Rail Unloading System: Unit 9 components:

Associated Emission Unit ID Numbers: 20, 21, 22, and 23

Emissions Control Equipment ID Number: CE21 for all Emission Units

Emissions Control Equipment Description: Fabric Filter Dust Collector

Emissions Control Equipment ID Number: CE24A for Emission Units 21, 22, and 23

Emissions Control Equipment Description: Dust Suppression System

Emission Units vented through this Emission Point: 20

Emission Unit Description: Rail Hopper A, B and C

Raw Material/Fuel: Coal

Rated Capacity: 1400 tons/hr

Emission Units vented through this Emission Point: 21

Emission Unit Description: Feeder Belt A

Raw Material/Fuel: Coal

Rated Capacity: 700 tons/hr

Emission Units vented through this Emission Point: 22

Emission Unit Description: Feeder Belt B

Raw Material/Fuel: Coal

Rated Capacity: 700 tons/hr

Emission Units vented through this Emission Point: 23

Emission Unit Description: Transfer Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 1400 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 93-A-288-S4

567 IAC 23.1(2)"v"

40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.036 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-288-S4

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 0.86 lb/hr; 0.56 tons/yr

Authority for Requirement: DNR Construction Permit 93-A-288-S4

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.01 gr/dscf; 0.86 lb/hr; 0.56 tons/yr

Authority for Requirement: DNR Construction Permit 93-A-288-S4
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. This emissions unit shall not operate more than 1295 hours in any rolling twelve-month period.
- B. The differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- C. The owner or operator shall develop and maintain an operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-288-S4

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain the following monthly records:
 - i. the number of hours that the emissions unit operated; and
 - ii. the rolling twelve-month total number of hours that the emissions unit operated.
- B. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- C. The owner or operator shall collect and record the pressure drop across the baghouse, in

inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.

- D. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 93-A-288-S4

NSPS and NESHAP Requirements:

This unit is subject to NSPS Subpart Y (§60.250) – Standards of Performance for Coal Preparation Plants and the General Provisions of Subpart A.

Authority for Requirement: DNR Construction Permit 93-A-288-S4

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 25.6

Stack Opening (inches, dia.): 420 in. x 360 in.

Exhaust Temperature (°F): Ambient

Exhaust Flowrate (scfm): 35,693

Discharge Style: Vents Inside

Authority for Requirement: DNR Construction Permit 93-A-288-S4

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may

vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 22 (Vents Internally)

Associated Equipment

Rail Unloading System: Unit 9, consisting of:

Associated Emission Unit ID Numbers: 20 and 21

Emissions Control Equipment ID Number: CE22 for Emission Units 20 and 21

Control Equipment Description: Fabric Filter Dust Collector

Emissions Control Equipment ID Number: CE24A for Emission Unit 21

Emissions Control Equipment Description: Dust Suppression System

Emission Units vented through this Emission Point: 20

Emission Unit Description: Rail Hoppers A, B and C

Raw Material/Fuel: Coal

Rated Capacity: 1400 tons/hr

Emission Units vented through this Emission Point: 21

Emission Unit Description: Feeder Belt A

Raw Material/Fuel: Coal

Rated Capacity: 700 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 93-A-289-S4

567 IAC 23.1(2)"v"

40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.036 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;

as amended by 80 FR 18133, April 3, 2015)

DNR Construction Permit 93-A-289-S4

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 1.24 lb/hr; 0.80 tons/yr

Authority for Requirement: DNR Construction Permit 93-A-289-S4

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.01 gr/dscf; 1.24 lb/hr; 0.80 tons/yr
Authority for Requirement: DNR Construction Permit 93-A-289-S4
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. This emissions unit shall not operate more than 1295 hours in any rolling twelve-month period.
- B. The differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- C. The owner or operator shall develop and maintain an operating and maintenance plan for the baghouse, including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-289-S4

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain the following monthly records:
 - i. the number of hours that the emissions unit operated; and
 - ii. the rolling twelve-month total number of hours that the emissions unit operated.
- B. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- C. The owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- D. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 93-A-289-S4

NSPS and NESHAP Requirements:

This unit is subject to NSPS Subpart Y (§60.250) – Standards of Performance for Coal Preparation Plants and the General Provisions of Subpart A.

Authority for Requirement: DNR Construction Permit 93-A-289-S4

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 25.6

Stack Opening (inches, dia.): 384 in. x 384 in.

Exhaust Temperature (°F): Ambient

Exhaust Flowrate (scfm): 32,661

Discharge Style: Vents Inside

Authority for Requirement: DNR Construction Permit 93-A-289-S4

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required?

Yes No

Facility Maintained Operation & Maintenance Plan Required?

Yes No

Compliance Assurance Monitoring (CAM) Plan Required?

Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 23A (Vents Internally)

Associated Equipment

Rail Unloading System: Unit 9
Associated Emission Unit ID Numbers: 24A
Emissions Control Equipment ID Number: CE24A
Control Equipment Description: Dust Suppression System

Emission Units vented through this Emission Point: 24A
Emission Unit Description: Transfer Conveyor Discharge/Radial Stacker Load
Raw Material/Fuel: Coal
Rated Capacity: 1400 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity
Emission Limit: 20%
Authority for Requirement: DNR Construction Permit 93-A-290-S3
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})
Emission Limit: 0.0725 lb/hr
Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-290-S3

Pollutant: Particulate Matter (PM₁₀)
Emission Limit: 0.60 lb/hr; 0.40 tons/yr
Authority for Requirement: DNR Construction Permit 93-A-290-S3

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.1 gr/dscf; 0.60 lb/hr; 0.40 tons/yr
Authority for Requirement: DNR Construction Permit 93-A-290-S3
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. This emissions unit shall not operate more than 1295 hours in any rolling twelve-month period.
- B. The owner or operator shall develop an operating and maintenance plan for the dust suppression system including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-290-S3

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain the following monthly records:
 - i. the number of hours that the emissions unit operated; and
 - ii. the rolling twelve-month total number of hours that the emissions unit operated.
- B. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the dust suppression system.

Authority for Requirement: DNR Construction Permit 93-A-290-S3

NSPS and NESHAP Requirements:

This unit is subject to NSPS Subpart Y (§60.250) – Standards of Performance for Coal Preparation Plants and the General Provisions of Subpart A.

Authority for Requirement: DNR Construction Permit 93-A-290-S3

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Discharge Style: Vents Inside

Authority for Requirement: DNR Construction Permit 93-A-290-S3

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 24 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 26, 27, 27A and 342

Emission Units vented through this Emission Point: 26
Emission Unit Description: Radial Stacker Discharge
Rated Capacity: 1400 tons/hr

Emission Units vented through this Emission Point: 27
Emission Unit Description: Coal Pile
Rated Capacity: 23 Acres

Emission Units vented through this Emission Point: 27A
Emission Unit Description: Coal Pile Bulldozing
Rated Capacity: Three Bulldozers

Emission Units vented through this Emission Point: 342
Emission Unit Description: G-Conveyor Discharge/Truck Loading and Unloading
Rated Capacity: 50 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity
Emission Limit: 40%
Authority for Requirement: DNR Construction Permit 13-A-139
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5}) for Radial Stack Discharge, EU26
Emission Limit: 0.0403 lb/hr
Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-139

Pollutant: Particulate Matter (PM_{2.5}) for Coal Pile Bulldozing, EU27A
Emission Limit: 0.8877 lb/hr
Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-139

Pollutant: Particulate Matter (PM_{2.5}) for Coal Pile Truck Unloading, EU342

Emission Limit: 0.0014 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-139

Pollutant: Particulate Matter (PM_{2.5}) for Coal Storage Pile, EU27

Emission Limit: For this emissions unit the limits are expressed in the form of a work practice instead of an emission limit. See the Operating Limits section of this permit for the work practice requirements.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-139

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, Coal Pile Bulldozing (EU27A) is limited to operating between 6:00 AM and 12:00 midnight.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, Coal Pile Truck Unloading (EU342) is limited to operating between 8:00 AM and 4:00 PM.
- C. The operation of the Radial Stacker Discharge (EU26) is limited to a maximum of 1295 hours in any rolling 12-month period.
- D. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the ground surface area of the coal pile (EU27) shall not exceed 20 acres (871,200 square feet).

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-139

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when the following emissions units operated: Radial Stacker Discharge (EU26), Coal Pile Bulldozing (EU27A) and Coal Pile Truck Unloading (EU342). This record shall include the following information: date of operation, initial startup time of operation and final end time of operation.
- B. The owner or operator shall maintain the following monthly records on the Radial Stacker Discharge (EU26):
- i. the number of hours that the emissions unit operated; and
 - ii. the rolling 12-month total of the number of hours that the emissions unit operated.
- C. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain records on the silt content and the moisture content of the material handled in these emissions units. The moisture content of the coal handled each month shall be determined from the records kept on the moisture content of the coal burned in the facility's boilers. This shall be done by: 1.) multiplying the moisture content determined daily by the amount of coal burned each day, 2.) summing the daily amount of moisture in the coal for the entire month and 3.) dividing the monthly total of moisture in the coal by the amount of coal burned in the month.
- D. The owner or operator shall maintain records on the surface area of the coal pile. By either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall submit to the Department its methodology for determining the size of the coal pile. After the coal pile is measured using its methodology, the owner or operator shall submit a report to the Department by November 1, 2013 indicating the size of the coal pile. Thereafter, the coal pile shall be measured semi-annually and information on the size of the coal pile shall be submitted with the facility's semi-annual reports.
- E. For the Radial Stacker Discharge (EU26), the PM_{2.5} emission rates established in the Emission Limits section above are based on the maximum capacity of the unit and the following equation and parameters :
- $$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$
- Where:
- E = emission factor in lbs PM_{2.5}/ ton material
 - k = particle size multiplier, 0.053 for PM_{2.5}
 - U = mean wind speed, 7.5 miles per hour, provided by the applicant; and
 - M = minimum material moisture content, 10.35%, provided by applicant
- F. For the Coal Pile Truck Unloading (EU342), the PM_{2.5} emission rates established in the Emission Limits section of this permit are based on the maximum capacity of the unit and the following equation and parameters :
- $$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$
- Where:
- E = emission factor in lbs PM_{2.5}/ ton material
 - k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and
M = minimum material moisture content, 10.35%, provided by applicant
G. For the Coal Pile Bulldozing (EU27A), the PM_{2.5} emission rate established in the Emission Limits section this permit is based on the maximum capacity of the unit and the following equation and parameters :

$$ER = (0.022) 78.4 (s)^{1.2}/(M)^{1.3} \quad (\text{AP-42, Table 11.9-1, bulldozing coal, 7/1998})$$

Where:

ER = emission rate, lbs PM_{2.5} per hour

0.022 = scaling factor for PM_{2.5}

s = material silt content, 7.23% , provided by the applicant; and

M = minimum material moisture content, 10.35%, provided by applicant

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014; as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-139

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 300 (Fugitive)

Associated Equipment

Associated Emission Unit ID Number: 300

Emission Unit vented through this Emission Point: 300
Emission Unit Description: Barge Coal Unloader
Raw Material/Fuel: Coal
Rated Capacity: 1500 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 13-A-140
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.0431 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-140

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, this emissions unit is limited to operating between March 1 and November 30.

- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, this emissions unit is limited to operating between 6:00 AM and 12:00 midnight.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014; as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-140

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain records on the moisture content of the material handled in this emissions unit. The moisture content of the coal handled each month shall be determined from the records kept on the moisture content of the coal burned in the facility's boilers. This shall be done by: 1.) multiplying the moisture content determined daily by the amount of coal burned each day, 2.) summing the daily amount of moisture in the coal for the entire month, and 3.) dividing the monthly total of moisture in the coal by the amount of coal burned in the month.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- C. The PM_{2.5} emission rate established in Emission Limits is based on the maximum capacity of the unit and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10.35 %, provided by applicant

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014; as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-140

NSPS and NESHAP Requirements:

This emissions unit is subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants*. (IAC 23.1(2)"v"). The owner or operator shall notify the Iowa DNR Air Quality Bureau prior to the start up of this equipment. Upon start up, the unit shall then comply with requirements of the Subpart and demonstrate compliance with the opacity limit with a one-time stack test.

Authority for Requirement: DNR Construction Permit 13-A-140

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant - Opacity

1st Stack Test to be Completed by - Within sixty (60) days after achieving maximum production rate and no later than one hundred eighty (180) days after the startup date of the equipment.

Test Method - 40 CFR 60, Appendix A, Method 9

Authority for Requirement - DNR Construction Permit 13-A-140

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test or performance evaluation of a continuous emission monitor. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 301

Associated Equipment

Coal Reclaim System to LSCS-1:

Associated Emission Unit ID Numbers: 305 & 306

Emissions Control Equipment ID Number: CE301

Control Equipment Description: Fabric Filter Dust Collector

Emission Units vented through this Emission Point: 305

Emission Unit Description: Coal Reclaim/RC-1 Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 500 tons/hr

Emission Units vented through this Emission Point: 306

Emission Unit Description: Reclaim Feeders

Raw Material/Fuel: Coal

Rated Capacity: 500 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 80-A-193-S3
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.0167 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-193-S3

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 0.23 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-193-S3

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.1 gr/dscf; 0.23 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-193-S3
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- B. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.
- C. The stack shall be raised to a minimum of 10 feet from the ground by no later than sixty (60) days from the date of the permit issuance. The stack configuration shall be vertical and unobstructed.

Authority for Requirement: DNR Construction Permit 80-A-193-S3

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.
- D. The owner or operator shall submit a notification to the Iowa DNR, Air Quality Bureau when the modification to the stack height has been completed.

Authority for Requirement: DNR Construction Permit 80-A-193-S3

NSPS and NESHAP Requirements:

These emissions units are subject to the requirements of the New Source Performance Standard (NSPS) for Coal Preparation Plants (40 CFR 60 Subpart Y, 567 IAC 23.1(2)"v") and General Provisions: Subpart A.

Authority for Requirement: DNR Construction Permit 80-A-193-S3

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 10 (minimum)

Stack Opening (inches, dia.): 9.625 x 10.625

Exhaust Temperature (°F): Ambient

Exhaust Flow Rate (scfm): 3,900

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 80-A-193-S3

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant – Particulate Matter (PM)
Stack Test to be Completed by – November 2, 2017
Test Method - 40 CFR 60, Appendix A, Method 5
40 CFR 51, Appendix M, Method 202
Authority for Requirement – 567 IAC 22.108(3)

The owner of this equipment or the owner’s authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 302 (Fugitive)

Associated Equipment

Associated Emission Unit ID Number: 301

Emission Unit vented through this Emission Point: 301
Emission Unit Description: Barge Unloader Feeder Discharge/UC-1 Conveyor Load
Raw Material/Fuel: Coal
Rated Capacity: 1500 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.0431 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-141

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 0.285 lb/hr

Authority for Requirement: DNR Construction Permit 13-A-141

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, this emissions unit is limited to operating between March 1 and November 30.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, this emissions unit is limited to operating between 6:00 AM and 12:00 midnight.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-141

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain records on the moisture content of the material handled in this emissions unit. The moisture content of the coal handled each month shall be determined from the records kept on the moisture content of the coal burned in the facility's boilers. This shall be done by: 1.) multiplying the moisture content determined daily by the amount of coal burned each day, 2.) summing the daily amount of moisture in the coal for the entire month and 3.) dividing the monthly total of moisture in the coal by the amount of coal burned in the month.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.

- C. The PM_{2.5} emission rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10.35 %, provided by applicant

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-141

NSPS and NESHAP Requirements:

This emissions unit is subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants*. (IAC 23.1(2)"v"). The owner or operator shall notify the Iowa DNR Air Quality Bureau prior to the start up of this equipment. Upon start up, the unit shall then comply with requirements of the Subpart and demonstrate compliance with the opacity limit using one-time stack testing.

Authority for Requirement: DNR Construction Permit 13-A-141

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)
At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant - Opacity

1st Stack Test to be Completed by - Within sixty (60) days after achieving maximum production rate and no later than one hundred eighty (180) days after the startup date of the equipment.

Test Method - 40 CFR 60, Appendix A, Method 9

Authority for Requirement - DNR Construction Permit 13-A-141

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Agency Approved Operation & Maintenance Plan Required?

Yes No

Facility Maintained Operation & Maintenance Plan Required?

Yes No

Compliance Assurance Monitoring (CAM) Plan Required?

Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 310B (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 310B

Emission Units vented through this Emission Point: 310B

Emission Unit Description: Reclaim Feeder -2 Discharge/Reclaim Conveyor -2 Load

Raw Material/Fuel: Coal

Rated Capacity: 750 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 00-A-683-S1
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.022 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-683-S1

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, this emissions unit is limited to operating between 6:00 AM and 10:00 PM.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-683-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain records on the moisture content of the material handled in this emissions unit. The moisture content of the coal handled each month shall be determined from the records kept on the moisture content of the coal burned in the facility's boilers. This shall be done by: 1.) multiplying the moisture content determined daily by the amount of coal burned each day, 2.) summing the daily amount of moisture in the coal for the entire month and 3.) dividing the monthly total of moisture in the coal by the amount of coal burned in the month.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- C. The PM_{2.5} emission rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10.35 %, provided by applicant

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-683-S1

NSPS Requirements:

This emissions unit is subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants*. (IAC 23.1(2)"v") and *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 00-A-683-S1

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 311

Associated Equipment

Associated Emission Unit ID Numbers: 312A
Emissions Control Equipment ID Number: CE311
Control Equipment Description: AAF Baghouse

Emission Units vented through this Emission Point: 312A
Emission Unit Description: RC-1/ UC-1 Conveyor Discharge/Live Storage Coal Silo
Raw Material/Fuel: Coal
Rated Capacity: 500 tons/hr (RC-1), 1500 tons/hr (UC-1)

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 20 %

Authority for Requirement: DNR Construction Permit 80-A-194-S3
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.103 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-194-S3

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 0.69 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-194-S3

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.1 gr/dscf; 0.69 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-194-S3
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the equipment covered by this permit (EU312A) is limited to operating between 6:00 AM and 10:00 PM.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- C. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.
- D. The Barge Coal Unloading System (EU300) shall not be used to convey coal unless the following conditions are met:
 - i. Muscatine Power and Water shall notify the Department within 90 days in advance of the anticipated Barge Coal Unloading (UC-1) to Live Storage Coal Silo (LSCS-1). The Department shall determine if the proposed start-up of Barge Coal Unloading System is an emissions increase for the purposes of Prevention Significant of Deterioration (PSD).
 - ii. Muscatine Power and Water shall notify the Department of its intent to demonstrate compliance at least 30 days in advance of planned testing. Muscatine Power and Water shall demonstrate compliance with particulate matter and opacity limitations specified in condition 10 at a process capacity at or near the permitted capacity of 1,500 tons of coal per hour associated with Barge Coal Unloading System within 60 days of achieving maximum production or within 180 days after start-up.
 - iii. This Condition D. shall not apply when Barge Coal Unloading System operates for any purpose, such as maintenance, without conveying coal.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
 as amended by 80 FR 18133, April 3, 2015)
 DNR Construction Permit 80-A-194-S3

Reporting and Record Keeping:

All records as required by this permit shall be kept on-site for a minimum of five (5) years and shall be available for inspection by the DNR. Records shall be legible and maintained in an orderly manner.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when the equipment covered by this permit operates. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- C. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall collect and record the pressure

drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.

- D. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 80-A-194-S3

NSPS and NESHAP Requirements:

These emissions units are subject to the requirements of the New Source Performance Standard (NSPS) for *Coal Preparation Plants* (40 CFR 60 Subpart Y, 567 IAC 23.1(2)"v") and *General Provisions* Subpart A.

Authority for Requirement: DNR Construction Permit 80-A-194-S3

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c) At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 157.5

Stack Opening (inches, dia.): 24

Exhaust Temperature (°F): Ambient

Exhaust Flowrate (scfm): 6,200

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 80-A-194-S3

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may

vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing

Pollutant – Opacity

Stack Test to be Completed by – When at a process capacity or near the permitted capacity of 1,500 tons of coal per hour associated with Barge Coal Unloading System within 60 days of achieving maximum production or within 180 days after start-up.

Test Method - Iowa Compliance Sampling Manual Method 5

Authority for Requirement – DNR Construction Permit 80-A-194-S3

Pollutant – Particulate Matter (PM)

Stack Test to be Completed by – When at a process capacity or near the permitted capacity of 1,500 tons of coal per hour associated with Barge Coal Unloading System within 60 days of achieving maximum production or within 180 days after start-up.

Test Method - 40 CFR 60, Appendix A, Method 5

40 CFR 51, Appendix M, Method 202

Authority for Requirement – Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;

as amended by 80 FR 18133, April 3, 2015)

DNR Construction Permit 80-A-194-S3

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Opacity Monitoring

The facility shall check the opacity weekly during a period when the emission unit on this emission point is at or near full capacity and record the reading. Maintain a written record of the observation and any action resulting from the observation for a minimum of five years.

The emission point shall be observed to ensure that no visible emissions occur during the material handling operation of the unit. If visible emissions are observed corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If corrective action does not return the observation to no visible emissions, then a Method 9 observation will be required.

If an opacity >20% is observed, this would be a violation and corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If weather conditions prevent the observer from conducting an opacity observation, the observer shall note such conditions on the data observation sheet. At least three attempts shall be made to retake opacity readings at approximately 2-hour intervals throughout the day. If all observation attempts for a week have been unsuccessful due to weather, an observation shall be made the next operating day where weather permits.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 311B (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 311B

Emission Units vented through this Emission Point: 311B

Emission Unit Description: Reclaim Conveyor-2 Discharge/Live Storage Coal Silo-2 Load

Raw Material/Fuel: Coal

Rated Capacity: 750 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 00-A-684-S1
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.0218 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-684-S1

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, this emissions unit is limited to operating between 6:00 AM and 10:00 PM.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-684-S1

Reporting and Record Keeping:

All records as required by this permit shall be kept on-site for a minimum of five (5) years and shall be available for inspection by the DNR. Records shall be legible and maintained in an orderly manner.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain records on the moisture content of the material handled in this emissions unit. The moisture content of the coal handled each month shall be determined from the records kept on the moisture content of the coal burned in the facility's boilers. This shall be done by: 1.) multiplying the moisture content determined daily by the amount of coal burned each day, 2.) summing the daily amount of moisture in the coal for the entire month and 3.) dividing the monthly total of moisture in the coal by the amount of coal burned in the month.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- C. The PM_{2.5} emission rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10.35 %, provided by applicant

The emission rate also includes potential emissions from a closed manway hatch. Emissions from the closed hatch are estimated at 1% of the emissions due to material handling.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-684-S1

NSPS and NESHAP Requirements:

This emissions unit is subject to the requirements of 40 CFR Part 60, Subpart Y, "Standards of Performance for *Coal Preparation Plants*." (IAC 23.1(2)"v") and the *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 00-A-684-S1

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 312 (Vents Internally)

Associated Equipment

Associated Emission Unit ID Numbers: 319A, 394
Emissions Control Equipment ID Number: CE312
Control Equipment Description: Fabric Filter Baghouse

Emission Units vented through this Emission Point: 319A, 394
Emission Unit Description: Silo Feeder SF-1 through SF-4, LSC-1 Conveyor Load, ChemMod
Additive Transfer to LSC-1 Conveyor
Raw Material/Fuel: Coal, Dry Additive
Rated Capacity: 500 tons/hr (LSC-Conveyor); 2 tons/hr (ChemMod Transfer)

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity
Emission Limit: 20%
Authority for Requirement: DNR Construction Permit 93-A-286-S5
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})
Emission Limit: 0.00030 lb/hr
Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-286-S5

Pollutant: Particulate Matter (PM₁₀)
Emission Limit: 0.77 lb/hr, 1.54 tons/yr
Authority for Requirement: DNR Construction Permit 93-A-286-S5

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.77 lb/hr, 1.54 tons/yr, 0.01 gr/dscf
Authority for Requirement: DNR Construction Permit 93-A-286-S5
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. This emissions unit shall not operate more than 4000 hours in any rolling twelve-month period.
- B. The differential pressure drop across the baghouse shall be maintained between 1 and 10 inches water column while the equipment is in operation.
- C. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.
- D. The transfer of the dry ChemMod additive shall be done in an enclosed conveyor. Dust curtains or other types of enclosures shall be used to minimize the emissions of particulate emissions.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-286-S5

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain the following monthly records:
 - i. the number of hours that the emissions unit operated; and
 - ii. the rolling twelve-month total number of hours that the emissions unit operated.
- B. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- C. The owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- D. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-286-S5

NSPS and NESHAP Requirements:

This unit is subject to NSPS Subpart Y (§60.250) – Standards of Performance for *Coal Preparation Plants* and the *General Provisions* of Subpart A.

Authority for Requirement: DNR Construction Permit 93-A-286-S5

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 5

Stack Opening (inches, dia.): 96 x 96

Exhaust Temperature (°F): Ambient

Exhaust Flow Rate (scfm): 9,000

Discharge Style: Vent Inside

Authority for Requirement: DNR Construction Permit 93-A-286-S5

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 312B (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 312B

Emission Units vented through this Emission Point: 312B
Emission Unit Description: LSCS-2 Discharge/Silo Feeder-6 Load
Raw Material/Fuel: Coal
Rated Capacity: 200 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 00-A-686-S1
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM2.5)

Emission Limit: 0.0058 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-686-S1

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Reporting and Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit

issuance, whichever comes later, the owner or operator shall maintain records on the moisture content of the material handled in this emissions unit. The moisture content of the coal handled each month shall be determined from the records kept on the moisture content of the coal burned in the facility's boilers. This shall be done by: 1.) multiplying the moisture content determined daily by the amount of coal burned each day, 2.) summing the daily amount of moisture in the coal for the entire month and 3.) dividing the monthly total of moisture in the coal by the amount of coal burned in the month.

- B. The PM_{2.5} emission rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10.35 %, provided by applicant

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-686-S1

NSPS and NESHAP Requirements:

This emissions unit is subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants*. (IAC 23.1(2)"v") and the *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 00-A-686-S1

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 313B (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 313B

Emission Units vented through this Emission Point: 313B

Emission Unit Description: Silo Feeder-6 Discharge/Reclaim Conveyor –3 Load

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 00-A-687-S1
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.0058 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-687-S1

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Reporting and Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit

issuance, whichever comes later, the owner or operator shall maintain records on the moisture content of the material handled in this emissions unit. The moisture content of the coal handled each month shall be determined from the records kept on the moisture content of the coal burned in the facility's boilers. This shall be done by: 1.) multiplying the moisture content determined daily by the amount of coal burned each day, 2.) summing the daily amount of moisture in the coal for the entire month and 3.) dividing the monthly total of moisture in the coal by the amount of coal burned in the month.

- B. The PM_{2.5} emission rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10.35 %, provided by applicant

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-687-S1

NSPS and NESHAP Requirements:

This emissions unit is subject to the requirements of 40 CFR Part 60, Subpart Y - Standards of Performance for *Coal Preparation Plants*. (IAC 23.1(2)"v") and the *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 00-A-687-S1

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 314

Associated Equipment

Associated Emission Unit ID Numbers: 317A, 314B, 315B

Emissions Control Equipment ID Number: CE314

Control Equipment Description: Fabric Filter Baghouse

Emission Units vented through this Emission Point: 317A

Emission Unit Description: Silo Feeder SF-1 through SF-5 / EPC-1 Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 200 Tons/hr

Emission Units vented through this Emission Point: 314B

Emission Unit Description: Reclaim Conveyor-3 Discharge / EPC-1 Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 200 Tons/hr

Emission Units vented through this Emission Point: 315B

Emission Unit Description: Pugmill Product Conv. Disch./EPC-1 Conv. Load

Raw Material/Fuel: Coal

Rated Capacity: 200 Tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 80-A-196-S4
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.0155 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-196-S4

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 0.34 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-196-S4

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.34 lb/hr, 0.01 gr/dscf⁽¹⁾

Authority for Requirement: DNR Construction Permit 80-A-196-S4
567 IAC 23.3(2)"a"

- ⁽¹⁾ Pursuant to the Federal PSD permit issued on January 24, 1980 for boiler #9 and the LAER agreement between the Department and Muscatine Power and Water, signed on December 29, 1979, all coal handling systems associated with boiler #9 are subject to a 0.01 gr/dscf standard for particulate matter.

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- B. The owner or operator shall develop an operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 80-A-196-S4

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. The owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 80-A-196-S4

NSPS and NESHAP Requirements:

This unit is subject to NSPS Subpart Y (§60.250) – Standards of Performance for *Coal Preparation Plants* and the *General Provisions* of Subpart A.

Authority for Requirement: DNR Construction Permit 80-A-196-S4

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 27.5

Stack Opening (inches, dia.): 24

Exhaust Temperature (°F): Ambient

Exhaust Flow Rate (scfm): 3,933

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 80-A-196-S4

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant - PM
Stack Test to be Completed by – November 2, 2017
Test Method – 40 CFR 60, Appendix A, Method 5
40 CFR 51, Appendix M, Method 202
Authority for Requirement – 567 IAC 22.108(3)

The owner of this equipment or the owner’s authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Opacity Monitoring

The facility shall check the opacity weekly during a period when the emission unit on this emission point is at or near full capacity and record the reading. Maintain a written record of the observation and any action resulting from the observation for a minimum of five years.

The emission point shall be observed to ensure that no visible emissions occur during the material handling operation of the unit. If visible emissions are observed corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If corrective action does not return the observation to no visible emissions, then a Method 9 observation will be required.

If an opacity > 20% is observed, this would be a violation and corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If weather conditions prevent the observer from conducting an opacity observation, the observer shall note such conditions on the data observation sheet. At least three attempts shall be made to retake opacity readings at approximately 2-hour intervals throughout the day. If all observation attempts for a week have been unsuccessful due to weather, an observation shall be made the next operating day where weather permits.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 320

Associated Equipment

Associated Emission Unit ID Numbers: 320-1, 322-1, 328 and 329

Emissions Control Equipment ID Number: CE320

Control Equipment Description: Fabric Filter Baghouse

Emission Units vented through this Emission Point: 320-1

Emission Unit Description: EPC-1 Conveyor & K-Conveyor Discharge/Unit 8 Surge Bins

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 322-1

Emission Unit Description: EPC-1 Conveyor & K-Conveyor Discharge/Unit 7 Surge Bins

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 328

Emission Unit Description: Unit 7 Coal Crusher & Bypass Feeder

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 329

Emission Unit Description: Unit 8 Coal Crusher Feeders 8A & 8B

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 01-A-193-S2
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.0823 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 01-A-193-S2

Pollutant: Particulate Matter (PM₁₀)
Emission Limit(s): 0.640 lb/hr
Authority for Requirement: DNR Construction Permit 01-A-193-S2

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.01 gr/dscf
Authority for Requirement: DNR Construction Permit 01-A-193-S2

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- B. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.
- C. The stack shall be raised to a minimum of 24 feet from the ground by no later than sixty (60) days from the date of the permit issuance. The stack configuration shall be vertical and unobstructed.

Authority for Requirement: DNR Construction Permit 01-A-193-S2

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. The owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.
- D. The owner or operator shall submit a notification to the Iowa DNR, Air Quality Bureau when the modification to the stack height has been completed.

Authority for Requirement: DNR Construction Permit 01-A-193-S2

NSPS and NESHAP Requirements:

These emission units are subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants*. (IAC 23.1(2)"v") and *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 01-A-193-S2

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

The emission point shall conform to the specifications listed below.

Stack Height (ft, from the ground): 24

Stack Opening (inches, dia.): 24 x 24

Stack Exhaust Flow Rate (scfm): 7,500

Stack Temperature (°F): Ambient

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 01-A-193-S2

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

- Pollutant - PM
- Stack Test to be Completed by – November 2, 2017
- Test Method - 40 CFR 60, Appendix A, Method 5
40 CFR 51, Appendix M, Method 202
- Authority for Requirement – 567 IAC 22.108(3)

The owner of this equipment or the owner’s authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Opacity Monitoring

The facility shall check the opacity weekly during a period when the emission unit on this emission point is at or near full capacity and record the reading. Maintain a written record of the observation and any action resulting from the observation for a minimum of five years.

The emission point shall be observed to ensure that no visible emissions occur during the material handling operation of the unit. If visible emissions are observed corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If corrective action does not return the observation to no visible emissions, then a Method 9 observation will be required.

If an opacity > 20% is observed, this would be a violation and corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If weather conditions prevent the observer from conducting an opacity observation, the observer shall note such conditions on the data observation sheet. At least three attempts shall be made to retake opacity readings at approximately 2-hour intervals throughout the day. If all observation attempts for a week have been unsuccessful due to weather, an observation shall be made the next operating day where weather permits.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 322

Associated Equipment

Associated Emission Unit ID Numbers: 323-1, 324A/325A, and 326

Emissions Control Equipment ID Number: CE322

Control Equipment Description: Fabric Filter Baghouse

Emission Units vented through this Emission Point: 323-1

Emission Units Description: Unit 7 Coal Crusher/Lump Breaker

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 324A/325A

Emission Units Description: Unit 8A & 8B Coal Crushers

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 326

Emission Units Description: 7 & 8 Crusher & Coal Bypass Chute Discharge/L-Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 80-A-006-S3
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.028 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-006-S3

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 0.719 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-006-S3

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.01 gr/dscf

Authority for Requirement: DNR Construction Permit 80-A-006-S3

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- B. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 80-A-006-S3

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 80-A-006-S3

NSPS and NESHAP Requirements:

These emission units are subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants*. (IAC 23.1(2)"v") and *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 80-A-006-S3

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

The emission point shall conform to the specifications listed below.

Stack Height (feet from the ground): 102

Stack Diameter (inches, dia.): 24

Stack Exhaust Flow Rate (scfm): 8,400

Stack Temperature (°F): 70

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 80-A-006-S3

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant - PM

Stack Test to be Completed by – November 2, 2017

Test Method - 40 CFR 60, Appendix A, Method 5

40 CFR 51, Appendix M, Method 202

Authority for Requirement – 567 IAC 22.108(3)

Opacity Monitoring

The facility shall check the opacity weekly during a period when the emission unit on this emission point is at or near full capacity and record the reading. Maintain a written record of the observation and any action resulting from the observation for a minimum of five years.

The emission point shall be observed to ensure that no visible emissions occur during the material handling operation of the unit. If visible emissions are observed corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If corrective action does not return the observation to no visible emissions, then a Method 9 observation will be required.

If an opacity > 20% is observed, this would be a violation and corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If weather conditions prevent the observer from conducting an opacity observation, the observer shall note such conditions on the data observation sheet. At least three attempts shall be made to retake opacity readings at approximately 2-hour intervals throughout the day. If all observation attempts for a week have been unsuccessful due to weather, an observation shall be made the next operating day where weather permits.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 330 and 330A (Fugitives)

Associated Equipment

Associated Emission Unit ID Number: 330

Emission Units vented through this Emission Point: 330

Emission Unit Description: Truck Unloading Track Hopper A-Conveyor

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40%

Authority for Requirement: DNR Construction Permits 13-A-153, 13-A-154
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.0058 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permits 13-A-153, 13-A-154

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the equipment covered by this permit (EU330) is limited to operating between 8:00 AM and 4:00 PM.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permits 13-A-153, 13-A-154

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when the equipment covered by this permit operates. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain records on the moisture content of the material handled in this emissions unit. The moisture content of the coal handled each month shall be determined from the records kept on the moisture content of the coal burned in the facility's boilers. This shall be done by: 1.) multiplying the moisture content determined daily by the amount of coal burned each day, 2.) summing the daily amount of moisture in the coal for the entire month and 3.) dividing the monthly total of moisture in the coal by the amount of coal burned in the month.
- C. The PM_{2.5} emission rate established in Permit Condition 10 is based on the maximum capacity of the unit and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10.35%, provided by the applicant.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permits 13-A-153, 13-A-154

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 333

Associated Equipment

Associated Emission Unit ID Numbers: 330A, 331, 333, and 336

Emissions Control Equipment ID Number: CE333

Control Equipment Description: Fabric Filter Baghouse

Emission Units vented through this Emission Point: 330A

Emission Unit Description: Track Hopper Feeders A & B/A-Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 331

Emission Unit Description: A-Conveyor Discharge/C-Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 333

Emission Unit Description: C-Conveyor Discharge/K-Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 336

Emission Unit Description: L- Conveyor Discharge/E- Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 80-A-007-S3
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.061 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-007-S3

Pollutant: Particulate Matter (PM₁₀)
Emission Limit(s): 0.814 lb/hr
Authority for Requirement: DNR Construction Permit 80-A-007-S3

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.01 gr/dscf⁽¹⁾
Authority for Requirement: DNR Construction Permit 80-A-007-S3

- ⁽¹⁾ Pursuant to the Federal PSD permit issued on January 24, 1980 for boiler #9 and the LAER agreement between the Department and Muscatine Power and Water, signed on December 29, 1979, all coal handling systems associated with boiler #9 are subject to 0.01 gr/dscf standard for particulate matter.

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- B. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 80-A-007-S3

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 80-A-007-S3

NSPS and NESHAP Requirements:

These emission units are subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants* (IAC 23.1(2)"v") and *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 80-A-007-S3

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

The emission point shall conform to the specifications listed below.

Stack Height (feet from the ground): 49.5

Stack Diameter (inches): 24

Stack Exhaust Flow Rate (scfm): 9,500

Stack Temperature (°F): Ambient

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 80-A-007-S3

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

- Pollutant - PM
- Stack Test to be Completed by – November 2, 2017
- Test Method - 40 CFR 60, Appendix A, Method 5
40 CFR 51, Appendix M, Method 202
- Authority for Requirement – 567 IAC 22.108(3)

The owner of this equipment or the owner’s authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Opacity Monitoring:

The facility shall check the opacity weekly during a period when the emission unit on this emission point is at or near full capacity and record the reading. Maintain a written record of the observation and any action resulting from the observation for a minimum of five years.

The emission point shall be observed to ensure that no visible emissions occur during the material handling operation of the unit. If visible emissions are observed corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If corrective action does not return the observation to no visible emissions, then a Method 9 observation will be required.

If an opacity > 20% is observed, this would be a violation and corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If weather conditions prevent the observer from conducting an opacity observation, the observer shall note such conditions on the data observation sheet. At least three attempts shall be made to retake opacity readings at approximately 2-hour intervals throughout the day. If all observation attempts for a week have been unsuccessful due to weather, an observation shall be made the next operating day where weather permits.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 341

Associated Equipment

Associated Emission Unit ID Numbers: 340, 342, 343, and 344

Emissions Control Equipment ID Number: CE341

Control Equipment Description: Fabric Filter Baghouse

Emission Units vented through this Emission Point: 340

Emission Unit Description: E-Conveyor Discharge/Unit 8 Coal Bunkers 8A, 8B & 8C

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 342

Emission Unit Description: G-Conveyor Discharge/Truck Loading & Unloading

Raw Material/Fuel: Coal

Rated Capacity: 50 tons/hr

Emission Units vented through this Emission Point: 343

Emission Unit Description: E-Conveyor Discharge/F-Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Point: 344

Emission Unit Description: F-Conv. Discharge/Unit 7 Coal Bunkers 7A & 7B

Raw Material/Fuel: Coal

Rated Capacity: 200 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 00-A-638-S1
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.061 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-638-S1

Pollutant: Particulate Matter (PM₁₀)
Emission Limit(s): 0.646 lb/hr
Authority for Requirement: DNR Construction Permit 00-A-638-S1

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.01 gr/dscf
Authority for Requirement: DNR Construction Permit 00-A-638-S1

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- B. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 00-A-638-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. The owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 00-A-638-S1

NSPS and NESHAP Requirements:

These emission units are subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants* (IAC 23.1(2)"v") and *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 00-A-638

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

The emission point shall conform to the specifications listed below.

Stack Height (feet from the ground): 130.25

Stack Diameter (inches): 22

Stack Exhaust Flow Rate (scfm): 8,357

Stack Temperature (°F): 82

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 00-A-638-S1

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant - PM

Stack Test to be Completed by – November 2, 2017

Test Method - 40 CFR 60, Appendix A, Method 5

40 CFR 51, Appendix M, Method 202

Authority for Requirement – 567 IAC 22.108(3)

The owner of this equipment or the owner’s authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Opacity Monitoring

The facility shall check the opacity weekly during a period when the emission unit on this emission point is at or near full capacity and record the reading. Maintain a written record of the observation and any action resulting from the observation for a minimum of five years.

The emission point shall be observed to ensure that no visible emissions occur during the material handling operation of the unit. If visible emissions are observed corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If corrective action does not return the observation to no visible emissions, then a Method 9 observation will be required.

If an opacity > 20% is observed, this would be a violation and corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If weather conditions prevent the observer from conducting an opacity observation, the observer shall note such conditions on the data observation sheet. At least three attempts shall be made to retake opacity readings at approximately 2-hour intervals throughout the day. If all observation attempts for a week have been unsuccessful due to weather, an observation shall be made the next operating day where weather permits.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement – 567 IAC 22.108(3)

Emission Point ID Number: 351 (Vents Internally)

Associated Equipment

Associated Emission Unit ID Numbers: 350A, 350B, and 350C

Emissions Control Equipment ID Number: CE351

Control Equipment Description: Fabric Filter Baghouse

Emission Units vented through this Emission Point: 350A

Emission Unit Description: LSC-1 Conveyor Discharge

Raw Material/Fuel: Coal

Rated Capacity: 500 tons/hr

Emission Units vented through this Emission Point: 350B

Emission Unit Description: PC-1 Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 500 tons/hr

Emission Units vented through this Emission Point: 350C

Emission Unit Description: SOC-1 Conveyor Load

Raw Material/Fuel: Coal

Rated Capacity: 500 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 06-A-650-S3

567 IAC 23.1(2)"v"

40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.0341 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;

as amended by 80 FR 18133, April 3, 2015)

DNR Construction Permit 06-A-650-S3

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 0.82 lb/hr

Authority for Requirement: DNR Construction Permit 06-A-650-S3

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.82 lb/hr, 0.01 gr/dscf ⁽¹⁾

Authority for Requirement DNR Construction Permit 06-A-650-S3

⁽¹⁾ Pursuant to the Federal PSD permit issued on January 24, 1980 for boiler #9 and the LAER agreement between the Department and Muscatine Power and Water, signed on December 29, 1979, all coal handling systems associated with boiler #9 are subject to a 0.01 gr/dscf standard for particulate matter.

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- B. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 06-A-650-S3

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. The owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 06-A-650-S3

NSPS and NESHAP Requirements:

These emission units are subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants* (IAC 23.1(2)"v") and *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 06-A-650-S3

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

The following equipment is associated with this emission point:
This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 3.3

Stack Opening (inches, dia.): 21

Exhaust Temperature (°F): 70

Discharge Style: Vents Indoors

Exhaust Flowrate (scfm): 9,273

Authority for Requirement: DNR Construction Permit 06-A-650-S3

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Opacity Monitoring

The facility shall check the opacity weekly during a period when the emission unit on this emission point is at or near full capacity and record the reading. Maintain a written record of the observation and any action resulting from the observation for a minimum of five years.

The emission point shall be observed to ensure that no visible emissions occur during the material handling operation of the unit. If visible emissions are observed corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If corrective action does not return the observation to no visible emissions, then a Method 9 observation will be required.

If an opacity > 20% is observed, this would be a violation and corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If weather conditions prevent the observer from conducting an opacity observation, the observer shall note such conditions on the data observation sheet. At least three attempts shall be made to retake opacity readings at approximately 2-hour intervals throughout the day. If all observation attempts for a week have been unsuccessful due to weather, an observation shall be made the next operating day where weather permits.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 360

Associated Equipment

Associated Emission Unit ID Numbers: 361 and 366
Emissions Control Equipment ID Number: CE360
Control Equipment Description: Fabric Filter Baghouse

Emission Unit vented through this Emission Point: 361
Emission Unit Description: PSC-9 Conveyor
Raw Material/Fuel: Coal
Rated Capacity: 500 Tons/hr

Emission Unit vented through this Emission Point: 366
Emission Unit Description: Coal Silos 9A, 9B, 9C, and 9D
Raw Material/Fuel: Coal
Rated Capacity: 500 Tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 20%

Authority for Requirement: DNR Construction Permit 80-A-197-S2
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.034 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-197-S2

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 0.390 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-197-S2

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.01 gr/dscf ⁽¹⁾

Authority for Requirement: DNR Construction Permit 80-A-197-S2

⁽¹⁾ Pursuant to the Federal PSD permit issued on January 24, 1980 for boiler #9 and the LAER agreement between the Department and Muscatine Power and Water, signed on December 29, 1979, all coal handling systems associated with boiler #9 are subject to 0.01 gr/dscf standard for particulate matter.

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- B. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 80-A-197-S2

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. The owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 80-A-197-S2

NSPS and NESHAP Requirements:

These emission units are subject to the requirements of 40 CFR Part 60, Subpart Y, Standards of Performance for *Coal Preparation Plants* (IAC 23.1(2)"v") and *General Provisions*, Subpart A.

Authority for Requirement: DNR Construction Permit 80-A-197-S2

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is

not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 140.5

Stack Opening (inches, dia.): 60 x 84

Exhaust Temperature (°F): Ambient

Exhaust Flow Rate (scfm): 4,600

Discharge Style: Horizontal

Authority for Requirement: DNR Construction Permit 80-A-197-S2

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant - PM

Stack Test to be Completed by – November 2, 2017

Test Method - 40 CFR 60, Appendix A, Method 5

40 CFR 51, Appendix M, Method 202

Authority for Requirement – 567 IAC 22.108(3)

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Opacity Monitoring

The facility shall check the opacity weekly during a period when the emission unit on this emission point is at or near full capacity and record the reading. Maintain a written record of the observation and any action resulting from the observation for a minimum of five years.

The emission point shall be observed to ensure that no visible emissions occur during the material handling operation of the unit. If visible emissions are observed corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If corrective action does not return the observation to no visible emissions, then a Method 9 observation will be required.

If an opacity > 20% is observed, this would be a violation and corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If weather conditions prevent the observer from conducting an opacity observation, the observer shall note such conditions on the data observation sheet. At least three attempts shall be made to retake opacity readings at approximately 2-hour intervals throughout the day. If all observation attempts for a week have been unsuccessful due to weather, an observation shall be made the next operating day where weather permits.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Emission Point ID Number: 370 (Vents Internally)

Associated Equipment

Associated Emission Unit ID Numbers: 370 and 372
Emissions Control Equipment ID Number: CE370
Control Equipment Description: Fabric Filter Baghouse

Emission Unit vented through this Emission Point: 370
Emission Unit Description: SOC-1 Conveyor Discharge/RSC-1 Conveyor Load
Raw Material/Fuel: Coal
Rated Capacity: 500 tons/hr

Emission Unit vented through this Emission Point: 372
Emission Unit Description: RSC Conveyor-1 Discharge
Raw Material/Fuel: Coal
Rated Capacity: 500 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity
Emission Limit: 20%
Authority for Requirement: DNR Construction Permit 93-A-283-S2
567 IAC 23.1(2)"v"
40 CFR 60 Subpart Y

Pollutant: Particulate Matter (PM_{2.5})
Emission Limit: 0.00029 lb/hr
Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-283-S2

Pollutant: Particulate Matter (PM₁₀)
Emission Limit: 0.54 lb/hr, 1.08 tons/yr
Authority for Requirement: DNR Construction Permit 93-A-283-S2

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.54 lb/hr, 1.08 tons/yr, 0.01 gr/dscf⁽¹⁾
Authority for Requirement: DNR Construction Permit 93-A-283-S2
567 IAC 23.3(2)"a"

⁽¹⁾ Pursuant to the Federal PSD permit issued on January 24, 1980 for boiler #9 and the LAER agreement between the Department and Muscatine Power and Water, signed on December 29, 1979,

all coal handling systems associated with boiler #9 are subject to a 0.01 gr/dscf standard for particulate matter.

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. This emissions unit shall not operate more than 4000 hours in any rolling twelve-month period.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- C. The owner or operator shall develop an operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-283-S2

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain the following monthly records:
 - i. the number of hours that the emissions unit operated; and
 - ii. the rolling twelve-month total number of hours that the emissions unit operated.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- C. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- D. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse and the dust suppression system.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 93-A-283-S2

NSPS and NESHAP Requirements:

These emission units are subject to the requirements of 40 CFR Part 60, Subpart Y, “Standards of Performance for Coal Preparation Plants.” (IAC 23.1(2)”v”) and General Provisions, Subpart A.

Authority for Requirement: DNR Construction Permit 93-A-283-S2

The opacity standard shall apply at all times except during periods of startup, shutdown, malfunction, and as otherwise provided in the applicable standard. 40 CFR 60.11(c)

At all times, including periods of startup, shutdown, and malfunction, the permittee shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source. 40 CFR 60.11(d)

The permittee shall not build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous diluents to achieve compliance with an opacity standard or with a standard which is based on the concentration of a pollutant in the gases discharged to the atmosphere. 40 CFR 60.12

Authority for Requirement: 567 IAC 23.1(2)”v”
40 CFR 60 Subpart Y

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 45

Stack Opening (inches, dia.): 25

Exhaust Temperature (°F): Ambient

Exhaust Flowrate (scfm): 12,525

Discharge Style: Vents Inside

Authority for Requirement: DNR Construction Permit 93-A-283-S2

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Opacity Monitoring

The facility shall check the opacity weekly during a period when the emission unit on this emission point is at or near full capacity and record the reading. Maintain a written record of the observation and any action resulting from the observation for a minimum of five years.

The emission point shall be observed to ensure that no visible emissions occur during the material handling operation of the unit. If visible emissions are observed corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If corrective action does not return the observation to no visible emissions, then a Method 9 observation will be required.

If an opacity > 20% is observed, this would be a violation and corrective action will be taken as soon as possible, but no later than eight hours from the observation of visible emissions. If weather conditions prevent the observer from conducting an opacity observation, the observer shall note such conditions on the data observation sheet. At least three attempts shall be made to retake opacity readings at approximately 2-hour intervals throughout the day. If all observation attempts for a week have been unsuccessful due to weather, an observation shall be made the next operating day where weather permits.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 391

Associated Equipment

Associated Emission Unit ID Numbers: 391
Emissions Control Equipment ID Number: CE391
Control Equipment Description: Fabric Filter Baghouse

Emission Unit vented through this Emission Point: 391
Emission Unit Description: 150 Ton Dry Additive Storage Silo
Raw Material/Fuel: Powder Additive
Rated Capacity: 25 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 13-A-341
567 IAC 23.3(2)"d"

⁽¹⁾ An exceedance of the indicator opacity of 10% will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.00547 lb/hr

Authority for Requirement: DNR Construction Permit 13-A-341

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 0.13 lb/hr

Authority for Requirement: DNR Construction Permit 13-A-341

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.13 lb/hr, 0.1 gr/dscf

Authority for Requirement: DNR Construction Permit 13-A-341
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The owner or operator shall develop an operating and maintenance plan for the fabric filter baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 13-A-341

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the fabric filter baghouse.

Authority for Requirement: DNR Construction Permit 13-A-341

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 70

Stack Opening (inches, dia.): 0.6 x 125.7

Exhaust Temperature (°F): 70

Exhaust Flowrate (scfm): 750

Discharge Style: Horizontal

Authority for Requirement: DNR Construction Permit 13-A-341

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 392

Associated Equipment

Associated Emission Unit ID Numbers: 392
Emissions Control Equipment ID Number: CE392
Control Equipment Description: Fabric Filter Baghouse

Emission Unit vented through this Emission Point: 392
Emission Unit Description: Day Bin for EPC Conveyor
Raw Material/Fuel: Dry Additive
Rated Capacity: 15 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity
Emission Limit: 40 % ⁽¹⁾
Authority for Requirement: DNR Construction Permit 13-A-342
567 IAC 23.1(2)"v"

⁽¹⁾ An exceedance of the indicator opacity of 10% will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})
Emission Limit: 0.00329 lb/hr
Authority for Requirement: DNR Construction Permit 13-A-342

Pollutant: Particulate Matter (PM₁₀)
Emission Limit: 0.102 lb/hr
Authority for Requirement: DNR Construction Permit 13-A-342
(

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.102 lb/hr, 0.1 gr/scf
Authority for Requirement: DNR Construction Permit 13-A-342
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The owner or operator shall develop an operating and maintenance plan for the fabric filter baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 13-A-342

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the fabric filter baghouse.

Authority for Requirement: DNR Construction Permit 13-A-342

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 46

Stack Opening (inches, dia.): 8

Exhaust Temperature (°F): 70

Exhaust Flowrate (scfm): 1,200

Discharge Style: Vertical – Turbine Style Exhaust

Authority for Requirement: DNR Construction Permit 13-A-342

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 393

Associated Equipment

Associated Emission Unit ID Numbers: 393
Emissions Control Equipment ID Number: CE393
Control Equipment Description: Fabric Filter Baghouse

Emission Unit vented through this Emission Point: 393
Emission Unit Description: Day Bin for LSC-1 Conveyor
Raw Material/Fuel: Dry Additive
Rated Capacity: 15 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 13-A-343
567 IAC 23.3(2)"d"

- ⁽¹⁾ An exceedance of the indicator opacity of 10% will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.00329 lb/hr

Authority for Requirement: DNR Construction Permit 13-A-343

Pollutant: Particulate Matter (PM₁₀)

Emission Limit: 0.102 lb/hr

Authority for Requirement: DNR Construction Permit 13-A-343

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.102 lb/hr, 0.1 gr/scf

Authority for Requirement: DNR Construction Permit 13-A-343
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The owner or operator shall develop an operating and maintenance plan for the fabric filter baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 13-A-343

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall develop an operating and maintenance plan for the fabric filter baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 13-A-343

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 39

Stack Opening (inches, dia.): 8

Exhaust Temperature (°F): 70

Exhaust Flowrate (scfm): 1,200

Discharge Style: Vertical – Turbine Style Exhaust

Authority for Requirement: DNR Construction Permit 13-A-343

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 40 (Fugitive)

Associated Equipment

Associated Emission Unit ID Number: 40

Emission Unit vented through this Emission Point: 40
Emission Unit Description: Limestone Hopper Loading
Raw Material/Fuel: Limestone
Rated Capacity: 400 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40%

Authority for Requirement: DNR Construction Permit 13-A-155
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit: 0.147 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-155

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the emissions unit is limited to operating between 8:00 AM and 4:00 PM.

- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the emissions unit shall be roofed and shall be permanently enclosed on the three sides that are not used by vehicles. The fourth side shall be equipped with drive-through plastic strips. The drive-through plastics strips shall be maintained in good condition and shall be replaced when they become warped or damaged or are otherwise not providing an effective enclosure.
- C. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the amount of limestone handled in this emissions unit shall be limited to 200 tons per hour.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-343

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of the following: 1.) the amount of limestone handled, 2.) the number of hours that the emissions unit operated, and 3.) the average amount of limestone handled in tons per hour (#1/ #2).
- C. The owner or operator shall maintain records on the moisture content of the material handled in this emissions unit.
- D. The PM_{2.5} emission rate established in the Emission Limits section of this permit is based on the limited hourly capacity of the unit and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 5.0 miles per hour, based on an enclosure that reduces the wind speed in the enclosure by 33%; and

M = minimum material moisture content, 0.7%, provided by applicant, based on AP-42, Table 13.2.4-1, average moisture content of crushed limestone

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-343

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 41

Associated Equipment

Associated Emission Unit ID Numbers: 41, 42, and 43A

Emissions Control Equipment ID Number: CE40

Control Equipment Description: Fabric Filter Baghouse

Emission Units vented through this Emission Points: 41

Emission Unit Description: Limestone Conveying

Raw Material/Fuel: Limestone

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Points: 42

Emission Unit Description: Limestone Crusher

Raw Material/Fuel: Limestone

Rated Capacity: 200 tons/hr

Emission Units vented through this Emission Points: 43A

Emission Unit Description: Limestone Storage Silos

Raw Material/Fuel: Limestone

Rated Capacity: 200 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40 % ⁽¹⁾

Authority for Requirement: DNR Construction Permit 80-A-202-S2

567 IAC 23.3(2)"d"

⁽¹⁾ An exceedance of the indicator opacity of (10%) will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.088 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;

as amended by 80 FR 18133, April 3, 2015)

DNR Construction Permit 80-A-202-S2

Pollutant: Particulate Matter (PM₁₀)
Emission Limit(s): 0.866 lb/hr
Authority for Requirement: DNR Construction Permit 80-A-202-S2

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.01 gr/dscf
Authority for Requirement: DNR Construction Permit 80-A-202-S2
567 IAC 22.108(14)

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The differential pressure drop across the baghouse shall be maintained between 2 and 10 inches water column while the equipment is in operation.
- B. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 80-A-202-S2

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. The owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.
- D. The owner or operator shall maintain the following monthly records:
 - i. The amount of limestone processed in the emissions units (tons); and
 - ii. The total amount of limestone processed in each calendar year (tons).For tons of limestone processed, it is acceptable to record the amount of limestone received at the facility. This record keeping is required to document whether annual throughput of limestone has exceeded 10,000 and whether a stack test for PM_{2.5} is required in accordance with the Monitoring Requirements section of this permit.

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014);

as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-202-S2

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 115
Stack Opening (inches, dia.): 66 x 66
Exhaust Temperature (°F): 70
Exhaust Flow Rate (scfm): 11,818
Discharge Style: Horizontal
Authority for Requirement: DNR Construction Permit 80-A-202-S2

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant – Opacity

Stack Test to be Completed by – Stack testing for PM_{2.5} and opacity shall be conducted if the annual throughput of limestone exceeds 10,000 tons. The test shall be started no later than 120 days after the month in which the throughput exceeded 10,000 tons. If the test cannot be started during the 120 day period due to the unit’s limited operating schedule, MPW may request an extension of an additional 60 days to begin the testing.

Test Method - 40 CFR 60, Appendix A, Method 9

Authority for Requirement: DNR Construction Permit 80-A-202-S2

Pollutant – Particulate Matter (PM_{2.5})

Stack Test to be Completed by – Stack testing for PM_{2.5} and opacity shall be conducted if the annual throughput of limestone exceeds 10,000 tons. The test shall be started no later than 120 days after the month in which the throughput exceeded 10,000 tons. If the test cannot be started during the 120 day period due to the unit’s limited operating schedule, MPW may request an extension of an additional 60 days to begin the testing.

Test Method - 40 CFR 51, Appendix M, 201A with 202

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-202-S2

Pollutant - Particulate Matter (PM)

Stack Test to be Completed by – November 2, 2017

Test Method - 40 CFR 60, Appendix A, Method 5

40 CFR 51, Appendix M, Method 202

Authority for Requirement – 567 IAC 22.108(3)

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Emission Point ID Number: 45 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 45 and 45A

Emission Units vented through this Emission Point: 45
Emission Unit Description: Limestone Storage Pile
Raw Material/Fuel: Limestone
Rated Capacity: 2 Acres

Emission Units vented through this Emission Point: 45A
Emission Unit Description: Limestone Truck Unloading
Raw Material/Fuel: Limestone
Rated Capacity: 200 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

For Emission Units 45 and 45A

Pollutant: Opacity
Emission Limit: 40%
Authority for Requirement: DNR Construction Permit 13-A-142
567 IAC 23.3(2)"d"

Pollutant: Fugitive Dust
Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.
Authority for Requirement: 567 IAC 23.3(2)"c"

For Emission Unit 45A Only

Pollutant: Particulate Matter (PM_{2.5})
Emission Limit: 0.0625 lb/hr
Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-142

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The Limestone Truck Unloading operation (EU45A) is limited to operating between 6:00 AM and 4:00 PM.
- B. The number of delivery trucks for unloading limestone is limited to six per day.
- C. The amount of limestone that can be unloaded onto the storage pile is limited to 90 tons per day.
- D. The amount of limestone that can be unloaded onto the storage pile is limited to 50 tons per hour.
- E. The ground surface area of the limestone storage pile (EU45) shall not exceed 1 acre (43,560 square feet).
- F. The operating limits specified above in A, B, C, D, and E shall go into effect starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-142

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when the Limestone Truck Unloading (EU45A) operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain an hourly and daily record in tons on the amount of limestone loaded onto the storage pile.
- C. The owner or operator shall maintain records on the moisture content and the silt content of the material handled in this emissions unit.
- D. The owner or operator shall maintain records on the surface area of the limestone pile. By either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall submit to the Department its methodology for determining the size of the limestone pile. After the limestone pile is measured using its methodology, the owner or operator shall submit a report to the Department by November 1, 2013 indicating the size of the limestone pile. Thereafter, the limestone pile shall be measured semi-annually and information on the size of the limestone pile shall be submitted with the facility's semi-annual reports.

E. For the Limestone Truck Unloading (EU45A), the PM_{2.5} emissions rate established in Permit Condition 10 is based on the maximum capacity of the unit and the following equation and parameters :

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 0.7%, provided by applicant. 0.7% is the mean moisture content value listed in AP-42, Table 13.2.4-1 for crushed limestone.

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-142

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 60

Associated Equipment

Associated Emission Unit ID Number: 60

Emission Unit vented through this Emission Point: 60

Emission Unit Description: Auxiliary Boiler

Raw Material/Fuel: Fuel Oil, Natural Gas, or Propane

Rated Capacity: 29.29 MMBtu/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40% opacity ⁽¹⁾

Authority for Requirement: DNR Construction Permit 13-A-152
567 IAC 23.3(2)"d"

⁽¹⁾ An exceedance of the indicator opacity of 10% will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.567 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-152

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 0.720 lb/hr

Authority for Requirement: DNR Construction Permit 13-A-152

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.03 lb/MMBtu

Authority for Requirement: DNR Construction Permit 13-A-152

Pollutant: SO₂

Emission Limit(s): 0.44 lbs/MMBTU when burning fuel oil, 500 ppm by volume when burning
natural gas or propane

Authority for Requirement: DNR Construction Permit 13-A-152

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. This boiler is limited to burning natural gas or distillate fuel oil only. Propane (LP gas) may be used as a startup fuel when the boiler is to burn distillate fuel oil.
- B. The maximum sulfur content of the fuel oil burned in this engine shall not exceed 0.43% by weight.

Authority for Requirement: DNR Construction Permit 13-A-152

- C. The heat input to the boiler shall not exceed 25,658 million BTU (MMBTU) in any rolling 12-month period. This is equivalent to 10% of the potential heat input to the boiler had it been operated for 8,760 hours at the maximum design heat input capacity

Authority for Requirement: 567 IAC 22.108(14)

Reporting & Record keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources:

- A. The owner or operator shall perform an analysis and shall maintain records on the sulfur content of each shipment of oil received. Alternatively, the owner or operator shall have the oil supplier provide analyses on the sulfur content of the oil received. The analysis does not have to be for each shipment of oil received, but shall be documented by receipts from the fuel supplier, a statement from the fuel supplier on the specification of the sulfur content of the purchased oil, or other supporting documentation.

Authority for Requirement: DNR Construction Permit 13-A-152

- B. For each day that the boiler operates, the owner or operator shall keep a record that identifies each fuel burned and the amount of each fuel burned in the boiler.
- C. The owner or operator shall keep the following monthly records:
 - a. The amount of each fuel burned in the boiler;
 - b. The heat input to the boiler (million BTU); and
 - c. The rolling 12-month total of the heat input to the boiler (million BTU).

The owner or operator shall maintain these monthly records by the 30th day following the end of the previous month.

- D. The monthly heat input to the boiler shall be determined by using the following equation:

$$HI = [(NG_{usage})(NG_{HC}) + (FO_{usage})(FO_{HC}) + (LPG_{usage})(LPG_{HC})] s$$

Where:

HI = heat input to the boiler, MMBTU
NG_{usage} = amount of natural gas burned, standard cubic feet (scf)

- NG_{HC} = heat content of natural gas, MMBTU/scf, based on fuel supplier data, or, if fuel supplier data is not used, 0.001026 MMBTU/scf
 FO_{usage} = amount of fuel oil burned, gallons
 FO_{HC} = heat content of fuel oil, MMBTU/gal, based on fuel supplier data, or, if fuel supplier data is not used, 0.138 MMBTU/gal
 LPG_{usage} = amount of propane burned, gallons
 LPG_{HC} = heat content of propane, MMBTU/gal, based on fuel supplier data, or, if fuel supplier data is not used, 0.092 MMBTU/gal

Authority for Requirement: 567 IAC 22.108(3)

NSPS and NESHAP Requirements

This equipment is subject to the National Emission Standards for Hazardous Air Pollutants for Major Sources: Industrial, Commercial, and Institutional Boilers and Process Heaters [40 CFR Part 63 Subpart DDDDD].

Authority for Requirement: 40 CFR Part 63 Subpart DDDDD
 567 IAC 23.1(4)"dd"
 567 IAC 22.08(3)

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (feet): 122.8
 Stack Diameter (inches): 27
 Stack Exhaust Flow Rate (scfm): 4,336
 Stack Temperature (°F): 365
 Discharge Style: Vertical Unobstructed
 Authority for Requirement: DNR Construction Permit 13-A-152

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 70

Associated Equipment

Associated Emission Unit ID Numbers: 70

Emissions Control Equipment ID Numbers: CE71 and CE72

Emissions Control Equipment Descriptions: Cyclone Separator and ESP

Continuous Emissions Monitors ID Numbers: ME70A, ME71A, ME73 and ME74

Emission Unit vented through this Emission Point: 70

Emission Unit Description: Unit 7 Traveling Grate Stoker Boiler

Raw Material/Fuel: Bituminous Coal, Subbituminous Coal, and/or Natural Gas

Rated Capacity: 289 MMBtu/hr, either Coal or Natural Gas

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limits: 40%

Authority for Requirement: DNR Construction Permit 74-A-175-S3
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limits: 8.57 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 74-A-175-S3

Pollutant: Particulate Matter (PM₁₀)

Emission Limits: 121.0 lb/hr

Authority for Requirement: DNR Construction Permit 74-A-175-S3

Pollutant: Particulate Matter (PM)

Emission Limits: 121 lb/hr, 530 tons/yr, 0.42 lb/MMBtu

Authority for Requirement: DNR Construction Permit 74-A-175-S3

Pollutant: Sulfur Dioxide (SO₂)

Emission Limits: 6.0 lb/MMBtu

Authority for Requirement: DNR Construction Permit 74-A-175-S3
567 IAC 23.3(3)"a"

Emission Limits for Boilers 7 and 8 Combined

Pollutant: Sulfur Dioxide (SO₂)

Emission Limits: 2772 lb/hr ⁽¹⁾, 12,141 tons/yr ⁽²⁾

Authority for Requirement: DNR Construction Permit 74-A-175-S3

- ⁽¹⁾ Beginning March 15, 1996, the combined total emission of sulfur dioxide from Boiler 7 and Boiler 8 shall not exceed 2,772 pounds per hour, averaged over a 24-hour calendar day.
- ⁽²⁾ Beginning March 15, 1996, the combined total emission of sulfur dioxide from Boiler 7 and Boiler 8 shall not exceed 12,141 tons per year.

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below:

Operating Limits:

- A. Total emissions of sulfur dioxide from unit 7 and unit 8 shall not exceed 2,772 pounds per hour, averaged over a 24-hour calendar day.
- B. The owner or operator shall develop an operating and maintenance plan for the multiclone and the electrostatic precipitator including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 74-A-175-S3

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner shall maintain a file of computations to show the total hourly emission rate of sulfur dioxide emissions from unit 7 and unit 8. The owner shall submit quarterly excess emission reports as specified in 567 IAC 25.1(6). Oral and written excess emission reporting shall be required as specified in Chapter 25 of the Iowa rules.

Authority for Requirement: DNR Construction Permit 74-A-175-S3

NSPS and NESHAP Requirements

This equipment is subject to the National Emission Standards for Hazardous Air Pollutants for Major Sources: Industrial, Commercial, and Institutional Boilers and Process Heaters [40 CFR Part 63 Subpart DDDDD].

Authority for Requirement: 40 CFR Part 63 Subpart DDDDD
567 IAC 23.1(4)"dd"
567 IAC 22.108(3)

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (feet): 220

Stack Diameter (inches): 106.3

Stack Exhaust Flow Rate (scfm): 65,000

Stack Temperature (°F): 350

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 74-A-175-S3

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant – Particulate Matter (PM_{2.5})

1st Stack Test to be Completed between – May 2, 2018 and May 2, 2019

Test Method - 40 CFR 51, Appendix M, 201A with 202

Authority for Requirement - 567 IAC 22.108(3)

Pollutant – Particulate Matter (PM₁₀)

1st Stack Test to be Completed by – November 2, 2016

2nd Stack Test to be Completed between – May 2, 2018 and May 2, 2019

Test Method - 40 CFR 51, Appendix M, 201A with 202

Authority for Requirement - 567 IAC 22.108(3)

Pollutant – Particulate Matter (PM)

1st Stack Test to be Completed by – November 2, 2016

2nd Stack Test to be Completed between – May 2, 2018 and May 2, 2019

Test Method - 40 CFR 60, Appendix A, Method 5

40 CFR 51, Appendix M, Method 202

Authority for Requirement - 567 IAC 22.108(3)

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Continuous Emissions Monitoring:

Pollutant - Opacity

Operational Specifications - 40 CFR Part 60

Initial System Calibration/Quality Assurance –July 2000

Ongoing System Calibration/Quality Assurance - 40 CFR Part 60

Reporting & Record keeping - 567 IAC 25. Submit all reports and petitions required by 567 IAC 25 to the Iowa DNR in order to demonstrate compliance with continuous emission monitoring and the 40% opacity (visible emissions) limit

Authority for Requirement - 567 IAC 25.1(1), 567 IAC 23.3(2)"d",
567 IAC 22.108(4), and 567 IAC 22.108(15)

Pollutant - Sulfur Dioxide (SO₂)

Operational Specifications – As found in 40 CFR Part 75

Initial System Calibration/Quality Assurance – 07/27 – 08/08/2006

Ongoing System Calibration/Quality Assurance –As found in 40 CFR Part 75

Reporting & Record keeping – As found in 40 CFR Part 75. Submit all reports and petitions required by 40 CFR 75 to the Iowa DNR in order to demonstrate compliance with the 6 lb/MMBtu SO₂ emission limit for boiler 7 alone and 2772 lb/hr SO₂ emissions for boilers 7 and 8.

Authority for Requirement - Iowa DNR Construction Permit 74-A-175-S2 and
EPA PSD permit 80-E-001 dated 1/24/80 and revision 80-E-001-S dated 9/6/83

Other Parameters (For the calculation of SO₂)

Pollutant - Other - Carbon Dioxide (CO₂)

Operational Specifications – As found in 40 CFR Part 75

Initial System Calibration/Quality Assurance – 07/27 – 08/08/2006

Ongoing System Calibration/Quality Assurance –As found in 40 CFR Part 75

Reporting & Record keeping – As found in 40 CFR Part 75. Submit all reports and petitions required by 40 CFR 75 to the Iowa DNR in order to demonstrate compliance with the 6 lb/MMBtu SO₂ emission limit for boiler 7 alone and 2772 lb/hr SO₂ emissions for boilers 7 and 8.

Authority for Requirement - Iowa DNR Construction Permit 74-A-175-S2 and
EPA PSD permit 80-E-001 dated 1/24/80 and revision 80-E-001-S dated 9/6/83

Pollutant - Other - Flow

Operational Specifications – As found in 40 CFR Part 75

Initial System Calibration/Quality Assurance – 11/29-12/14/95

Ongoing System Calibration/Quality Assurance –As found in 40 CFR Part 75

Reporting & Record keeping – As found in 40 CFR Part 75. Submit all reports and petitions required by 40 CFR 75 to the Iowa DNR in order to demonstrate compliance with the 6 lb/MMBtu SO₂ emission limit for boiler 7 alone and 2772 lb/hr SO₂ emissions for boilers 7 and 8.

Authority for Requirement - Iowa DNR Construction Permit 74-A-175-S2 and
EPA PSD permit 80-E-001 dated 1/24/80 and revision 80-E-
001-S dated 9/6/83

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required performance evaluation of a continuous emission monitor. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Monitoring Guidelines

The facility makes a commitment to take timely corrective action during periods of excursion where the indicators are out of range. A corrective action may include an investigation of the reason for the excursion, evaluation of the situation and necessary follow-up action to return operation within the indicator range. An excursion is determined by the averaged discrete data point over a period of time. An excursion does not necessarily indicate a violation of an applicable requirement. If the corrective action measures fail to return the indicators to the appropriate range, the facility will report the exceedance to the department and conduct source testing within 90 days of the exceedance to demonstrate compliance with applicable requirements. If the test demonstrates compliance with emission limits then new indicator ranges must be set for monitoring and the new ranges must be incorporated in the operating permit. If the test demonstrates noncompliance with emission limits, then the facility, within 60 days, proposes a schedule to implement corrective action to bring the source into compliance and demonstrate compliance.

Monitoring Methods and Corrective Actions

Compliance Assurance Monitoring (CAM) Plan for CE71 Multi-Cyclone

I. Background

- A. Emissions Unit:
Identification: EP70/EU70
Description: Unit 7 Traveling Grate Stoker Boiler
Facility: Muscatine Power & Water, 1700 Dick Drake Way, Muscatine, Iowa 52761

- B. Applicable Regulation, Emission Limit, and Monitoring Requirements:
 Applicable regulation: Permit 74-A-175-S3
 PM Emission Limit: 121 lb/hr, 530 tons/yr, 0.42 lb/MMBtu
 PM₁₀ Emission Limit: 121 lb/hr
 PM_{2.5} Emission Limit: 8.57 lb/hr

- C. Current Monitoring Requirements:
 Stack Testing
 Continuous Opacity Monitoring (COMS) ME70A
 Audible Precipitator “Malfunction” Alarm

- D. Current Technology: Cyclonic Separator Dust Collector

II. Monitoring Approach

- A. Indicator: Continuous monitoring of differential pressure alarms will be used as an indicator.
- B. Measurement Approach: Differential pressure alarms are checked continuously to detect differential pressure of less than 1.0 inches or greater than 5.1 inches of water.
- C. Indicator Range: An excursion is defined as a differential pressure of less than 1.0 inches or greater than 5.1 inches of water for an hourly average, except during periods of start-up, shutdown, and upset conditions.
- D. QIP (Quality Improvement Plan) Threshold: The QIP threshold is six excursions in a one month period.
- E. Performance Criteria Data representativeness: Differential pressure of less than 1.0 inches or greater than 5.1 inches water would indicate a decrease in the performance of either the cyclone separator or the dust collector and potentially indicate an increase of or particulate emissions.
- Verification of operational Differential pressure alarm records will be maintained for five years.
- QA/QC practices and criteria: The facility shall monitor the differential pressure alarm status when the system is in operation. If an hourly average differential pressure of less than 1.0 inches of water or a differential pressure greater than 5.1 inches of water is observed, corrective action will be taken within 8 hours, except when an alarm arises during periods of startup, shutdown, or upset conditions.

Monitoring frequency Differential pressure alarms shall be monitored by the DCS when the emission unit is in operation.

Compliance Assurance Monitoring (CAM) Plan for CE72 Electrostatic Precipitator

II. Background

- A. Emissions Unit:
 Identification: EP70/EU70
 Description: Unit 7 Traveling Grate Stoker Boiler
 Facility: Muscatine Power & Water, 1700 Dick Drake Way, Muscatine, Iowa 52761
- B. Applicable Regulation, Emission Limit, and Monitoring Requirements:
 Applicable regulation: Permit 74-A-175-S3
 PM Emission Limit: 121 lb/hr, 530 ton/yr, 0.42 lb/MMBtu
 PM₁₀ Emission Limit: 121 lb/hr
 PM_{2.5} Emission Limit: 8.57 lb/hr
- C. Current Monitoring Requirements:
 Stack Testing
 Continuous Opacity Monitoring (COMS) ME70A
 Audible Precipitator “Malfunction” Alarm
- D. Current Technology: Electrostatic Precipitator

III. Monitoring Approach:

1. <u>Indicator</u> Measurement Approach	Opacity of ESP exhaust	Audible Precipitator “Malfunction” Alarm
	COMS in ESP exhaust	The audible and visual alarm continuously monitors T-R set failure and rapper control malfunction.
2. <u>Indicator Range</u>	A CAM excursion will be defined as opacity exceeding 30% over any 1-hour averaging period. Except during startup, shutdown, or cleaning of control equipment as per 567 IAC 24.1(1). Corrective action will be implemented within 8 hours plus the period of time until generating capacity is available to meet consumer demand, after it is determined that the opacity monitor is functioning properly.	A CAM excursion will be defined as Failure of two T-R sets or more than 25% of the rappers. Corrective action measures will be implemented on the occurrence of a “Malfunction” alarm. The appropriate measures for remediation will be implemented within eight hours plus the period of time until generating capacity is available to meet customer demand. Random T-R set failure and rapper failure (up to one T-R set and 25% of the rappers per precipitator section) will not

		significantly affect precipitator performance.
3. <u>Performance Criteria</u> A. Data Representativeness	COMS installed at a representative location in the ESP exhaust per 40 CFR 60, Appendix B, Performance Specification 1 (PS-1).	Rapper system operation, T-R set operation and ash removal system operation are indicators of the proper electromechanical operation of the ESP. An audible alarm will continuously monitor T-R set failure and rapper control health. Daily inspection of the rapper system operation, T-R sets and ash removal system provide additional assurance of proper electromechanical operation of the ESP.
B. Verification of Operational Status	Results of initial COMS performance evaluation conducted per PS-1 (July 2000).	Results of equipment verification tests conducted to calibrate the audible and visible alarm displays.
C. QA/QC Practices/Criteria	Installation and evaluation of the COMS per PS-1. The continuous opacity monitor is automatically calibrated for zero and span adjustments daily.	All instruments and control equipment will be calibrated, maintained, and operated according to the manufactures specifications.
D. Monitoring Frequency	Monitor the opacity of the ESP exhaust continuously (every 10 seconds).	An audible alarm will continuously (greater than four times per hour) monitor T-R set failure and rapper control malfunction.
E. Data Collection Procedures	Set up the data acquisition system (DAS) to retain all 6-minute average opacity data.	Maintain records of T-R and rapper failures exceeding CAM thresholds for longer than one hour.
F. Averaging period	Use the 10-second opacity data to calculate 6-minute averages. Use the 6-minute averages to calculate hourly block average opacity for the CAM.	N/A

IV. Quality Improvement Plan (QIP):

A Quality Improvement Plan (QIP) will be required to be submitted to the IDNR if an accumulation of excursions of either the opacity indicator or the T-R and rapper alarms exceed 5 percent of the boiler's normal operating time for a 6-month reporting period. All requirements in 40 CFR 64.8(b) shall be fulfilled if a QIP is required.

V. Quality Assurance and Quality Control:

In addition to monitoring the opacity and T-R / rapper alarms, MP&W will conduct the following activities to assure compliance. The following monitoring is not required during periods of time greater than one day in which the source does not operate.

- A. Monitor detection equipment, including alarm displays in the control room, which alert operators to irregular operating conditions such as high hopper levels, high opacity, and continuous opacity monitoring system (COMS) failure.
- B. Conduct daily inspections of the ESP electromechanical operation:
 - Inspection of rapper operation
 - Inspection of T-R set operation including power usage level
 - Inspection of ash removal system operation
- C. Each Major Scheduled Unit Outage (typically lasting four or more weeks):
 - Check and correct plate/electrode alignment
 - Inspect for collection surface fouling
 - Inspect T-R set mechanical condition
 - Inspect internal structural components
 - Evaluate and correct ash transport system wear areas

Corrective action to correct abnormal operating conditions will be implemented within 8 hours plus the period of time until generating capacity is available to meet consumer demand.

- D. Record Keeping and Recording:
 - Records of all daily inspections and any actions resulting from these inspections will be kept for five years.
 - Records of all planned unit outage inspections and any actions resulting from these inspections will be kept for five years.
 - MP&W shall record the summary information on the number, duration and cause (including unknown cause, if applicable) of excursions or exceedances, as applicable, and the corrective actions taken. 40 CFR 64.9(a)(2)(i).
 - MP&W shall record the summary information on the number, duration and cause (including unknown cause, if applicable) for monitor downtime incidents (other than downtime associated with zero and span or other daily calibration checks, if applicable). 40 CFR 64.9(a)(2)(ii).
 - All excursions and monitor downtime incidents will be reported in semi-annual monitoring reports and annual compliance certifications.
- E. Quality Control:
 - All instruments and equipment will be calibrated, maintained, and operated according to the manufacturer's specifications.
 - An inventory of spare parts will be maintained. Parts will be re-ordered as they are used.

Authority for requirement: 567 IAC 22.108(3)
40 CFR 64

Emission Point ID Number: 80

Associated Equipment

Associated Emission Unit ID Number: 80

Emissions Control Equipment ID Numbers: CE80A, CE81

Emissions Control Equipment Descriptions: ESP, Over-fired Air (OFA)

Continuous Emissions Monitors ID Numbers: ME80A, ME81A, ME82A, ME83, ME84, and ME85

Emission Unit vented through this Emission Point: 80

Emission Unit Description: Unit 8 Cyclone Boiler

Raw Material/Fuel: Bituminous Coal, Subbituminous Coal, or Natural Gas

Waste Solvent (330 gal/month for combustion)

Diesel Oil and/or Waste Oil (Occasionally for short periods to facilitate slag tapping or coal combustion)

Rated Capacity: 890 MMBtu/hr Coal or Natural Gas

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limits: 40%

Authority for Requirement: DNR Construction Permit 95-A-373-P2
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limits: 37.57 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 95-A-373-P2

Pollutant: Particulate Matter (PM₁₀)

Emission Limits: 266.9 lb/hr

Authority for Requirement: DNR Construction Permit 95-A-373-P2

Pollutant: Particulate Matter (PM)

Emission Limits: 267 lb/hr, 1169 tons/yr, 0.30 lb/MMBtu

Authority for Requirement: DNR Construction Permit 95-A-373-P2

Pollutant: Sulfur Dioxide (SO₂)

Emission Limits: 6 lb/MMBtu

Authority for Requirement: DNR Construction Permit 95-A-373-P2

Pollutant: Nitrogen Oxides (NO_x)

Emission Limits: 3352.45 tons/yr, 0.86 lb/MMBtu⁽¹⁾

Authority for Requirement: DNR Construction Permit 95-A-373-P2

⁽¹⁾ As requested to remain an insignificant increase for PSD and to meet Acid Rain requirements in 40 CFR 76.6. Standard is a twelve month rolling average, and includes startup, shutdown and malfunctions.

Emission Limits for Boilers 7 and 8 Combined

Pollutant: Sulfur Dioxide (SO₂)

Emission Limits: 2772 lb/hr, 12,141 tons/yr

Authority for Requirement: DNR Construction Permit 95-A-373-P2

BACT Emission Limit

Pollutant: Carbon Monoxide (CO)

BACT Emission Limits: 960 tons/yr ⁽²⁾, 250 ppm ⁽³⁾

Authority for Requirement: DNR Construction Permit 95-A-373-P2

⁽²⁾ Standard is a twelve month rolling average, and includes startup, shutdown and malfunctions.

⁽³⁾ Standard is averaged over a calendar day, and does not include startup, shutdown and malfunction.

Acid Rain Limits

Pollutant: Sulfur Dioxide (SO₂)

Emission Limits: Sulfur Dioxide Allowances

Authority for Requirement: 567 IAC 22.108(7) (See attached Phase II Permit in appendix)

Pollutant: Nitrogen Oxides (NO_x)

Emission Limits: See attached Phase II Acid Rain Permit

Authority for Requirement: 567 IAC 22.125(4) (Attached Phase II Acid Rain Permit)
40 CFR 76.7(a)(1)

Pollutant: Carbon Monoxide (CO)

Emission Limits: 432.4 lbs/hr

Authority for Requirement: DNR Construction Permit 95-A-373-P2

Cross-State Air Pollution Rule (CSAPR) (aka Transport Rule (TR)) Limit

Pollutant: Nitrogen Oxides (NO_x) Annual, Nitrogen Oxides (NO_x) Ozone Season,
Sulfur Dioxide (SO₂) Group 1

Emission Limits: Nitrogen Oxides and Sulfur Dioxide Allowance

Authority for Requirement: 40 CFR Part 97 (See Appendix B for requirements)

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below:

Operating Limits:

- A. No person shall allow, cause or permit the combustion of number 1 or number 2 diesel fuel exceeding a sulfur content of 0.5 percent by weight.

Authority for Requirement: 567 IAC 23.3(3)"b"(1)

- A. Total emission of sulfur dioxide from Unit 7 Boiler and Unit 8 Boiler shall not exceed 2,772 pounds per hour, averaged over a 24-hour calendar day.
- B. The owner or operator shall, to the extent practicable, maintain and operate the unit in a manner consistent with good air pollution control practice for minimizing emissions at all times, including periods of startup, shutdown and malfunction.
- C. The owner or operator shall combust coal and/or natural gas in this unit. Waste solvent may also be combusted at a rate of 330 gal/month. Diesel oil and/or waste oil may be combusted in this unit for short periods of time to facilitate coal combustion and/or slag tapping.

Authority for Requirement: DNR Construction Permit 95-A-373-P2

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

1. The combined SO₂ emissions in pounds per hour from boilers 7 and 8 averaged over a 24-hour calendar day.
2. The combined SO₂ emissions in tons per calendar year from boilers 7 and 8.
3. The facility shall monitor the percent of sulfur by weight in the diesel fuel as delivered. The documentation may be vendor supplied or facility generated.

Authority for Requirement: 567 IAC 22.108(3)

- A. The owner or operator shall monitor emissions from this unit and calculate the annual emissions, in tons per year on a calendar-year basis, for a period of five years following resumption of regular operations after the change made in construction permit project 07-355. This information shall be retained by the owner or operator for a period of ten years after the construction permit project 07-355 is completed (IAC 567 33.3(18)"f"(4)).
- B. The owner or operator shall submit a report to the department within 60 days after the end of each year during which records must be generated under 567-IAC 33.3(18)"f" (4) setting out the unit's annual emissions during the calendar year that preceded submission of the report. This shall be for a period of five years following resumption of regular operations (project 07-355). The owner or operator shall also notify the DNR if the combined total annual emissions of Boiler 8 and Boiler 9, in tons per year, exceed any of the following:
 1. Particulate Matter (PM) – 327.12 tpy

2. Particulate Matter less than 10 microns (PM10) – 317.12 tpy
 3. Sulfur Dioxide (SO₂) – 3,633.45 tpy
 4. Nitrogen Oxides (NO_x) – 4,620.17 tpy
 5. Volatile Organic Compounds (VOC) – 80.46 tpy
- C. The owner or operator shall make the information required to be documented and maintained pursuant to IAC 567-33.3(18)“f” available for review upon request for inspection by the Department or the general public pursuant to the requirements for Title V operating permits contained in 567-22.107(6).
- D. The owner or operator shall maintain a file of computations to show the total hourly emission level for SO₂. The owner shall submit quarterly excess emission reports as specified in IAC 567-25.1(6).
- E. The owner or operator shall record the amount of waste solvent, diesel oil and/or used oil used on a monthly basis.
- F. Using the data collected and recorded by the NO_x CEMs, the owner or operator shall record monthly:
- i. NO_x emissions from the boiler (tons); and
 - ii. the rolling 12-month total of NO_x emissions from the boiler (tons).

Authority for Requirement: DNR Construction Permit 95-A-373-P2

NSPS and NESHAP Requirements

This equipment is subject to the National Emission Standards for Hazardous Air Pollutants: *Coal- and Oil-Fired Electric Utility Steam Generating Units (MATS)* [40 CFR Part 63, Subpart UUUUU].

Authority for Requirement: 40 CFR Part 63 Subpart UUUUU

This unit is considered an affected source under 40 CFR 72, 73, 75, 76, 77 and 78 definitions. Therefore, this emission unit is subject to the applicable provisions of the Acid Rain Program.

Authority for Requirement: DNR Construction Permit 95-A-373-P2
40 CRF Parts 72, 73, 75, 76, 77, 78

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 225

Stack Diameter (inches, dia.): 102.4

Stack Exhaust Flow Rate (scfm): 229,000

Stack Temperature (°F): 350

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 95-A-373-P2

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may

vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant – Particulate Matter (PM_{2.5})

1st Stack Test to be Completed by – November 2, 2016

2nd Stack Test to be Completed between – May 2, 2018 and May 2, 2019

Test Method - 40 CFR 51, Appendix M, 201A with 202

Authority for Requirement - 567 IAC 22.108(3)

Pollutant – Particulate Matter (PM₁₀)

1st Stack Test to be Completed by – November 2, 2016

2nd Stack Test to be Completed between – May 2, 2018 and May 2, 2019

Test Method - 40 CFR 51, Appendix M, 201A with 202

Authority for Requirement - 567 IAC 22.108(3)

Pollutant – Particulate Matter (PM)

1st Stack Test to be Completed by – November 2, 2016

2nd Stack Test to be Completed between – May 2, 2018 and May 2, 2019

Test Method - 40 CFR 60, Appendix A, Method 5

40 CFR 51, Appendix M, Method 202

Authority for Requirement - 567 IAC 22.108(3)

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Continuous Emissions Monitoring:

Pollutant - Opacity

Operational Specifications - 40 CFR Part 60

Initial System Calibration/Quality Assurance – 07/09/2011

Ongoing System Calibration/Quality Assurance - 40 CFR Part 60

Reporting & Record keeping - 40 CFR Part 60. Submit all reports and petitions required by 40 CFR 60 to the Iowa DNR in order to demonstrate compliance with continuous emission monitoring under the acid rain program and the 40% opacity (visible emissions) limit

Authority for Requirement - 567 IAC 25.1(1), 567 IAC 25.2, 567 IAC 23.3(2)"d", 567 IAC 22.108(4), and 567 IAC 22.108(15)

Pollutant - Sulfur Dioxide (SO₂)

Operational Specifications - 40 CFR Part 75

Initial System Calibration/Quality Assurance – 07/17 – 08/09/2006

Ongoing System Calibration/Quality Assurance - 40 CFR Part 75

Reporting & Record keeping - 40 CFR Part 75. Submit all reports and petitions required by 40 CFR 75 to the EPA in order to demonstrate compliance with continuous emission monitoring under the acid rain program and the 6 lb/MMBtu SO₂ emission limit.

The owner or operator shall maintain an on-site record of CEMS-related data for not less than two years from the origination. The record shall contain all hourly SO₂ and flow rate measurements, any missing data substitution, subsequent aggregate and averaging calculation, results of quality assurance and averaging calculations, results of quality assurance activities, and all performance test results. These records shall be made readily available for inspection by the IDNR, EPA, or any authorized agent of these agencies.

Authority for Requirement - 567 IAC 25.2, 567 IAC 23.3(3)"a"(2),
567 IAC 22.108(4), and 567 IAC 22.108(15),
DNR Construction Permit 95-A-373-P2, and
EPA PSD permit 80-E-001 dated 1/24/80 and revision 80-E-001-S dated 9/6/83

Pollutant - Nitrogen Oxides (NO_x)

Operational Specifications - 40 CFR Part 75

Initial System Calibration/Quality Assurance - 07/17 – 08/09/2006

Ongoing System Calibration/Quality Assurance - 40 CFR Part 75

Reporting & Record keeping - 40 CFR Part 75. Submit all reports and petitions required by 40 CFR 75 to the EPA in order to demonstrate compliance with continuous emission monitoring under the acid rain program

Authority for Requirement - 567 IAC 25.2

Pollutant – Carbon Monoxide (CO)

Operational Specifications - 40 CFR Part 75

Initial System Calibration/Quality Assurance – December 12, 2008

Ongoing System Calibration/Quality Assurance - 40 CFR Part 75

Reporting & Record keeping - 40 CFR Part 75. Submit all reports and petitions required by construction permit 95-A-373-P2 to the Iowa DNR in order to demonstrate compliance with the CO emission limits.

Authority for Requirement - DNR Construction Permit 95-A-373-P2

Other Parameters

Pollutant - Other - Carbon Dioxide (CO₂)

Operational Specifications - 40 CFR Part 75

Initial System Calibration/Quality Assurance - 8/11-8/26/94

Ongoing System Calibration/Quality Assurance - 40 CFR Part 75

Reporting & Record keeping - 40 CFR Part 75. Submit all reports and petitions required by 40 CFR 75 to the EPA in order to demonstrate compliance with continuous emission monitoring under the acid rain program.

Authority for Requirement - 567 IAC 25.2, 567 IAC 22.108(4), 567 IAC 22.108(15), DNR Construction Permit 95-A-373-P2, and

EPA PSD permit 80-E-001 dated 1/24/80 and revision 80-E-001-S dated 9/6/83

Pollutant - Other - Flow

Operational Specifications - 40 CFR Part 75

Initial System Calibration/Quality Assurance – 08/10/2011

Ongoing System Calibration/Quality Assurance - 40 CFR Part 75

Reporting & Record keeping - 40 CFR Part 75. Submit all reports and petitions required by 40 CFR 75 to the EPA in order to demonstrate compliance with continuous emission monitoring under the acid rain program.

Authority for Requirement - 567 IAC 25.2, 567 IAC 22.108(4), 567 IAC 22.108(15), DNR Construction Permit 95-A-373-P2, and

EPA PSD permit 80-E-001 dated 1/24/80 and revision 80-E-001-S dated 9/6/83

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required performance evaluation of a continuous emission monitor. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Monitoring Guidelines

The facility makes a commitment to take timely corrective action during periods of excursion where the indicators are out of range. A corrective action may include an investigation of the reason for the excursion, evaluation of the situation and necessary follow-up action to return operation within the indicator range. An excursion is determined by the averaged discrete data point over a period of time. An excursion does not necessarily indicate a violation of an applicable requirement. If the corrective action measures fail to return the indicators to the appropriate range, the facility will report the exceedance to the department and conduct source testing within 90 days of the exceedance to demonstrate compliance with applicable requirements. If the test demonstrates compliance with emission limits then new indicator ranges must be set for monitoring and the new ranges must be incorporated in the operating permit. If the test demonstrates noncompliance with emission limits, then the facility, within 60

days, proposes a schedule to implement corrective action to bring the source into compliance and demonstrate compliance.

Monitoring Methods and Corrective Actions

Compliance Assurance Monitoring (CAM) Plan for CE80A Electrostatic Precipitator

I. Background

- A. Emissions Unit:
 Identification: EP80/EU80
 Description: Unit 8 Cyclone Boiler
 Facility: Muscatine Power & Water, 1700 Dick Drake Way,
 Muscatine, Iowa 52761
- B. Applicable Regulation, Emission Limit, and Monitoring Requirements:
 Applicable regulation: DNR Construction Permit 95-A-373-P2
 PM Emission Limit: 267 lb/hr, 1,169 tons/yr, 0.30 lb/MMBtu
 PM₁₀ Emission Limits: 266.9 lb/hr
- C. Current Monitoring Requirements:
 Stack Testing
 Continuous Opacity Monitoring (COMS) ME80A
 Audible Precipitator various “Malfunction” Alarms
- D. Current Technology: Electrostatic Precipitator

II. Monitoring Approach:

1. Indicator	Opacity of ESP exhaust	Audible Precipitator “Malfunction” Alarm
Measurement Approach	COMS in ESP exhaust	The audible and visual alarm continuously monitors T-R set failure and rapper control malfunction.
2. Indicator Range	A CAM excursion will be defined as opacity exceeding 25% over any 1-hour averaging period. Except during startup, shutdown, or cleaning of control equipment as per 567 IAC 24.1(1). Corrective action will be implemented within 8 hours plus the period of time	A CAM excursion will be defined as Failure of three T-R sets or more than 32 of the rappers. Corrective action measures will be implemented on the occurrence of a “Malfunction” alarm. The appropriate measures for remediation will be implemented within eight hours plus the period of time until generating capacity is available to meet customer demand.

	until generating capacity is available to meet consumer demand, after it is determined that the opacity monitor is functioning properly.	Random T-R set failure and rapper failure (up to two T-R set and 31 of the rappers) will not significantly affect precipitator performance.
3. Performance Criteria	COMS installed at a representative location in the ESP exhaust per 40 CFR 60, Appendix B, Performance Specification 1 (PS-1).	Rapper system operation, T-R set operation and ash removal system operation are indicators of the proper electromechanical operation of the ESP. An audible alarm will continuously monitor T-R set failure and rapper control health. Daily inspection of the rapper system operation, T-R sets and ash removal system provide additional assurance of proper electromechanical operation of the ESP.
A. Data Representativeness		
B. Verification of Operational Status	Results of initial COMS performance evaluation conducted per PS-1 (July 2000).	Results of equipment verification tests conducted to calibrate the audible and visible alarm displays.
C. QA/QC Practices/Criteria	Installation and evaluation of the COMS per PS-1. The continuous opacity monitor is automatically calibrated for zero and span adjustments daily.	All instruments and control equipment will be calibrated, maintained, and operated according to the manufactures specifications.
D. Monitoring Frequency	Monitor the opacity of the ESP exhaust continuously (every 10 seconds).	An audible alarm will continuously (greater than four times per hour) monitor T-R set failure and rapper control malfunction.
E. Data Collection Procedures	Set up the data acquisition system (DAS) to retain all 6-minute average opacity data.	Maintain records of T-R and rapper failures exceeding CAM thresholds for longer than one hour.
F. Averaging period	Use the 10-second opacity data to calculate 6-minute averages. Use the 6-minute averages to calculate hourly block average opacity for the CAM.	N/A

III. Quality Improvement Plan (QIP):

A Quality Improvement Plan (QIP) will be required to be submitted to the IDNR if an accumulation of excursions of either the opacity indicator or the T-R and rapper alarms exceed 5 percent of the boiler's normal operating time for a 6-month reporting period. All requirements in 40 CFR 64.8(b) shall be fulfilled if a QIP is required.

IV. Quality Assurance and Quality Control:

In addition to monitoring the opacity and T-R / rapper alarms, MP&W will conduct the following activities to assure compliance. The following monitoring is not required during periods of time greater than one day in which the source does not operate.

- A. Monitor detection equipment, including alarm displays in the control room, which alert operators to irregular operating conditions such as high hopper levels, high opacity, and continuous opacity monitoring system (COMS) failure.
- B. Conduct daily inspections of the ESP electromechanical operation:
 - Inspection of rapper operation
 - Inspection of T-R set operation including power usage level
 - Inspection of ash removal system operation
- C. Each Major Scheduled Unit Outage (typically lasting four or more weeks):
 - Check and correct plate/electrode alignment
 - Inspect for collection surface fouling
 - Inspect T-R set mechanical condition
 - Inspect internal structural components
 - Evaluate and correct ash transport system wear areas

Corrective action to correct abnormal operating conditions will be implemented within 8 hours plus the period of time until generating capacity is available to meet consumer demand.

- D. Record Keeping and Recording:
 - Records of all daily inspections and any actions resulting from these inspections will be kept for five years.
 - Records of all planned unit outage inspections and any actions resulting from these inspections will be kept for five years.
 - MP&W shall record the summary information on the number, duration and cause (including unknown cause, if applicable) of excursions or exceedances, as applicable, and the corrective actions taken. 40 CFR 64.9(a)(2)(i).
 - MP&W shall record the summary information on the number, duration and cause (including unknown cause, if applicable) for monitor downtime incidents (other than downtime associated with zero and span or other daily calibration checks, if applicable). 40 CFR 64.9(a)(2)(ii).
 - All excursions and monitor downtime incidents will be reported in semi-annual monitoring reports and annual compliance certifications.

E. Quality Control:

- All instruments and equipment will be calibrated, maintained, and operated according to the manufacturer's specifications.
- An inventory of spare parts will be maintained. Parts will be re-ordered as they are used.

Authority for requirement: 567 IAC 22.108(3)
40 CFR 64

Emission Point ID Number: 810

Associated Equipment

Associated Emission Unit ID Numbers: CE810A/CE810B
Emissions Control Equipment ID Number: CE811
Control Equipment Description: Cartridge Filter – Final Filter

Emission Units vented through this Emission Point: CE810A/CE810B
Emission Unit Description: Filter/Separator Dust Collector DC-6A
Raw Material/Fuel: Fly Ash
Rated Capacity: 8 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 00-A-639-S1
567 IAC 23.3(2)"d"

⁽¹⁾ An exceedence of the indicator opacity of (10%) will required the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedence. If exceedences continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.056 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 00-A-639-S1

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 0.190 lb/hr

Authority for Requirement: DNR Construction Permit 00-A-639-S1

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.025 gr/dscf

Authority for Requirement: DNR Construction Permit 00-A-639-S1

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below:

- A. The owner or operator shall develop a operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 00-A-639-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

Authority for Requirement: DNR Construction Permit 00-A-639-S1

Emission Point Characteristics

The emission point shall conform to the specifications listed below.

Stack Height (feet from the ground): 142

Stack Diameter (inches): 16

Stack Exhaust Flow Rate (scfm): 890

Stack Temperature (°F): 93

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 00-A-639-S1

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 813 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 810

Emission Units vented through this Emission Point: 810

Emission Unit Description: Fly Ash Silo

Raw Material/Fuel: Fly Ash

Rated Capacity: 8 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 814

Associated Equipment

Associated Emission Unit ID Numbers: 810 & 811

Emissions Control Equipment ID Number: CE812

Control Equipment Description: Bin Vent Filter

Emission Units vented through this Emission Point: 810

Emission Unit Description: Fly Ash Silo

Raw Material/Fuel: Fly Ash

Rated Capacity: 8 tons/hr

Emission Units vented through this Emission Point: 811

Emission Unit Description: Dry Fly Ash Truck Loading

Raw Material/Fuel: Fly Ash

Rated Capacity: 20 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 01-A-218-S1
567 IAC 23.3(2)"d"

- (1) An exceedance of the indicator opacity of "no visible emissions" will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.0013 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 01-A-218-S1

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 0.004 lb/hr

Authority for Requirement: DNR Construction Permit 01-A-218-S1
567 IAC 23.3(2)"a"

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.1 gr/dscf
Authority for Requirement: DNR Construction Permit 01-A-218-S1
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall not fill the fly ash silo (EU810) and load fly ash into trucks (EU811) at the same time.
- B. The owner or operator shall develop a operating and maintenance plan for the bin vent filter including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 01-A-218-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a record of any time when both the fly ash silo was loaded and fly ash was loaded into trucks.
- B. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the bin vent filter.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 01-A-218-S1

Emission Point Characteristics

The emission point shall conform to the specifications listed below.

Stack Height (feet from the ground): 65
Stack Diameter (inches): 8
Stack Exhaust Flow Rate (scfm): 5
Stack Temperature (°F): 150
Discharge Style: Downward
Authority for Requirement: DNR Construction Permit 01-A-218-S1

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may

vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 90

Associated Equipment

Associated Emission Unit ID Number: 90

Emissions Control Equipment ID Numbers: CE91, CE92, CE93, CE94 and CE95

Emissions Control Equipment Descriptions: 2 Electrostatic Precipitators (CE91 & CE92) and
2 Wet Limestone Scrubbers (CE93 & CE94)
Over Fire Air (CE95)

Continuous Emissions Monitors ID Numbers: ME90B, ME91A, ME92, ME95A, ME96A,
ME97, ME98A, and ME93

Emission Unit vented through this Emission Point: 90

Emission Unit Description: Unit 9 Dry Bottom Tangential Fired Boiler

Raw Material/Fuel: Bituminous Coal, Subbituminous Coal, and/or Fuel Oil

Rated Capacity: 1,556 MMBtu/hr (Coal or Fuel Oil)

72.24 tons/hr Bituminous Coal

94.27 tons/hr Subbituminous Coal

1,725.6 gal/hr Fuel Oil

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limits: 20% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 80-A-191-P2

567 IAC 23.1(2)"z"

40 CFR 60 Subpart Da

⁽¹⁾ Except for one 6-minute period per hour of not greater than 27% opacity. Standard is a 6-minute average.

Pollutant: Particulate Matter (PM_{2.5})

Emission Limits: 43.59 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)

DNR Construction Permit 80-A-191-P2

Pollutant: Particulate Matter (PM₁₀)

Emission Limits: 46.68 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-191-P2

Pollutant: Federal Particulate Matter (PM)

Emission Limits: 0.03 lb/MMBtu⁽²⁾

Authority for Requirement: DNR Construction Permit 80-A-191-P2

567 IAC 23.1(2)"z"

40 CFR 60 Subpart Da

EPA PSD Permit 80-E-001 dated 1/24/80, and revision

80-E-001-S dated 9/6/83

⁽²⁾ Standard also requires 1% potential combustion concentration (99% reduction) when combusting solid fuel, and 30% potential combustion concentration (70% reduction) when combusting liquid fuel (40 CFR 60.42Da(a)). Compliance with the 0.03 lb/MMBtu standard constitutes compliance with the percent reduction requirements (40 CFR 60.48Da(a).) This standard applies at all times except during periods of startup, shutdown or malfunction (40 CFR 60.48Da(c)).

Pollutant: Sulfur Dioxide (SO₂)

Emission Limits: 70% reduction⁽³⁾

Authority for Requirement: DNR Construction Permit 80-A-191-P2

40 FR 60 Subpart Da

⁽³⁾ When combusting solid or solid-derived fuels, 30% of the potential combustion concentration (70% reduction). When combusting liquid or gaseous fuels, 0.8 lb/MMBtu and 10% of the potential combustion concentration, or 100% of the potential combustion concentration (zero percent reduction) when emissions are less than 0.20 lb/MMBtu. If different fuels are combusted simultaneously, the applicable standard is determined by proration using the formula set forth in 40 CFR 60.43Da(h)(2). Standard is a 30-day rolling average. (40 CFR 60.43Da(g)). After the initial performance test, compliance with the SO₂ emission limitations and percentage reduction requirements under 60.43Da is based on the average emission rate for 30 successive boiler operating days. A separate performance tests is completed at the end of each boiler operating day after the initial performance test, and a new 30 day average emission rate for SO₂ and a new percent reduction for SO₂ are calculated to show compliance with the standards (40 CFR 60.48Da(e)). Compliance shall be demonstrated by following the procedures in 40 CFR 60.48Da(g) and (h)).

Pollutant: Nitrogen Oxides (NO_x)

Emission Limits: 0.60 lb/MMBtu⁽⁴⁾, 65% reduction⁽⁵⁾, 0.235 lb/MMBtu⁽⁶⁾

Authority for Requirement: DNR Construction Permit 80-A-191-P2

40 CFR 60 Subpart Da

⁽⁴⁾ For bituminous coal. Limit for subbituminous coal is 0.50 lb/MMBtu, limit for oil is 0.30 lb/MMBtu, limit for gas is 0.20 lb/MMBtu, and for other fuel types, or if two or more fuels are combusted simultaneously, the NO_x BACT limit shall be the limit specified in 40 CFR 60.44Da(a) and/or as determined by the proration procedures specified in 40 CFR 60.44a(c). Standard is a 30-day rolling average. This standard applies at all times except during periods of startup, shutdown or malfunction (40 CFR 60.48Da(c)). After the initial performance test, compliance with the NO_x emission limitations under 60.44Da is based on the average emission rate for 30 successive boiler operating days. A separate performance tests is completed at the end of each boiler operating day after the initial performance test, and a new 30 day average emission rate for NO_x are calculated to show compliance with the standards (40 CFR 60.48Da(e)). Compliance shall be demonstrated by following the procedures in 40 CFR 60.48Da(g) and (h)).

⁽⁵⁾ For solid fuels. For liquid fuels, standard is a 30% reduction of potential combustion concentration. Compliance with the lb/MMBtu standard constitutes compliance with the percent reduction requirements (40 CFR 60.48a(b)).

⁽⁶⁾ As requested to remain an insignificant increase for PSD and to meet Acid Rain requirements in 40 CFR 76.6. Standard is a twelve month rolling average, and includes startup, shutdown and malfunctions.

Pollutant: Carbon Monoxide (CO)

Emission Limits: 329.2 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-191-P2

BACT Limits

Pollutant: Particulate Matter (PM)

Emission Limits: 0.03 lb/MMBtu

Authority for Requirement: DNR Construction Permit 80-A-191-P2

EPA PSD Permit 80-E-001 dated 01/24/80, and revision
80-E-001-S dated 9/6/83

Pollutant: Nitrogen Oxides (NO_x)

Emission Limits: 0.6 lb/MMBtu ⁽¹⁾

Authority for Requirement: DNR Construction Permit 80-A-191-P2

EPA PSD Permit 80-E-011 dated 01/24/80, and revision
80-E-001-S dated 9/6/83

⁽¹⁾ For bituminous coal. BACT NO_x limits are the NO_x emissions specified in NSPS Subpart Da, so limit for subbituminous coal is 0.50 lb/MMBtu, limit for oil is 0.30 lb/MMBtu, limit for gas is 0.20 lb/MMBtu, and for other fuel types, or if two or more fuels are combusted simultaneously, the NO_x BACT limit shall be the limit specified in 40 CFR 60.44a(a) and/or as determined by the proration procedures specified in 40 CFR 60.44a(c). Reference EPA permit 80-E-001 of January 24, 1980. Standard is a 30-day rolling average.

Pollutant: Sulfur Dioxide (SO₂)

Emission Limits: 0.56 lb/MMBtu ⁽²⁾, 0.45 lb/MMBtu ⁽³⁾, 92% reduction ⁽⁴⁾

Authority for Requirement: DNR Construction Permit 80-A-191-P2

EPA PSD permit 80-E-001 dated 1/24/80, revision
80-E-001-S dated 9/6/83, and LAER offset condition

⁽²⁾ 24 hour calendar day average

⁽³⁾ 0.45 lb/MMBtu 30 day rolling average

⁽⁴⁾ 30-day rolling average for the flue gas desulfurization system

Pollutant: Carbon Monoxide (CO)

Emission Limits: 720 tons/yr ⁽⁵⁾, 100 ppm ⁽⁶⁾

Authority for Requirement: DNR Construction Permit 80-A-191-P2

⁽⁵⁾ Standard is a 12-month rolling total, and includes startup, shutdown, and malfunctions.

⁽⁶⁾ Standard is averaged over a calendar day, and does not include startup, shutdown and malfunction.

Acid Rain Limits

Pollutant: Sulfur Dioxide (SO₂)

Emission Limits: Sulfur Dioxide Allowances

Authority for Requirement: 567 IAC 22.108(7) (See attached Phase II Permit in appendix)

Pollutant: Nitrogen Oxides (NO_x)

Emission Limits: See attached Phase II Acid Rain Permit

Authority for Requirement: 567 IAC 22.125(4) (Attached Phase II Acid Rain Permit)
40 CFR 76.7(a)(1)

Pollutant: Nitrogen Oxides (NO_x)

Emission Limits: 0.40 lb/MMBtu

Standard is an annual average.

Authority for Requirement: 40 CFR 76 (a)(1) Acid Rain Program

Cross-State Air Pollution Rule (CSAPR) (aka Transport Rule (TR)) Limit

Pollutant: Nitrogen Oxides (NO_x) Annual, Nitrogen Oxides (NO_x) Ozone Season,
Sulfur Dioxide (SO₂) Group 1

Emission Limits: Nitrogen Oxides and Sulfur Dioxide Allowance

Authority for Requirement: 40 CFR Part 97 (See Appendix B for requirements)

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The owner or operator shall, to the extent practicable, maintain and operate the unit in a manner consistent with good air pollution control practice for minimizing emissions at all times, including periods of startup, shutdown and malfunction.
- B. The unit shall only combust coal and/or fuel oil in this unit.

Authority for Requirement: DNR Construction Permit 80-A-191-P2

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall monitor emissions from this unit and calculate the annual emissions, in tons per year on a calendar-year basis, for a period of five years following resumption of regular operations after the change made in construction permit project (07-355). This information shall be retained by the owner or operator for a period of ten years after the construction permit project (07-355) is completed (IAC 567 33.3(18)"f"(4)).
- B. The owner or operator shall submit a report to the department within 60 days after the end of

each year during which records must be generated under 567-IAC 33.3(18)"f" (4) setting out the unit's annual emissions during the calendar year that preceded submission of the report. This shall be for a period of five years following resumption of regular operations (construction permit project 07-355). The owner or operator shall notify the DNR if the combined total annual emissions of Boiler 8 and Boiler 9, in tons per year, exceed any of the following:

1. Particulate Matter (PM) – 327.12 tpy
 2. Particulate Matter less than 10 microns (PM10) – 317.12 tpy
 3. Sulfur Dioxide (SO₂) – 3,633.45 tpy
 4. Nitrogen Oxides (NO_x) – 4,620.17 tpy
 5. Volatile Organic Compounds (VOC) – 80.46 tpy
- C. The owner or operator shall make the information required to be documented and maintained pursuant to IAC 567-33.3(18)"f" available for review upon request for inspection by the Department or the general public pursuant to the requirements for Title V operating permits contained in 567-22.107(6).
- D. The owner or operator shall maintain a file of computations to show the total hourly emission level for SO₂. The owner shall submit quarterly excess emission reports as specified in IAC 567-25.1(6).

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-191-P2

NSPS and NESHAP Requirements:

This unit is subject to the NSPS standard Subpart Da, *Standards of Performance for Electric Utility Steam Generating Unit for which Construction is Commenced After September 18, 1978*.

This unit is considered an affected source under 40 CFR 72, 73, 75, 76, 77 and 78 definitions. Therefore, this emission unit is subject to the applicable provisions of the Acid Rain Program.

Authority for Requirement: DNR Construction Permit 80-A-191-P2

This equipment is subject to the National Emission Standards for Hazardous Air Pollutants: *Coal- and Oil-Fired Electric Utility Steam Generating Units (MATS)* [40 CFR Part 63, Subpart UUUUU].

Authority for Requirement: 40 CFR Part 63 Subpart UUUUU

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 300
Stack Opening (inches, dia.): 126
Exhaust Temperature (°F): 180
Exhaust Flowrate (scfm): 430,625
Discharge Style: Vertical Unobstructed
Authority for Requirement: DNR Construction Permit 80-A-191-P2

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant – Particulate Matter (PM_{2.5})
1st Stack Test to be Completed by – November 2, 2016
2nd Stack Test to be Completed between – May 2, 2018 and May 2, 2019
Test Method – 40 CFR 51, Appendix M, 201A with 202
Authority for Requirement - 567 IAC 22.108(3)

Pollutant – Particulate Matter (PM₁₀)
1st Stack Test to be Completed by – November 2, 2016
2nd Stack Test to be Completed between – May 2, 2018 and May 2, 2019
Test Method – 40 CFR 51, Appendix M, 201A with 202
Authority for Requirement - 567 IAC 22.108(3)

Pollutant – Particulate Matter (PM)
1st 1st Stack Test to be Completed by – November 2, 2016
2nd Stack Test to be Completed between – May 2, 2018 and May 2, 2019
Test Method – 40 CFR 60, Appendix A, Method 5
40 CFR 51, Appendix M, Method 202
Authority for Requirement - 567 IAC 22.108(3)

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Continuous Emissions Monitoring:

Pollutant - Opacity

Operational Specifications - 40 CFR Part 60

Initial System Calibration/Quality Assurance – 06/22/2011

Ongoing System Calibration/Quality Assurance - 40 CFR Part 60

Reporting & Record keeping - 40 CFR Part 60. Submit all reports and petitions required by 40 CFR 60 and the DNR Construction Permit 80-A-191-P2 to the DNR in order to demonstrate compliance with the 20% opacity (visible emissions) limit

Authority for Requirement – 567 IAC 25.1(1), 567 IAC 23.3(2)"d",
567 IAC 22.108(4), and 567 IAC 22.108(15)
40 CFR 60 Subpart Da
DNR Construction Permit 80-A-191-P2

Pollutant - Sulfur Dioxide (SO₂) (Two required)

Operational Specifications - 40 CFR Part 60 (Inlet CEMS) and Part 75 (Outlet CEMS)

Initial System Calibration/Quality Assurance – 07/26 – 08/15/2005

Ongoing System Calibration/Quality Assurance - 40 CFR Part 60 (Inlet CEMS)
and Part 75 (Outlet CEMS)

Reporting & Record keeping - 40 CFR Part 60 and Part 75. Submit all reports and Petitions required by 40 CFR Part 60 and the DNR Construction Permit 80-A-191-P2 to the Iowa DNR
Send Part 75 reports to EPA in order to demonstrate compliance with continuous emission monitoring under the acid rain program and the set emission limits.

Authority for Requirement - 567 IAC 25.2, 567 IAC 23.3(3)"a"(2),
567 IAC 22.108(4), 567 IAC 22.108(15)
40 CFR 60 Subpart Da
EPA PSD permit 80-E-001 dated 1/24/80, and revision
80-E-001-S dated 9/6/83
DNR Construction Permit 80-A-191-P2

Pollutant - Nitrogen Oxides (NO_x)

Operational Specifications - 40 CFR Part 60 and Part 75

Initial System Calibration/Quality Assurance – 07/26 – 08/15/2005

Ongoing System Calibration/Quality Assurance - 40 CFR Part 60 and Part 75

Reporting & Record keeping - 40 CFR Part 60 and Part 75. Submit all reports and petitions required by 40 CFR 60 and the DNR Construction Permit 80-A-191-P2 to the Iowa DNR
Send Part 75 reports to EPA in order to demonstrate compliance with continuous emission monitoring under the acid rain program and the set emission limit

Authority for Requirement - 567 IAC 25.2
40 CFR 60 Subpart Da
DNR Construction Permit 80-A-191-P2

Pollutant – Carbon Monoxide (CO)

Operational Specifications - 40 CFR Part 75

Initial System Calibration/Quality Assurance – May 20, 2008

Ongoing System Calibration/Quality Assurance - 40 CFR Part 75

Reporting & Record keeping - 40 CFR Part 75. Submit all reports and petitions required by the DNR Construction Permit 80-A-191-P1 to the Iowa DNR in order to demonstrate compliance with continuous emission monitoring and the CO emission limits.

Authority for Requirement - 567 IAC 22.108(4), and 567 IAC 22.108(15),
DNR Construction Permit 80-A-191-P2

Other Parameters

Pollutant - Other - Carbon Dioxide (CO₂) (Two required)

Operational Specifications - 40 CFR Part 60 (Inlet CEMS) and Part 75 (Outlet CEMS)

Initial System Calibration/Quality Assurance - 8/12-8/26/94

Ongoing System Calibration/Quality Assurance - 40 CFR Part 60 (Inlet CEMS)
and Part 75 (Outlet CEMS)

Reporting & Record keeping - 40 CFR Part 60 and Part 75. Submit all reports and petitions required by 40 CFR Part 60 to the Iowa DNR. Send Part 75 reports to EPA in order to demonstrate compliance with continuous emission monitoring under the acid rain program and the set emission limits.

Authority for Requirement - 567 IAC 25.2, 567 IAC 22.108(4),
567 IAC 22.108(15)
40 CFR 60 Subpart Da
EPA PSD Permit 80-E-001 dated 1/24/80, and revision
80-E-001-S dated 9/6/83

Pollutant - Other - Flow

Operational Specifications - 40 CFR Part 75

Initial System Calibration/Quality Assurance – 08/12/2011

Ongoing System Calibration/Quality Assurance - 40 CFR Part 75

Reporting & Record keeping - 40 CFR Part 75. Submit all reports and petitions required by 40 CFR Part 75 to the EPA in order to demonstrate compliance with continuous emission monitoring under the acid rain program.

Authority for Requirement - 567 IAC 25.2, 567 IAC 22.108(4),
567 IAC 22.108(15)
EPA PSD permit 80-E-001 dated 1/24/80, and revision
80-E-001-S dated 9/6/83

The owner of this equipment or the owner's authorized agent shall provide written notice to the Director, not less than 30 days before a required performance evaluation of a continuous emission monitor. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Agency Approved Operation & Maintenance Plans Required?

Yes No

Facility Maintained Operation & Maintenance Plan Required?

Yes No

Compliance Assurance Monitoring (CAM) Plan Required?

Yes No

Authority for Requirement: 567 IAC 22.108(3)

Electrostatic Precipitator
Compliance Assurance Monitoring Plan

Facility: Muscatine Power and Water
EIQ Number: 92-3726
Emission Unit: EU 90, Tangentially Fired Boiler
Emission Point: EP 90, Boiler Stack
Control Equipment: CE91 and CE92

Monitoring Guidelines

The facility makes a commitment to take timely corrective action during periods of excursion where the indicators are out of range. A corrective action may include an investigation of the reason for the excursion, evaluation of the situation and necessary follow-up action to return operation within the indicator range. An excursion is determined by the averaged discrete data point over a period of time. An excursion does not necessarily indicate a violation of an applicable requirement. If the corrective action measures fail to return the indicators to the appropriate range, the facility will report the exceedance to the department and conduct source testing within 90 days of the exceedance to demonstrate compliance with applicable requirements. If the test demonstrates compliance with emission limits then new indicator ranges must be set for monitoring and the new ranges must be incorporated in the operating permit. If the test demonstrates noncompliance with emission limits, then the facility, within 60 days, proposes a schedule to implement corrective action to bring the source into compliance and demonstrate compliance.

Compliance Assurance Monitoring (CAM) Plan for CE91 and CE92 Electrostatic Precipitator

I. Background

- A. Emissions Unit:
Identification: EP90/EU90
Description: Unit 9 Dry Bottom Tangentially Fired Boiler
Facility: Muscatine Power & Water, 1700 Dick Drake Way, Muscatine, Iowa
52761
- B. Applicable Regulation, Emission Limit, and Monitoring Requirements:
Applicable regulation: 567 IAC 23.1(2)"z", Permit 80-A-191-P2
40 CFR 60 Subpart Da

EPA PSD permit 80-E-001 dated 1/24/80 and revision 80-E-001-S dated 9/6/83

Emission Limits: PM: 0.03 lb/MMBtu, PM₁₀: 46.68 lb/hr, PM_{2.5}: 43.59 lb/hr

- C. Current Monitoring Requirements:
 Stack Testing
 Continuous Opacity Monitoring (COMS) ME90A
 Audible Precipitator “Malfunction” Alarm

D. Current Technology: Electrostatic Precipitator

II. Monitoring Approach:

<p>1. Indicator</p> <p>Measurement Approach</p>	<p>Opacity of ESP exhaust</p>	<p>Audible Precipitator “Malfunction” Alarm</p>
	<p>COMS in ESP exhaust</p>	<p>Meters continuously display voltage and amperage on each of the eight ESP control cabinets. The ESP “Automatic Control Panel” continuously monitors voltage and current and activates an alarm message to the FDG Control Room.</p> <p>Various systems monitor and display alarm conditions in the control room. Daily visual inspections of the ESP electromechanical operation are also conducted.</p>
<p>2. Indicator Range</p>	<p>A CAM excursion will be defined as opacity exceeding 16% over any 1-hour averaging period. Except during startup, shutdown, or cleaning of control equipment as per 567 IAC 24.1(1). Corrective action will be implemented within 8 hours plus the period of time until generating capacity is available to meet consumer demand, after it is determined that the opacity monitor is functioning properly.</p>	<p>A CAM excursion will be defined as Failure of three T-R sets or more than 8 rappers per precipitator or the following T-R set operation “PPTR Fault” alarms:</p> <ul style="list-style-type: none"> • T-R over temperature >85⁰ C • T-R under voltage, which varies from <70 to <120 VAC on the transformer primary (or <18 to <30 KV on the transformer secondary) • Primary voltage <350 or >500 VAC • Over current: <ul style="list-style-type: none"> ▪ TR-1 & TR-2 (750 MA) >225 amp @ 480 VAC

		<ul style="list-style-type: none"> ▪ TR-3 & TR-4 (1,000 MA) >250 amp @ 480 VAC ▪ TR-5 & TR-6 (1,200 MA) >275 amp @ 480 VAC ▪ TR-7 & TR-8 (1,500 MA) >300 amp @ 480 VAC <p>Corrective action measures will be implemented on the occurrence of an above listed alarm. The appropriate measures for remediation will be implemented within eight hours plus the period of time until generating capacity is available to meet customer demand.</p> <p>Random T-R set failure and rapper failure (up to three T-R sets per two precipitators and 8 rappers per precipitator) will not significantly affect precipitator performance.</p>
3. Performance Criteria A. Data Representativeness	COMS installed at an alternate representative location in the ESP exhaust per 40 CFR 60, Appendix B, Performance Specification 1 (PS-1).	<p>The precipitator fault alarm was selected as the performance indicator because it is indicative of operation of the ESP in a manner necessary to comply with the emission standard.</p> <p>Continuous monitoring of operating conditions such as voltage, amperage, rapper failure, high hopper levels, high opacity, and continuous emissions monitor failure provides additional assurance of proper electromechanical operation of the ESP.</p>
B. Verification of Operational Status	Results of initial COMS performance evaluation conducted per PS-1 (July 1997).	Results of equipment verification tests conducted to calibrate the audible and visible alarm displays.
C. QA/QC Practices/Criteria	Installation and evaluation of the COMS per PS-1. The continuous opacity monitor is automatically calibrated for zero and span adjustments daily.	All instruments and control equipment will be calibrated, maintained, and operated according to the manufactures specifications.
D. Monitoring Frequency	Monitor the opacity of the ESP exhaust continuously (every 10	An audible alarm will continuously (greater than four times per hour)

	seconds).	monitor T-R set failure, rapper control malfunction T-R temperature, T-R voltage and T-R current levels.
E. Data Collection Procedures	Set up the data acquisition system (DAS) to retain all 6-minute average opacity data.	Maintain records of T-R and rapper failures and precipitator fault alarms exceeding CAM thresholds for longer than one hour.
F. Averaging period	Use the 10-second opacity data to calculate 6-minute averages. Use the 6-minute averages to calculate hourly block average opacity for the CAM.	N/A

III. Quality Improvement Plan (QIP):

A Quality Improvement Plan (QIP) will be required to be submitted to the IDNR if an accumulation of excursions of either the opacity indicator or the various ESP operation alarms exceed 5 percent of the boiler's normal operating time for a 6-month reporting period. All requirements in 40 CFR 64.8(b) shall be fulfilled if a QIP is required.

IV. Quality Assurance and Quality Control:

In addition to monitoring the opacity and ESP operation alarms, MP&W will conduct the following activities to assure compliance. The following monitoring is not required during periods of time greater than one day in which the source does not operate.

- A. Monitor detection equipment, including alarm displays in the control room, which alert operators to irregular operating conditions such as high hopper levels, high opacity, and continuous opacity monitoring system (COMS) failure.
- B. Conduct daily inspections of the ESP electromechanical operation:
 - Rapper operation
 - Ash removal system operation
 - ESP air leakage
 - Arcing
- C. Each Major Scheduled Unit Outage (typically lasting four or more weeks):
 - Check and correct plate/electrode alignment
 - Inspect condition of collection surfaces, insulators, electrical contacts, rappers, doors and seals.
 - Evaluate and correct ash transport system wear areas
 - Inspect internal structural components

Corrective action to correct abnormal operating conditions will be implemented within 8 hours plus the period of time until generating capacity is available to meet consumer demand.

D. Record Keeping and Recording:

- Records of all daily inspections and any actions resulting from these inspections will be kept for five years.
- Records of all planned unit outage inspections and any actions resulting from these inspections will be kept for five years.
- MP&W shall record the summary information on the number, duration and cause (including unknown cause, if applicable) of excursions or exceedances, as applicable, and the corrective actions taken. 40 CFR 64.9(a)(2)(i).
- MP&W shall record the summary information on the number, duration and cause (including unknown cause, if applicable) for monitor downtime incidents (other than downtime associated with zero and span or other daily calibration checks, if applicable). 40 CFR 64.9(a)(2)(ii).
- All excursions and monitor downtime incidents will be reported in semi-annual monitoring reports and annual compliance certifications.

E. Quality Control:

- All instruments and equipment will be calibrated, maintained, and operated according to the manufacturer's specifications.
- An inventory of spare parts will be maintained. Parts will be re-ordered as they are used.

Authority for requirement: 567 IAC 22.108(3)
40 CFR 64

Emission Point ID Number: 912A (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 912A

Emission Units vented through this Emission Point: 912A

Emission Unit Description: Reversing Conveyor A – Discharge/Load

Raw Material/Fuel: Synthetic Gypsum

Rated Capacity: 20 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limits: 40%

Authority for Requirement: DNR Construction Permit 13-A-157
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limits: 0.00121 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-157

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

A. There are no operating limits established by this permit.

Authority for Requirement: DNR Construction Permit 13-A-157

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain records on the moisture content of the material handled in this emissions unit.
- B. The PM_{2.5} emission rate established in Permit Condition 10 is based on the maximum capacity of the unit, two transfer points and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10%, provided by applicant

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-157

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 912B (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 912B

Emission Units vented through this Emission Point: 912B

Emission Unit Description: Reversing Conveyor B – Discharge/Load

Raw Material/Fuel: Synthetic Gypsum

Rated Capacity: 20 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limits: 40%

Authority for Requirement: DNR Construction Permit 13-A-158
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limits: 0.00121 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-158

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

A. There are no operating limits established by this permit.

Authority for Requirement: DNR Construction Permit 13-A-158

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain records on the moisture content of the material handled in this emissions unit.
- B. The PM_{2.5} emission rate established in Permit Condition 10 is based on the maximum capacity of the unit, two transfer points and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10%, provided by applicant

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-158

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 916B (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 916A and 916B

Emission Units vented through this Emission Point: 916A

Emission Unit Description: Loadout Conveyor Discharge/Radial Stacker Conveyor Load

Raw Material/Fuel: Synthetic Gypsum

Rated Capacity: 40 tons/hr

Emission Units vented through this Emission Point: 916B

Emission Unit Description: Radial Stacker Conveyor Storage Pile

Raw Material/Fuel: Synthetic Gypsum

Rated Capacity: 40 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limits: 40%

Authority for Requirement: DNR Construction Permit 13-A-159
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limits: 0.0012 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-159

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the emissions unit is limited to operating between 7:00 AM and 7:00 PM.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the amount of synthetic gypsum that can be handled in this emissions unit is limited to 20 tons per hour.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-159

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when the emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of the following: 1.) the amount of synthetic gypsum handled, 2.) the number of hours that the emissions unit operated, and 3.) the average amount of synthetic gypsum handled in tons per hour (#1/ #2).
- C. The owner or operator shall maintain records on the moisture content of the material handled in this emissions unit.
- D. The PM_{2.5} emission rate established in Permit Condition 10 is based on the limited hourly capacity of the unit, two transfer points, and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10%, provided by applicant

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-159

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 919 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 919, 919A and 919B

Emission Units vented through this Emission Point: 919

Emission Unit Description: Synthetic Gypsum Storage Pile Truck Load Traffic and Wind Erosion

Raw Material/Fuel: Synthetic Gypsum

Rated Capacity: 40 Tons/hr

Emission Units vented through this Emission Point: 919A

Emission Unit Description: Synthetic Gypsum Storage Pile Truck Loading

Raw Material/Fuel: Synthetic Gypsum

Rated Capacity: 40 tons/hr

Emission Units vented through this Emission Point: 919B

Emission Unit Description: Synthetic Gypsum Storage Pile Radial Stacker, Pile Formation

Raw Material/Fuel: Synthetic Gypsum

Rated Capacity: 40 tons/hr; maximum storage pile size: 2.0 acres

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limits: 40%

Authority for Requirement: DNR Construction Permit 13-A-146
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5}) for EU919A and Radial Stacker

Emission Limits: 0.00121 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-146

Pollutant: Particulate Matter (PM_{2.5}) for EU919B

Emission Limits: 0.0125 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-146

Pollutant: Particulate Matter (PM_{2.5}) for Wind Erosion and Truck traffic around pile

Emission Limits: For these emissions units the limits are expressed in the form of a work practice instead of an emission limit. See Operating Limits section of this permit for the work practice requirements.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-146

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

Operating Limits:

- A. The Synthetic Gypsum Truck Loading operation (EU919A) associated with the synthetic gypsum storage pile is limited to operating between 7:00 AM and 7:00 PM.
- B. The Radial Stacker associated with the synthetic gypsum storage pile is limited to operating between 7:00 AM and 7:00 PM.
- C. Pile formation operations associated with the synthetic gypsum storage pile are limited to operating between 7:00 AM and 7:00 PM.
- D. A maximum of nine trucks shall be loaded with synthetic gypsum per day.
- E. The amount of synthetic gypsum loaded out shall not exceed 78,840 tons per rolling 12-month period.
- F. The ground surface area of the synthetic gypsum storage pile (EU919) shall not exceed 0.5 acre (21,780 square feet).
- G. The maximum silt loading content of any paved road used by the trucks to haul away synthetic gypsum shall not exceed 13.5 g/m².
- H. The silt content of the synthetic gypsum shall not exceed 10% by weight.
- I. Operating limits A through H go into effect starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-146

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when the following units operated: Synthetic Gypsum Truck Loading, Synthetic Gypsum Radial Stacker, Synthetic Gypsum Storage Pile formation. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record on the number of trucks loaded out with synthetic gypsum.
- C. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain the following monthly records:
 - i. the amount of synthetic gypsum loaded out (tons); and
 - ii. the rolling 12-month total of the amount of synthetic gypsum loaded out (tons).
- D. The owner or operator shall maintain records on the moisture content and the silt content of the material handled in this emissions unit.
- E. The owner or operator shall maintain records on the surface area of the synthetic gypsum storage pile. By either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall submit to the Department its methodology for determining the size of the synthetic gypsum storage pile. After the synthetic gypsum storage pile is measured using its methodology, the owner or operator shall submit a report to the Department by November 1, 2013 indicating the size of the synthetic gypsum storage pile.
- F. For any paved road used by trucks to haul away synthetic gypsum, silt loading testing shall be done at least quarterly between April 1st through September 30th to assure that silt loading does not exceed 13.5 g/m². The owner or operator shall maintain records on the date and results of the silt loading test. After 2 years of silt loading tests, the owner or operator can request a re-evaluation of the testing frequency.
- G. For the Synthetic Gypsum Truck Loading (EU919A), the PM_{2.5} emissions rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and the following equation and parameters :

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10%, provided by applicant.

- H. For the Synthetic Gypsum Radial Stacker, the PM_{2.5} emissions rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and the following equation and parameters :

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 10%, provided by applicant.

- I. For the Synthetic Gypsum Storage Pile Formation, the PM_{2.5} emission rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and the following equation and parameters :

$$E = [k (sL)^{0.91} (W)^{1.02}] (1-P/4N) \quad (\text{AP-42, Equation 2 from Section 13.2.1.3, 01/2011})$$

Where:

k = particle size multiplier (0.00054 lb/VMT), AP 42 Table 13.2.1-1

sL = silt loading, 13.5 g/m², provided by the applicant

W = 31.5 tons, average weight of vehicles, provided by the applicant

P = 110, annual number of days of precipitation exceeding 0.01 inch

N = 365, number of days in the averaging period.

The maximum vehicle miles traveled (VMT) for this operation is 0.032 VMT per hour.

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-146

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 920

Associated Equipment

Associated Emission Unit ID Number: 920
Emissions Control Equipment ID Number: CE922
Control Equipment Description: Bin Vent Filter

Emission Unit vented through this Emission Point: 920
Emission Unit Description: Fly Ash Silo Vent Filter Exhaust
Raw Material/Fuel: Fly Ash
Rated Capacity: 40 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 80-A-201-S1
567 IAC 23.3(2)"d"

⁽¹⁾ An exceedance of the indicator opacity of (10%) will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.0058 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-201-S1

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 0.071 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-201-S1

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.02 gr/dscf

Authority for Requirement: DNR Construction Permit 80-A-201-S1

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

- A. The owner or operator shall develop a operating and maintenance plan for the bin vent filter including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 80-A-201-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the bin vent filter.

Authority for Requirement: DNR Construction Permit 80-A-201-S1

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 112.7

Stack Opening (inches, dia.): 49 x 64

Exhaust Temperature (°F): 150

Exhaust Flowrate (scfm): 417

Discharge Style: Horizontal

Authority for Requirement: DNR Construction Permit 80-A-201-S1

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 920A

Associated Equipment

Associated Emission Unit ID Number: CE920
Emissions Control Equipment ID Number: CE921
Control Equipment Description: Cartridge Fabric

Emission Unit vented through this Emission Point: CE920
Emission Unit Description: Cyclone Separator Dust Collector
Raw Material/Fuel: Fly Ash
Rated Capacity: 20 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 80-A-200-S1
567 IAC 23.3(2)"d"

- ⁽¹⁾ An exceedance of the indicator opacity of "no visible emissions" will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.122 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 80-A-200-S1

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 0.250 lb/hr

Authority for Requirement: DNR Construction Permit 80-A-200-S1

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.02 gr/dscf

Authority for Requirement: DNR Construction Permit 80-A-200-S1

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

- A. By no later than sixty (60) days from the date of the permit issuance, the stacks for this emissions unit (CE920) shall be raised to 13.83 feet and shall be made vertical, unobstructed.
- B. EP920A and EP920B are the two emission points for the fly ash vacuum blowers. Only one of the two emission points shall operate at the same time.
- C. For the control equipment, the cartridge filter media shall be Dollinger's Fiberloc 063 or Fiberloc 195 filter media or a filter media with an equivalent high efficiency for particulate control.
- D. The owner or operator shall develop a operating and maintenance plan for the cartridge filter including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 80-A-200-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall properly operate and maintain equipment to monitor the differential pressure drop across the cartridge filter. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. The owner or operator shall monitor the pressure drop across the cartridge filter, in inches of water, continuously. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall follow its procedure of replacing the filter media when the differential pressure across the cartridge filter exceeds 30 inches water column. The cartridge filter shall be replaced before the differential pressure exceeds 35 inches water column. A record shall be maintained on when the cartridge filter is replaced.
- D. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the cartridge filter.
- E. The owner or operator shall submit a notification to the Iowa DNR, Air Quality Bureau when the modification to the stack height has been completed.

Authority for Requirement: DNR Construction Permit 80-A-200-S1

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 13.83
Stack Opening (inches, dia.): 18
Exhaust Temperature (°F): 190
Exhaust Flowrate (scfm): 2,920
Discharge Style: Vertical Unobstructed
Authority for Requirement: DNR Construction Permit 80-A-200-S1

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

Pollutant - PM
Stack Test to be Completed by – November 2, 2017
Test Method - 40 CFR 60, Appendix A, Method 5
40 CFR 51, Appendix M, Method 202
Authority for Requirement – 567 IAC 22.108(3)

The owner of this equipment or the owner’s authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 920B

Associated Equipment

Associated Emission Unit ID Number: CE920
Emissions Control Equipment ID Number: CE920
Control Equipment Description: Cartridge Fabric

Emission Unit vented through this Emission Point: CE920
Emission Unit Description: Cyclone Separator Dust Collector
Raw Material/Fuel: Fly Ash
Rated Capacity: 40 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 13-A-147
567 IAC 23.3(2)"d"

⁽¹⁾ An exceedance of the indicator opacity of "no visible emissions" will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.122 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-147

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 0.250 lb/hr

Authority for Requirement: DNR Construction Permit 13-A-147

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.02 gr/dscf

Authority for Requirement: DNR Construction Permit 13-A-147

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

- A. By no later than sixty (60) days from the date of the permit issuance, the stacks for this emissions unit (CE920) shall be raised to 13.83 feet and shall be made vertical, unobstructed.
- B. EP920A and EP920B are the two emission points for the fly ash vacuum blowers. Only one of the two emission points shall operate at the same time.
- C. For the control equipment, the cartridge filter media shall be Dollinger's Fiberloc 063 or Fiberloc 195 filter media or a filter media with an equivalent high efficiency for particulate control.
- D. The owner or operator shall develop an operating and maintenance plan for the cartridge filter including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: DNR Construction Permit 13-A-147

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the cartridge filter. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- B. The owner or operator shall monitor the pressure drop across the cartridge filter, in inches of water, continuously. This requirement shall not apply on the days that the equipment is not in operation.
- C. The owner or operator shall follow its procedure of replacing the filter media when the differential pressure across the cartridge filter exceeds 30 inches water column. The cartridge filter shall be replaced before the differential pressure exceeds 35 inches water column. A record shall be maintained on when the cartridge filter is replaced.
- D. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the cartridge filter.

Authority for Requirement: DNR Construction Permit 13-A-147

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 13.83

Stack Opening (inches, dia.): 18

Exhaust Temperature (°F): 190

Exhaust Flowrate (scfm): 2,920

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 13-A-147

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Stack Testing:

- Pollutant – Particulate Matter (PM)
- Stack Test to be Completed by – November 2, 2017
- Test Method - 40 CFR 60, Appendix A, Method 5
40 CFR 51, Appendix M, Method 202
- Authority for Requirement – 567 IAC 22.108(3)

The owner of this equipment or the owner’s authorized agent shall provide written notice to the Director, not less than 30 days before a required stack test. Results of the test shall be submitted in writing to the Director in the form of a comprehensive report within 6 weeks of the completion of the testing. 567 IAC 25.1(7)

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement – 567 IAC 22.108(3)

Emission Point ID Number: 924 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 924

Control Equipment Description: Enclosed Loading Spout

Emission Unit vented through this Emission Point: 924

Emission Unit Description: Dry Fly Ash Truck

Raw Material/Fuel: Fly Ash

Rated Capacity: 80 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40%

Authority for Requirement: DNR Construction Permit 13-A-148

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.032 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-148

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

A. Trucks shall be loaded by means of an enclosed loading spout.

B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the emissions unit is limited to operating between 7:00 AM and 4:00 PM.

C. The owner or operator shall develop a operating and maintenance plan for the enclosed loading spout including a preventative maintenance schedule that is consistent with the

manufacturer's instructions for routine and long-term maintenance.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-148

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the enclosed loading spout.
- C. The owner or operator shall maintain records on the moisture content of the material handled in this emissions unit.
- D. For the Dry Fly Ash Truck Unloading (EU924), the PM2.5 emissions rate established in the Emission Limitations section of this permit is based on the maximum capacity of the unit and the following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} (1 - 0.8) \text{ (AP-42, Equation 1 from Section 13.2.4.3, 11/2006)}$$

Where:

E = emission factor in lbs PM2.5/ ton material

k = particle size multiplier, 0.053 for PM2.5

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 0.5%, provided by applicant.

0.8 = control efficiency credit given to enclosed loading spout

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-148

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 860 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 860, 860B, 860C and 860D

Emission Units vented through this Emission Point: 860

Emission Unit Description: Ash/Slag Storage Pile Wind Erosion

Raw Material/Fuel: Ash/Slag

Rated Capacity: Maximum Pile Size 3 acres

Emission Units vented through this Emission Point: 860B

Emission Unit Description: Ash/Slag Loading

Raw Material/Fuel: Ash/Slag

Rated Capacity: 40 tons/hr

Emission Units vented through this Emission Point: 860C

Emission Unit Description: Ash/Slag Unloading

Raw Material/Fuel: Ash/Slag

Rated Capacity: 80 tons/hr

Emission Units vented through this Emission Point: 860D

Emission Unit Description: Ash/Slag Storage Pile Bulldozing

Raw Material/Fuel: Ash/Slag

Rated Capacity: 3 Dozers

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40%

Authority for Requirement: DNR Construction Permit 13-A-143

Pollutant: Particulate Matter (PM_{2.5}) for EU860B and EU860C

Emission Limit(s): 0.0031 lb/hr (each)

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-143

Pollutant: Particulate Matter (PM_{2.5}) for EU860D

Emission Limit(s): 0.0742 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-143

Pollutant: Particulate Matter (PM_{2.5}) for Ash/Slag Storage Pile Wind Erosion

Emission Limit(s): For this emissions unit the limits are expressed in the form of a work practice instead of an emission limit. See the Operating Limits section of this permit for the work practice requirements.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-143

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the Ash/Slag Truck Loading operations (EU860B) associated with the ash/slag storage pile are limited to operating between 7:00 AM and 7:00 PM.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the Ash/Slag Truck Unloading operations (EU860C) associated with the ash/slag storage pile are limited to operating between 7:00 AM and 7:00 PM.
- C. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the Ash/Slag Storage Pile Bulldozing operation (EU860D) is limited to operating between 7:00 AM and 7:00 PM.
- D. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, only one bulldozer shall be in operation at any one time on the ash/slag storage pile.
- E. The silt content of the material stored in the ash/slag storage pile (EU860) shall not exceed 1.66% by weight.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-143

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when the following units operated: Ash/Slag Truck Loading (EU860B), Ash/Slag Truck Unloading (EU860C) and Ash/Slag Storage Pile Bulldozing (EU860D). This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.

B. The owner or operator shall maintain records on the moisture content and the silt content of the material handled in this emissions unit.

C. For the Ash/Slag Truck Loading (EU860B), the PM_{2.5} emissions rate established in the Emissions Limits section of this permit is based on the maximum capacity of the unit and the following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \text{ (AP-42, Equation 1 from Section 13.2.4.3, 11/2006)}$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 8.44%, provided by applicant.

D. For the Ash/Slag Truck Unloading (EU860C), the PM_{2.5} emissions rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and the following equation and parameters :

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \text{ (AP-42, Equation 1 from Section 13.2.4.3, 11/2006)}$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 8.44%, provided by applicant.

E. For the Ash/Slag Pile Bulldozing (EU860D), the PM_{2.5} emission rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and the following equation and parameters:

$$ER = (0.105) 5.7 (s)^{1.2} / (M)^{1.3} \text{ (AP-42, Table 11.9-1, bulldozing overburden, 7/1998)}$$

Where:

ER = emission rate, lbs PM_{2.5} per hour

0.105 = scaling factor for PM_{2.5}

s = material silt content, 1.66%, based on analysis of material silt content provided by the applicant; and

M = minimum material moisture content, 8.44%, based on analysis of material moisture content, provided by applicant.

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-143

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 925 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 924

Emission Units vented through this Emission Point: 924
Emission Unit Description: Dry Fly Ash Truck - Unloading
Raw Material/Fuel: Fly Ash
Rated Capacity: 20 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40 %

Authority for Requirement: DNR Construction Permit 01-A-456-S1
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.040 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 01-A-456-S1

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the emissions unit is limited to operating between 7:00 AM and 4:00 PM.

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 01-A-456-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. The owner or operator shall maintain records on the moisture content of the material handled in this emissions unit.
- C. For the Dry Fly Ash Truck Unloading (EU924), the PM_{2.5} emissions rate established in Permit Condition 10 is based on the maximum capacity of the unit and the following equation and parameters :
 - E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} (AP-42, Equation 1 from Section 13.2.4.3, 11/2006)
 - Where:
 - E = emission factor in lbs PM_{2.5}/ ton material
 - k = particle size multiplier, 0.053 for PM_{2.5}
 - U = mean wind speed, 7.5 miles per hour, provided by the applicant; and
 - M = minimum material moisture content, 0.5%, provided by applicant.

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 01-A-456-S1

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

- Agency Approved Operation & Maintenance Plan Required?** Yes No
- Facility Maintained Operation & Maintenance Plan Required?** Yes No
- Compliance Assurance Monitoring (CAM) Plan Required?** Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 926

Associated Equipment

Associated Emission Unit ID Numbers: 924, 926A1, and 926B

Emissions Control Equipment ID Number: CE926

Control Equipment Description: Fabric Filter Dust Collector

Emission Units vented through this Emission Point: 924

Emission Unit Description: Dry Fly Ash Truck Load Out

Raw Material/Fuel: Fly Ash

Rated Capacity: 100 tons/hr

Emission Units vented through this Emission Point: 926A1

Emission Unit Description: 10-Ton Fly Ash Hopper

Raw Material/Fuel: Fly Ash

Rated Capacity: 30 tons/hr

Emission Units vented through this Emission Point: 926B

Emission Unit Description: 150-Ton Fly Ash Silo

Raw Material/Fuel: Fly Ash

Rated Capacity: 30 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 01-A-457-S5
567 IAC 23.3(2)"d"

⁽¹⁾ An exceedence of the indicator opacity of 10% will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedence. If exceedences continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.018 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 01-A-457-S5

Pollutant: Particulate Matter (PM₁₀)
Emission Limit(s): 0.411 lb/hr
Authority for Requirement: DNR Construction Permit 01-A-457-S5

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.02 gr/dscf
Authority for Requirement: DNR Construction Permit 01-A-457-S5
567 IAC 23.3(2)"a"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

- A. This emissions unit shall be limited to operating between 7:00 AM and 4:00 PM.
- B. The differential pressure drop across the baghouse shall be maintained between 1 and 10 inches water column while the equipment is in operation.
- C. The owner or operator shall develop an operating and maintenance plan for the baghouse including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.
- D. There are three diesel internal combustion engines that are used to provide power to the fly ash handling equipment. These engines are identified as EU928A, EU928B, and EU928C. These engines shall be shut down and replaced by electric motors by no later than October 12, 2013.

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 01-A-457-S5

Reporting & Record keeping:

All records as required by this permit shall be kept on-site for a minimum of five (5) years and shall be available for inspection by the DNR. Records shall be legible and maintained in an orderly manner.

- A. The owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. The owner or operator shall properly operate and maintain equipment to periodically monitor the differential pressure drop across the baghouse. The monitoring devices and any recorders shall be installed, calibrated, operated and maintained in accordance with the manufacturer's recommendations, instructions and operating manuals or per written facility specific operation and maintenance plan.
- C. The owner or operator shall collect and record the pressure drop across the baghouse, in inches of water, at least once per day. This requirement shall not apply on the days that the equipment is not in operation.
- D. The owner or operator shall maintain a record of all inspections and maintenance and any action resulting from the inspection and maintenance of the baghouse.

E. The owner or operator shall submit a notification to the Iowa DNR, Air Quality Bureau when the diesel IC engines EU928A, EU928B, and EU928C have been permanently shut down.

Authority for Requirement: DNR Construction Permit 01-A-457-S5

Emission Point Characteristics

The emission point shall conform to the specifications listed below.

Stack Height (feet from the ground): 19.3

Stack Diameter (inches): 10 x 10

Stack Exhaust Flow Rate (scfm): 2,400

Stack Temperature (°F): Ambient

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 01-A-457-S5

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 926A2 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 926A2

Control Equipment Description: Wind Screen

Emission Units vented through this Emission Point: 926A2

Emission Unit Description: Fly Ash Hopper Loading

Raw Material/Fuel: Fly Ash

Rated Capacity: 30 tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40 %

Authority for Requirement: DNR Construction Permit 04-A-617-S1
567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.0084 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 04-A-617-S1

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 0.1 tons/yr

Authority for Requirement: DNR Construction Permit 04-A-617-S1

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.2 tons/yr⁽¹⁾

Authority for Requirement: DNR Construction Permit 04-A-617-S1

⁽¹⁾ Pursuant to the Federal PSD permit issued on January 24, 1980 for boiler #9 and the LAER agreement between the Department and Muscatine Power and Water, signed by the Department on December 28, 1979, all ash handling associated with boiler #9 is subject to a 0.02 gr/scf standard for particulate matter. Compliance with this standard shall be demonstrated using USEPA Method 5.

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All

persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below:

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, this emissions unit is limited to operating between 7:00 AM and 4:00 PM.
- B. This source shall not operate more than 500 hours per 12 month rolling average.

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 04-A-617-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. The owner or operator shall maintain the following monthly records:
 - i. the number of hours that the emissions unit operated; and
 - ii. the rolling 12-month total number of hours that the emissions unit operated.
- C. The owner or operator shall maintain records on the moisture content of the material handled in this emissions unit.
- D. The PM_{2.5} emission rate established in the Emission Limits section of this permit is based on the maximum capacity of the unit and following equation and parameters:

$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 2.5 %, provided by applicant

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 04-A-617-S1

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 926A3 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 926A3

Emission Units vented through this Emission Point: 926A3
Emission Unit Description: Fly Ash Pile Formation
Raw Material/Fuel: Fly Ash
Rated Capacity: 4.5 Tons/hr

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40 %

Authority for Requirement: DNR Construction Permit 04-A-618-S1
567 IAC 23.3(2)"d"

Pollutant: State Particulate Matter (PM_{2.5})

Emission Limit(s): 0.00095 lb/hr

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 04-A-618-S1

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 0.01 tons/yr

Authority for Requirement: DNR Construction Permit 04-A-618-S1

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.02 tons/yr ⁽¹⁾

Authority for Requirement: DNR Construction Permit 04-A-618-S1

⁽¹⁾ Pursuant to the Federal PSD permit issued on January 24, 1980 for boiler #9 and the LAER agreement between the Department and Muscatine Power and Water, signed by the Department on December 28, 1979, all ash handling associated with boiler #9 is subject to a 0.02 gr/scf standard for particulate matter. Compliance with this standard shall be demonstrated using USEPA Method 5.

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below:

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the emissions unit is limited to operating between 7:00 AM and 4:00 PM.
- B. The emissions unit is limited to operating a maximum of 500 hours in any rolling 12-month period.
- C. The storage pile formation shall be formed and consumed in calendar day. That is, there shall not be a pile formation remaining at the end of each calendar day.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 04-A-618-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. The owner or operator shall maintain the following monthly records:
 - i. the number of hours that the emissions unit operated; and
 - ii. the rolling 12 month total of the number of hours that the emissions unit operated.
- C. The owner or operator shall maintain records on the moisture content of the material handled in this emissions unit.
- D. The PM_{2.5} emission rate established in Permit Condition 10 is based on the maximum capacity of the unit and following equation and parameters:
$$E = (k) (0.0032) (U/5)^{1.3} / (M/2)^{1.4} \quad (\text{AP-42, Equation 1 from Section 13.2.4.3, 11/2006})$$

Where:

E = emission factor in lbs PM_{2.5}/ ton material

k = particle size multiplier, 0.053 for PM_{2.5}

U = mean wind speed, 7.5 miles per hour, provided by the applicant; and

M = minimum material moisture content, 2.5 %, provided by applicant

Authority for Requirement: Muscatine PM_{2.5} SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 04-A-618-S1

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 926A4 (Fugitive)

Associated Equipment

Associated Emission Unit ID Numbers: 926A4

Control Equipment: Dust Suppressant

Emission Units vented through this Emission Point: 926A4

Emission Unit Description: Vehicle Traffic from Fly Ash Pile to Hopper

Raw Material/Fuel: Fly Ash

Rated Capacity: 851 VMT/12-month rolling period

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: DNR Construction Permit 04-A-619-S1
567 IAC 23.3(2)"c"

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): For this emissions unit the limits are expressed in the form of a work practice instead of an emission limit. See the Operating Limits section of this permit for the work practice requirements.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 04-A-619-S1

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 2.0 tons/yr

Authority for Requirement: DNR Construction Permit 04-A-619-S1

Pollutant: Particulate Matter (PM)

Emission Limit(s): 5.3 tons/yr

Authority for Requirement: DNR Construction Permit 04-A-619-S1

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below:

Operating Limits:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the emissions unit is limited to operating between 7:00 AM and 4:00 PM.
- B. The transport vehicle used in moving fly ash from EU-926A3 to EU-926A2 is limited to traveling a maximum of 851 miles per 12-month rolling period.
- C. For Fly Ash Bag Storage Reclamation Area:
 - i. Fugitive emissions from the fly ash bag storage reclamation area shall be controlled by applying water or a chemical dust suppressant. This area is limited to the area traversed by the endloader while removing fly ash from the storage bag(s), EU-926A3, and depositing it in the system hopper, EU-926A2. Applications of the selected dust suppressant will occur daily whenever the reclamation process is operated. Record keeping will be done in accordance with requirements described in Condition 2 below. A control efficiency of 80% shall be maintained on the fly ash bag storage reclamation area. Muscatine Power and Water may elect to use any dust suppressant that is capable of achieving the 80% control efficiency. If water is used as the suppressant the water spray rate shall be a minimum of 0.23 gallons per square yard. If a chemical suppressant is used Muscatine Power and Water shall follow the chemical manufactures recommendations to achieve 80% control.
 - ii. If the selected dust suppressant cannot be applied because the ambient air temperature (as measured at the facility during daylight operating hours) will be lower than 32 degrees F or weather conditions are adequate to control fugitive emissions, or the application of the dust suppressant in combination with weather conditions could create an unmarketable fly ash product, then the dust suppressant application shall resume as soon after the scheduled application as the conditions preventing the application have abated.
 - iii. Dust suppression need not occur when a rain gage located at the site indicates that at least 0.2 inches of precipitation (water equivalent) has occurred within the preceding 24-hr time period or the road will not be used on a given day.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 04-A-619-S1

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. By no later than July 14, 2013, the owner or operator shall maintain a daily record of when this emissions unit operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.

- B. The owner or operator shall maintain the following monthly records on this road segment:
 - i. The vehicle miles traveled; and
 - ii. The rolling 12-month total of the vehicle miles traveled.

- C. The owner or operator shall maintain records on this road segment. These records shall show the following information:
 - i. The dates that the road was treated by water or a chemical dust suppressant.
 - ii. The amount of water applied.
 - iii. If applicable, the name of the chemical dust suppressant used.
 - iv. If applicable, the application rate and the dilution ratio of the chemical dust suppressant used.
 - v. The ambient air temperature and the amount of precipitation (water equivalent) received at the site over the last 24 hour period.
 - vi. Other indications of why water or a dust suppressant could not be applied to the road.

Authority for Requirement: DNR Construction Permit 04-A-619-S1

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

- Agency Approved Operation & Maintenance Plan Required?** Yes No
- Facility Maintained Operation & Maintenance Plan Required?** Yes No
- Compliance Assurance Monitoring (CAM) Plan Required?** Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 927

Associated Equipment

Associated Emission Unit ID Numbers: 927

Emission Units vented through this Emission Point: 927

Emission Unit Description: Portable Diesel Tank – Breathing Loss & Working Loss

Raw Material/Fuel: Diesel Fuel

Rated Capacity: 300 Gallon Tank

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit: 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 01-A-458
567 IAC 23.3(2)"d"

⁽¹⁾ An exceedence of the indicator opacity of (25%) will required the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedence. If exceedences continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter

Emission Limit(s): 0.1 gr/dscf

Authority for Requirement: DNR Construction Permit 01-A-458
567 IAC 23.3(2)"a"

Emission Point Characteristics

The emission point shall conform to the specifications listed below.

Stack Height (feet from the ground): NA

Stack Diameter (inches): NA

Stack Exhaust Flow Rate (scfm): NA

Stack Temperature (°F): NA

Discharge Style: NA

Authority for Requirement: DNR Construction Permit 01-A-458

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall

submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 7890

Associated Equipment

Associated Emission Unit ID Numbers: 7890

Emission Units vented through this Emission Point: 7890

Emission Unit Description: Portable Gasoline IC Engines for Non-emergency Power

Unit Number	Manufacturer/Model	Rated Capacity (HP)	Raw Material/Fuel	Construction Date
1	Onan 848M-GA018	18	Unleaded Gasoline	Prior to 07/01/08
2	Honda EB 4000	10		Prior to 07/01/08
3	Stihl TS400	1		Prior to 07/01/08
4	Stihl TS410	1		Prior to 07/01/08
5	Honda GX 160	5.5		Prior to 07/01/08
6	Honda GX 160	5.5		Prior to 07/01/08
7	Honda GX 160	5.5		After 07/01/08
8	Honda GX 160	5.5		After 07/01/08
9	Honda GX 160	5.5		After 07/01/08
10	Honda PT2A	4.8		After 07/01/08
11	Honda PT2A	4.8		After 07/01/08
12	Honda GX340	11		Prior to 07/01/08

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 13-A-150
567 IAC 23.3(2)"d"

- ⁽¹⁾ An exceedance of the indicator opacity of 10% will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.0604 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-150

Pollutant: Particulate Matter (PM)
Emission Limit(s): 0.1 gr/scf
Authority for Requirement: DNR Construction Permit 13-A-150
567 IAC 23.3(2)"a"

Pollutant: Sulfur Dioxide (SO₂)
Emission Limit(s): 500 ppmv
Authority for Requirement: DNR Construction Permit 13-A-150
567 IAC 23.3(3)"e"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, each of the engines covered by this permit is limited to operating sixteen hours per day from 6 AM to 10 PM.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-150

Reporting & Record Keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources.

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when the engines operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.

Authority for Requirement: DNR Construction Permit 13-A-150

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): Varies
Stack Opening inches, dia.): Varies
Exhaust Temperature (°F): 800
Exhaust Flowrate (scfm): Varies
Discharge Style: Varies
Authority for Requirement: DNR Construction Permit 13-A-150

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the

temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 7892

Associated Equipment

Associated Emission Unit ID Numbers: 7892

Emission Units vented through this Emission Point: 7892

Emission Unit Description: Portable Diesel IC Engine for Non-emergency Power

Raw Material/Fuel: Diesel Fuel

Rated Capacity: 105 HP

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 13-A-151
567 IAC 23.3(2)"d"

⁽¹⁾ An exceedance of the indicator opacity of 10% will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.187 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-151

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.1 gr/dscf

Authority for Requirement: DNR Construction Permit 13-A-151
567 IAC 23.3(2)"a"

Pollutant: Sulfur Dioxide (SO₂)

Emission Limit(s): 2.5 lb/MMBtu

Authority for Requirement: DNR Construction Permit 13-A-151
567 IAC 23.3(3)"b"(2)

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

- A. This engine is limited to burning #1 or #2 diesel fuel oil only.
- B. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, this engine is limited to operating sixteen hours per day from 6 AM to 10 PM.
- C. The maximum sulfur content of the fuel oil burned in this engine shall not exceed 0.5% by weight.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-151

Reporting & Record keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources:

- A. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, the owner or operator shall maintain a daily record of when the engines operated. This record shall include the following information: date of operation, initial start up time of operation and final end time of operation.
- B. The owner or operator shall perform an analysis and shall maintain records on the sulfur content of each shipment of oil received. Alternatively, the owner or operator shall have the oil supplier provide analyses on the sulfur content of the oil received. The analysis does not have to be for each shipment of oil received, but shall be documented by receipts from the fuel supplier, a statement from the fuel supplier on the specification of the sulfur content of the purchased oil, or other supporting documentation.

Authority for Requirement: DNR Construction Permit 13-A-151

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 6.8

Stack Opening (inches, dia.): 3

Exhaust Temperature (°F): 800

Exhaust Flowrate (scfm): 420

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 13-A-151

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall

submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Numbers: 50, 820, and 930

Associated Equipment

Associated Emission Unit ID Numbers: 50, 820, 930

Emission Point	Emission Unit vented through this Emission Point	Emission Unit Description	Raw Material/ Fuel	Rated Capacity (HP)	Construction Date
50	50	Emergency Generator	Diesel	227	July 1980
820	820	Unit 8 Fire Protection System Diesel Engine		182	February 2001
930	930	Unit 9 Fire Protection System Diesel Engine		182	February 2003

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40%

Authority for Requirement: 567 IAC 23.3(2)"d"

Pollutant: Particulate Matter (PM)

Emission Limit(s): 0.1 gr/dscf

Authority for Requirement: 567 IAC 23.3(2)"a"

Pollutant: Sulfur Dioxide (SO₂)

Emission Limit(s): 2.5 lb/MMBtu

Authority for Requirement: 567 IAC 23.3(3)"b"(2)

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

1. No person shall allow, cause or permit the combustion of number 1 or number 2 fuel oil exceeding a sulfur content of 0.5 percent by weight.

Authority for Requirement: 567 IAC 23.3(3)"b"(1)

Reporting & Record keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources:

1. The facility shall monitor the percent of sulfur by weight in the fuel oil as delivered. The documentation may be vendor supplied or facility generated.

Authority for Requirement: 567 IAC 22.108(3)

NSPS and NESHAP Requirements:

These emergency engines are subject to 40 CFR 63 Subpart ZZZZ - National Emission Standards for Hazardous Air Pollutants for *Stationary Reciprocating Internal Combustion Engines* (RICE). According to 40 CFR 63.6590(a)(1)(ii) this compression ignition emergency engine, located at a major source, is an existing stationary RICE as it was constructed prior to June 12, 2006.

Compliance Date

Per 63.6595(a)(1) you must comply with the provisions of Subpart ZZZZ that are applicable by May 3, 2013.

Fuel Requirements

No requirements except (beginning January 1, 2015) if you own or operate an existing emergency compression ignition stationary engine with a site rating of more than 100 bhp and a displacement of less than 30 liters per cylinder that uses diesel fuel and operates or is contractually obligated to be available for more than 15 hours per calendar year for the purposes specified in 40 CFR 63.6640(f)(2)(ii) and (iii), you must use diesel fuel that meets the requirements in 40 CFR 80.510(b) for nonroad diesel fuel. Those requirements include a maximum sulfur content of 15 ppm (0.0015%) by weight and a minimum cetane index of 40 or a maximum aromatic content of 35 percent by volume. 40 CFR 63.6604(b)

Operation and Maintenance Requirements 40 CFR 63.6602, 63.6625, 63.6640 and Tables 2c and 6 to Subpart ZZZZ

1. Change oil and filter every 500 hours of operation or annually, whichever comes first. (See 63.6625(i) for the oil analysis option to extend time frame of requirements.)
2. Inspect air cleaner every 1000 hours of operation or annually, whichever comes first, and replace as necessary.
3. Inspect all hoses and belts every 500 hours of operation or annually, whichever comes first, and replace as necessary.
4. Operate and maintain the stationary RICE and after-treatment control device (if any) according to the manufacturer's emission related written instructions or develop your own maintenance plan which must provide to the extent practicable for the maintenance and operation of the engine in a manner consistent with good air pollution control practice for minimizing emissions.
5. Install a non-resettable hour meter if one is not already installed.

6. Minimize the engine's time spent at idle during startup and minimize the engine's startup time to a period needed for appropriate and safe loading of the engine, not to exceed 30 minutes.

Operating Limits 40 CFR 63.6640(f)

1. Any operation other than emergency operation, maintenance and testing, emergency demand response and operation in non-emergency situations (*up to*) 50 hours per year is prohibited.
2. There is no time limit on the use of emergency stationary RICE in emergency situations.
3. You may operate your emergency stationary RICE up to 100 combined hours per calendar year for maintenance checks and readiness testing, emergency demand response and periods where there is a deviation of voltage or frequency of 5 percent or greater below standard voltage or frequency. See 40 CFR 63.6640(f)(2) for additional information and restrictions.
4. You may operate your emergency stationary RICE up to 50 hours per calendar year for non-emergency situations, but those 50 hours are counted toward the 100 hours of maintenance and testing and emergency demand response. The 50 hours per year for non-emergency situations cannot be used for peak shaving or non-emergency demand response, or to generate income for a facility to supply power to an electric grid or otherwise supply power as part of a financial arrangement with another entity.

Recordkeeping Requirements 40 CFR 63.6655

1. Keep records of the maintenance conducted on the stationary RICE.
2. Keep records of the hours of operation of the engine that is recorded through the non-resettable hour meter. Document how many hours are spent for emergency operation, including what classified the operation as emergency and how many hours are spent for non-emergency operation. See 40 CFR 63.6655(f) for additional information.

Notification and Reporting Requirements 40 CFR 63.6645, 63.6650 and Table 2c to Subpart ZZZZ

1. An initial notification is not required per 40 CFR 63.6645(a)(5).
2. A report may be required for failure to perform the work practice requirements on the schedule required in Table 2c. (See Footnote 1 of Table 2c for more information.)
3. If you own or operate an emergency stationary RICE with a site rating of more than 100 bhp that operates or is contractually obligated to be available for more than 15 hours per calendar year for the purposes specified in 40 CFR 63.6640(f)(2)(ii) and (iii), you must submit an annual report. See 40 CFR 63.6650(h) for additional information.

Authority for Requirement: 40 CFR Part 63 Subpart ZZZZ
567 IAC 23.1(4)"cz"
567 IAC 22.108(3)

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: V168

Associated Equipment

Associated Emission Unit ID Number: V168

Emission Units vented through this Emission Point: V168

Emission Unit Description: Portable Cummins Diesel IC Engine for Emergency Use

Raw Material/Fuel: Diesel Fuel

Rated Capacity: 345 kW

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Opacity

Emission Limit(s): 40% ⁽¹⁾

Authority for Requirement: DNR Construction Permit 11-A-562-S1
567 IAC 23.3(2)"d"

⁽²⁾ An exceedance of the indicator opacity of 10% will require the owner/operator to promptly investigate the emission unit and make corrections to operations or equipment associated with the exceedance. If exceedances continue after the corrections, the DNR may require additional proof to demonstrate compliance (e.g., stack testing).

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): 0.187 lb/hr

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 11-A-562-S1

Pollutant: Particulate Matter (PM₁₀)

Emission Limit(s): 1.05 lb/hr

Authority for Requirement: DNR Construction Permit 11-A-562-S1

Pollutant: Particulate Matter (PM)

Emission Limit(s): 1.05 lb/hr

Authority for Requirement: DNR Construction Permit 11-A-562-S1

Pollutant: Sulfur Dioxide (SO₂)

Emission Limit(s): 0.01 lb/hr, 2.5 lb/MMBtu

Authority for Requirement: DNR Construction Permit 11-A-562-S1
567 IAC 23.3(3)"b"(2)

Reporting & Record keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources:

- A. Each time this unit is operated log the following information:
 - a. The date and time the usage starts;
 - b. The duration of the usage;
 - c. The reason for the usage (IE testing, emergency, etc);
 - d. The location of the usage.
- B. At the end of each month, calculate the total number of hours this unit operated over the previous month.
- C. At the end of each month, calculate the total number of hours this unit operated over the previous twelve (12) months.
- D. For each diesel fuel delivery received on site, maintain documentation of the type of fuel received.
- E. Maintain, on site, a fuel analysis that is no more than 12 months old which shows the sulfur content of each type of fuel received over the previous 12 months.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 11-A-562-S1

Emission Point Characteristics

This emission point shall conform to the conditions listed below.

Stack Height (ft, from the ground): 13.5

Stack Opening (inches, dia.): 6

Exhaust Temperature (°F): 805

Exhaust Flowrate (scfm): 1050

Discharge Style: Vertical Unobstructed

Authority for Requirement: DNR Construction Permit 11-A-562-S1

The temperature and flowrate are intended to be representative and characteristic of the design of the permitted emission point. The Department recognizes that the temperature and flow rate may vary with changes in the process and ambient conditions. If it is determined that either the temperature or flowrate above are different than the values stated, the owner or operator shall submit a request to the Department within thirty (30) days of the discovery to determine if a permit amendment is required or submit a permit application requesting to amend the permit.

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: 9999

Associated Equipment

Associated Emission Unit ID Numbers: 9999

Emission Units vented through this Emission Point: 9999

Emission Unit Description: Facility Haul Roads

Raw Material/Fuel: Gypsum, Limestone, Fly ash, Ash/slag, ChemMod Additives

Rated Capacity:

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

Pollutant: Particulate Matter (PM_{2.5})

Emission Limit(s): For this emissions unit the limits are expressed in the form of a work practice instead of an emission limit. See the Operating Limits section below for the work practice requirements.

Authority for Requirement: Muscatine PM2.5 SIP (79 FR 71025, December 1, 2014;
as amended by 80 FR 18133, April 3, 2015)
DNR Construction Permit 13-A-160-S1

Pollutant: Fugitive Dust

Emission Limit: No person shall allow, cause or permit any materials to be handled, transported or stored; or a building, its appurtenances or a construction haul road to be used, constructed, altered, repaired or demolished, without taking reasonable precautions to prevent a nuisance. All persons shall take reasonable precautions to prevent the discharge of visible emissions of fugitive dusts beyond the lot line of the property on which the emissions originate.

Authority for Requirement: 567 IAC 23.3(2)"c"

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

A. The following road segments are covered by this permit:

Road #	Segment ID	Length & type of surface	Used by trucks hauling:	Physical Description
1	A – B	412 feet, Paved	Gypsum Limestone Ash/slag ChemMod	Road: Unit 8 access road From: Intersection of Unit 8 access road with Unit 9 access road (near Guard House) To: Intersection Unit 8 access road with west

Road #	Segment ID	Length & type of surface	Used by trucks hauling:	Physical Description
			additives (Full & empty)	Ash/Slag Pile road (near truck scale)
2	B – C straight	656 feet, Paved	Gypsum Limestone ChemMod additives (Full & empty) Ash/slag (empty)	Road: Unit 8 access road From: Intersection of Unit 8 access road with west Ash/Slag Pile road (near truck scale) To: Intersection Unit 8 access road with east Ash/Slag Pile road (access to Unit 8A substation)
3	B – C curved	1030 feet, Paved	Ash/slag (Full)	Road: Ash/Slag Pile road From: Intersection of Unit 8 access road with west Ash/Slag Pile road (near truck scale) To: Intersection Unit 8 access road with east Ash/Slag Pile road (access to Unit 8A substation)
4	C – D	566 feet, Paved	Gypsum Limestone Ash/slag ChemMod additives (Full & empty)	Road: Unit 8 access road From: Intersection of Unit 8 access road with east Ash/Slag Pile road (access to Unit 8A substation) To: Intersection Unit 8 access road with Gypsum Haul road (near fuel dispensing pumps)
5	D – I	194 feet, Paved	Gypsum Limestone ChemMod additives (Full & empty)	Road: Gypsum Haul Road From: Intersection of Unit 8 access road with Gypsum Haul road (near fuel dispensing pumps) To: Intersection of Gypsum Haul Road with A-Conveyor access road (near A-Conveyor track hopper) Exclusion: EU919A, “Synthetic Gypsum Road-Paved” at EP919 is covered in Construction Permit 12-A-303
6	I – F	290 feet, Paved	Gypsum ChemMod additives (Full & empty)	Road: Gypsum Haul Road From: Intersection of Gypsum Haul road with A-Conveyor access road (near A-Conveyor track hopper) To: Unit 9 Fly Ash silo Exclusion: EU919A, “Synthetic Gypsum Road-Paved” at EP919 is covered in Construction Permit 12-A-303
7	I – E	253 feet, Paved	Limestone (Full & empty)	Road: A-Conveyor access road From: Intersection of Gypsum Haul road with A-Conveyor access road (near A-Conveyor track hopper) To: Intersection A-Conveyor access road with Limestone pile access road (near Transfer

Road #	Segment ID	Length & type of surface	Used by trucks hauling:	Physical Description
				House) Exclusion: None Notes: EU45B “Limestone Haul Roads – Unpaved” and EU45B “Limestone Haul Roads-Paved” are now included in this permit
8	E – H	261 feet, Unpaved	Limestone (Full & empty)	Road: Limestone pile access road From: Intersection of A-Conveyor access road with Limestone pile access road (near Transfer House) To: Limestone pile (limestone load hopper)
9	A – G	1627 feet, Paved	Flyash (Full & empty)	Road: Unit 9 access road From: Intersection of Unit 8 access road with Unit 9 access road (near Guard House) To: Intersection of Unit 9 access road with Material handling access road (near Material Handling Maintenance Building)
10	G – J	597 feet, Unpaved	Flyash (Full & empty)	Road: Material handling access road From: Intersection of Unit 9 access road with Material handling access road (near Material Handling Maintenance Building) To: Intersection of Material Handling Maintenance Building access road with Bag Fly Ash Haul road (near Unit 9 substation access)
11	J – J loop	1312 ft, Unpaved	Flyash (Full & empty)	Road: Bag Fly Ash Haul road From: Intersection of Material Handling Maintenance Building access road with Bag Fly Ash Haul road (near Unit 9 substation access) To: Bag Fly Ash storage area Exclusion: This does not include EU926A4 “Vehicle Traffic from Fly Ash Pile to Hopper” at EP926A4, covered in construction permit 04-A-619-S1
12	F – K	605 ft, Paved	ChemMod additives (Full & empty)	Road: Gypsum Haul Road From: Unit 9 Fly Ash Silo To: Intersection Gypsum Haul road with LSCS-1 access road
13	K – L	155 ft, Paved	ChemMod additives (Full & empty)	Road: LSCS-1 access road From: Intersection Gypsum Haul road with LSCS-1 access road To: ChemMod® 150-Ton powder additive bulk storage silo (near LSCS-1)

B. Operating limits for this emissions unit shall be:

Segment ID	Maximum Number of Truck per Year (Roundtrip except where noted)						Control measures Required:	Operating limit Road use limited between:
	Gyp-sum	Lime-stone	Ash/slag	Fly-ash	ChemMod®			
					Liquid	Powder		
A – B	3287	2900	7588	0	13	234	Water flushing	7:00 AM to 7:00 PM gypsum and ash/slag trucks 6:00 AM to 4:00 PM limestone trucks No restriction for ChemMod® trucks
B–C straight	3287	2900	7588 ¹	0	13	234	Water flushing	7:00 AM to 7:00 PM gypsum and ash/slag trucks 6:00 AM to 4:00 PM limestone trucks No restriction for ChemMod® trucks
B–C curved	0	0	7588 ¹	0	0	0	Paving and water flushing	7:00 AM to 7:00 PM ash/slag trucks
C – D	3287	2900	7588	0	13	234	Water flushing	7:00 AM to 7:00 PM gypsum and ash/slag trucks 6:00 AM to 4:00 PM limestone trucks No restriction for ChemMod® trucks
D – I	3287	2900	0	0	13	234	None	7:00 AM to 7:00 PM gypsum and ash/slag trucks 6:00 AM to 4:00 PM limestone trucks No restriction for ChemMod® trucks
I – F	3287	0	0	0	13	234	None	7:00 AM to 7:00 PM gypsum trucks No restriction for ChemMod® trucks
I – E	0	2900	0	0	0	0	None	6:00 AM to 4:00 PM limestone trucks
E – H	0	2900	0	0	0	0	None	6:00 AM to 4:00 PM limestone trucks
A – G	0	0	0	1606	0	0	None	7:00 AM to 7:00 PM

Segment ID	Maximum Number of Truck per Year (Roundtrip except where noted)						Control measures Required:	Operating limit Road use limited between:
								flyash trucks
G – J	0	0	0	1606	0	0	None	7:00 AM to 7:00 PM flyash trucks
J – J loop	0	0	0	1606	0	0	None	7:00 AM to 7:00 PM flyash trucks
F – K	0	0	0	0	13	234	None	No restriction
K – L	0	0	0	0	13	234	None	No restriction

- C. Haul road segment identified as “B-C curved” shall be paved. Use of this road by commercial vehicles shall be limited to the hours of 0700 through 1900 hours daily.
- D. Fugitive emissions from road segments “A-B”, “B-C straight”, “B-C curved”, and “C-D” shall be controlled to a maximum silt loading content of 6.75 g/m². This represents 50% control efficiency. Water flushing shall occur at least once per month, subject to precipitation, environmental factors and roadway use. The water flushing rate shall be a minimum of 0.23 gallons per square yard. Silt loading testing shall be done, before flushing, at least quarterly between April 1st through September 30th to assure that silt loading does not exceed 6.75 g/m².
- E. The maximum silt loading content of the other paved road segments listed in Condition B. above shall not exceed 13.5 g/m². Silt loading testing shall be done on these road segments at least quarterly between April 1st through September 30th to assure that the silt loading does not exceed 13.5 g/m².
- F. If water flushing cannot be accomplished because the ambient air temperature (as measured at the facility during the daylight operating hours) will be less than 35°F or conditions due to weather, in combination with the application of water, could create hazardous driving conditions, then the water flushing can be postponed and performed as soon after the scheduled date as the conditions preventing the application have abated. Additionally, water flushing need not occur when a rain gauge located at the site indicates that at least 0.2 inch of precipitation (water equivalent) has occurred within the preceding 24-hour time period.

¹ One way trip for trucks.

Authority for Requirement: DNR Construction Permit 13-A-160-S1

Reporting & Record keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources:

- A. The owner or operator shall maintain a daily record on the facility’s haul roads. These records shall show the following information:
- i. The Segment ID; and
 - ii. The number of each type of truck that has used the road segment (i.e. gypsum, limestone, ash/slag, flyash, or ChemMod®). With the exception of ash/ slag trucks using road segments B – C (straight) and B – C (curved), this is the number of roundtrips made by each type of truck. For ash/slag trucks using road segments B-C (straight) this is the number of empty

trucks using the road. For ash/slag trucks using road segments B-C (curved) this is the number of full trucks using the road.

- B. The owner or operator shall maintain the following monthly records on the facility's haul roads:
 - i. The Segment ID;
 - ii. The total number of each type of truck that has used the road segment; and
 - iii. The rolling 12-month total of the number of each type of truck that has used the road segment.
- C. The owner or operator shall maintain records on the road segments A-B, B-C (straight), B-C (curved), and C-D. These records shall show the following information:
 - i. The Segment ID;
 - ii. The dates of silt loading testing and the results of the test;
 - iii. The dates of water flushing and the amount of water applied; and
 - iv. A record of why water flushing could not be conducted on a scheduled day because of ambient air temperature, precipitation, or other environmental or safety factors.

For each silt loading test, the test shall consist of taking samples from each of the four identified road segments. The results of the sampling from road segments A-B, B-C (straight), and C-D can then be averaged together. The results of the sampling from road segment B-C (curved) shall not be averaged with the results from the other road segments.

After 5 years of silt loading tests on road segments A-B, B-C (straight), B-C (curved) and C-D, the owner or operator can request a re-evaluation of the testing frequency.
- D. The owner or operator shall maintain records on road segments D-I, I-F, I-E, A-G, F-K, and K-L. These records shall show the following information:
 - i. The Segment ID; and
 - ii. The dates of the silt loading testing and the results of the test.

For each silt loading test, the test shall consist of taking samples from each of the six identified road segments. The results of the sampling from road segments D-I, I-F, and I-E can then be averaged together. The results of the sampling from road segments F-K and K-L can also be averaged together. The results of the sampling from road segment A-G shall not be averaged with the results from the other road segments.

After 2 years of silt loading tests on road segments D-I, I-F, I-E, A-G, F-K, K-L the owner or operator can request a re-evaluation of the testing frequency.
- E. The owner or operator shall maintain a daily record of when trucks used the following road segments: B – C (curved), I – F, I – E, E – H, A – G, G – J, and J – J loop. This record shall include the following information: date of operation, initial start up time of truck use and final end time of truck use.

Authority for Requirement: DNR Construction Permit 13-A-160-S1

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

Emission Point ID Number: Levee

Associated Equipment

Associated Emission Unit ID Numbers: Levee

Emission Units vented through this Emission Point: Levee

Emission Unit Description: Mississippi River Levee

Raw Material/Fuel: Public Access

Rated Capacity:

Applicable Requirements

Emission Limits (lb./hr, gr./dscf, lb./MMBtu, % opacity, etc.)

The emissions from this emission point shall not exceed the levels specified below.

There are no emission limits for this emission unit.

Operational Limits & Requirements

The owner/operator of this equipment shall comply with the operational limits and requirements listed below.

A. There are no operating limits associated with the river levee.

Authority for Requirement: DNR Construction Permit 13-A-161

Reporting & Record keeping:

The following records shall be maintained on-site for five (5) years and available for inspection upon request by representatives of the Department of Natural Resources:

A. Control measures include restricting public access to the levee that is located between Muscatine Power and Water's (MPW) property and the Mississippi River. Starting on either August 14, 2013 or by no later than 30 days after the date of permit issuance, whichever comes later, MPW shall restrict public access to the levee by posting signs warning of restricted access to the north and south fence lines that intersect the levee. A third sign will be posted in the area of highest modeled concentrations prohibiting loitering and fishing. In-person surveillance of the levee shall be conducted by MPW staff periodically throughout the day with documentation as to surveillance times and locations.

The restriction does not apply to MPW employees, employees, owner or lessees of contiguous properties, federal, state or local officials, emergency and maintenance service personnel (both private and public section), who have a legitimate reason or need for accessing the levee.

Authority for Requirement: DNR Construction Permit 13-A-161

Monitoring Requirements

The owner/operator of this equipment shall comply with the monitoring requirements listed below.

Agency Approved Operation & Maintenance Plan Required? Yes No

Facility Maintained Operation & Maintenance Plan Required? Yes No

Compliance Assurance Monitoring (CAM) Plan Required? Yes No

Authority for Requirement: 567 IAC 22.108(3)

IV. General Conditions

This permit is issued under the authority of the Iowa Code subsection 455B.133(8) and in accordance with 567 Iowa Administrative Code chapter 22.

G1. Duty to Comply

1. The permittee must comply with all conditions of the Title V permit. Any permit noncompliance constitutes a violation of the Act and is grounds for enforcement action; for a permit termination, revocation and reissuance, or modification; or for denial of a permit renewal application. *567 IAC 22.108(9)"a"*
2. Any compliance schedule shall be supplemental to, and shall not sanction noncompliance with, the applicable requirements on which it is based. *567 IAC 22.105 (2)"h"(3)*
3. Where an applicable requirement of the Act is more stringent than an applicable requirement of regulations promulgated under Title IV of the Act, both provisions shall be enforceable by the administrator and are incorporated into this permit. *567 IAC 22.108 (1)"b"*
4. Unless specified as either "state enforceable only" or "local program enforceable only", all terms and conditions in the permit, including provisions to limit a source's potential to emit, are enforceable by the administrator and citizens under the Act. *567 IAC 22.108 (14)*
5. It shall not be a defense for a permittee, in an enforcement action, that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of the permit. *567 IAC 22.108 (9)"b"*
6. For applicable requirements with which the permittee is in compliance, the permittee shall continue to comply with such requirements. For applicable requirements that will become effective during the permit term, the permittee shall meet such requirements on a timely basis. *567 IAC 22.108(15)"c"*

G2. Permit Expiration

1. Except as provided in rule 567—22.104(455B), permit expiration terminates a source's right to operate unless a timely and complete application for renewal has been submitted in accordance with rule 567—22.105(455B). *567 IAC 22.116(2)*
2. To be considered timely, the owner, operator, or designated representative (where applicable) of each source required to obtain a Title V permit shall submit on forms or electronic format specified by the Department to the Air Quality Bureau, Iowa Department of Natural Resources, Air Quality Bureau, 7900 Hickman Rd, Suite #1, Windsor Heights, Iowa 50324, two copies (three if your facility is located in Linn or Polk county) of a complete permit application, at least 6 months but not more than 18 months prior to the date of permit expiration. An additional copy must also be sent to U.S. EPA Region VII, Attention: Chief of Air Permits, 11201 Renner Blvd., Lenexa, KS 66219. Additional copies to local programs or EPA are not required for application materials submitted through the electronic format specified by the Department. The application must include all emission points, emission units, air pollution control equipment, and monitoring devices at the facility. All emissions generating activities, including fugitive emissions, must be included. The definition of a complete application is as indicated in 567 IAC 22.105(2). *567 IAC 22.105*

G3. Certification Requirement for Title V Related Documents

Any application, report, compliance certification or other document submitted pursuant to this permit shall contain certification by a responsible official of truth, accuracy, and completeness. All certifications shall state that, based on information and belief formed after reasonable inquiry, the statements and information in the document are true, accurate, and complete. *567 IAC 22.107 (4)*

G4. Annual Compliance Certification

By March 31 of each year, the permittee shall submit compliance certifications for the previous calendar year. The certifications shall include descriptions of means to monitor the compliance status of all emissions sources including emissions limitations, standards, and work practices in accordance with applicable requirements. The certification for a source shall include the identification of each term or condition of the permit that is the basis of the certification; the compliance status; whether compliance was continuous or intermittent; the method(s) used for determining the compliance status of the source, currently and over the reporting period consistent with all applicable department rules. For sources determined not to be in compliance at the time of compliance certification, a compliance schedule shall be submitted which provides for periodic progress reports, dates for achieving activities, milestones, and an explanation of why any dates were missed and preventive or corrective measures. The compliance certification shall be submitted to the administrator, director, and the appropriate DNR Field office. *567 IAC 22.108 (15)"e"*

G5. Semi-Annual Monitoring Report

By March 31 and September 30 of each year, the permittee shall submit a report of any monitoring required under this permit for the 6 month periods of July 1 to December 31 and January 1 to June 30, respectively. All instances of deviations from permit requirements must be clearly identified in these reports, and the report must be signed by a responsible official, consistent with 567 IAC 22.107(4). The semi-annual monitoring report shall be submitted to the director and the appropriate DNR Field office. *567 IAC 22.108 (5)*

G6. Annual Fee

1. The permittee is required under subrule 567 IAC 22.106 to pay an annual fee based on the total tons of actual emissions of each regulated air pollutant. Beginning July 1, 1996, Title V operating permit fees will be paid on July 1 of each year. The fee shall be based on emissions for the previous calendar year.
2. The fee amount shall be calculated based on the first 4,000 tons of each regulated air pollutant emitted each year. The fee to be charged per ton of pollutant will be available from the department by June 1 of each year. The Responsible Official will be advised of any change in the annual fee per ton of pollutant.
3. The following forms shall be submitted annually by March 31 documenting actual emissions for the previous calendar year.
 - a. Form 1.0 "Facility Identification";
 - b. Form 4.0 "Emissions unit-actual operations and emissions" for each emission unit;
 - c. Form 5.0 "Title V annual emissions summary/fee"; and
 - d. Part 3 "Application certification."
4. The fee shall be submitted annually by July 1. The fee shall be submitted with the following forms:
 - a. Form 1.0 "Facility Identification";
 - b. Form 5.0 "Title V annual emissions summary/fee";
 - c. Part 3 "Application certification."
5. If there are any changes to the emission calculation form, the department shall make revised forms available to the public by January 1. If revised forms are not available by January 1, forms from the previous year may be used and the year of emissions documented changed. The department shall calculate the total statewide Title V emissions for the prior calendar year and make this information available to the public no later than April 30 of each year.

6. Phase I acid rain affected units under section 404 of the Act shall not be required to pay a fee for emissions which occur during the years 1993 through 1999 inclusive.
7. The fee for a portable emissions unit or stationary source which operates both in Iowa and out of state shall be calculated only for emissions from the source while operating in Iowa.
8. Failure to pay the appropriate Title V fee represents cause for revocation of the Title V permit as indicated in 567 IAC 22.115(1)"d".

G7. Inspection of Premises, Records, Equipment, Methods and Discharges

Upon presentation of proper credentials and any other documents as may be required by law, the permittee shall allow the director or the director's authorized representative to:

1. Enter upon the permittee's premises where a Title V source is located or emissions-related activity is conducted, or where records must be kept under the conditions of the permit;
2. Have access to and copy, at reasonable times, any records that must be kept under the conditions of the permit;
3. Inspect, at reasonable times, any facilities, equipment (including monitoring and air pollution control equipment), practices, or operations regulated or required under the permit; and
4. Sample or monitor, at reasonable times, substances or parameters for the purpose of ensuring compliance with the permit or other applicable requirements. *567 IAC 22.108 (15)"b"*

G8. Duty to Provide Information

The permittee shall furnish to the director, within a reasonable time, any information that the director may request in writing to determine whether cause exists for modifying, revoking and reissuing, or terminating the permit or to determine compliance with the permit. Upon request, the permittee also shall furnish to the director copies of records required to be kept by the permit, or for information claimed to be confidential, the permittee shall furnish such records directly to the administrator of EPA along with a claim of confidentiality. *567 IAC 22.108 (9)"e"*

G9. General Maintenance and Repair Duties

The owner or operator of any air emission source or control equipment shall:

1. Maintain and operate the equipment or control equipment at all times in a manner consistent with good practice for minimizing emissions.
2. Remedy any cause of excess emissions in an expeditious manner.
3. Minimize the amount and duration of any excess emission to the maximum extent possible during periods of such emissions. These measures may include but not be limited to the use of clean fuels, production cutbacks, or the use of alternate process units or, in the case of utilities, purchase of electrical power until repairs are completed.
4. Schedule, at a minimum, routine maintenance of equipment or control equipment during periods of process shutdowns to the maximum extent possible. *567 IAC 24.2(1)*

G10. Recordkeeping Requirements for Compliance Monitoring

1. In addition to any source specific recordkeeping requirements contained in this permit, the permittee shall maintain the following compliance monitoring records, where applicable:
 - a. The date, place and time of sampling or measurements
 - b. The date the analyses were performed.
 - c. The company or entity that performed the analyses.
 - d. The analytical techniques or methods used.
 - e. The results of such analyses; and
 - f. The operating conditions as existing at the time of sampling or measurement.
 - g. The records of quality assurance for continuous compliance monitoring systems (including but not limited to quality control activities, audits and calibration drifts.)

2. The permittee shall retain records of all required compliance monitoring data and support information for a period of at least 5 years from the date of compliance monitoring sample, measurement report or application. Support information includes all calibration and maintenance records and all original strip chart recordings for continuous compliance monitoring, and copies of all reports required by the permit.

3. For any source which in its application identified reasonably anticipated alternative operating scenarios, the permittee shall:

- a. Comply with all terms and conditions of this permit specific to each alternative scenario.
- b. Maintain a log at the permitted facility of the scenario under which it is operating.
- c. Consider the permit shield, if provided in this permit, to extend to all terms and conditions under each operating scenario. *567 IAC 22.108(4), 567 IAC 22.108(12)*

G11. Evidence used in establishing that a violation has or is occurring.

Notwithstanding any other provisions of these rules, any credible evidence may be used for the purpose of establishing whether a person has violated or is in violation of any provisions herein.

1. Information from the use of the following methods is presumptively credible evidence of whether a violation has occurred at a source:

- a. A monitoring method approved for the source and incorporated in an operating permit pursuant to 567 Chapter 22;
- b. Compliance test methods specified in 567 Chapter 25; or
- c. Testing or monitoring methods approved for the source in a construction permit issued pursuant to 567 Chapter 22.

2. The following testing, monitoring or information gathering methods are presumptively credible testing, monitoring, or information gathering methods:

- a. Any monitoring or testing methods provided in these rules; or
- b. Other testing, monitoring, or information gathering methods that produce information comparable to that produced by any method in subrule 21.5(1) or this subrule. *567 IAC 21.5(1)-567 IAC 21.5(2)*

G12. Prevention of Accidental Release: Risk Management Plan Notification and Compliance Certification

If the permittee is required to develop and register a risk management plan pursuant to section 112(r) of the Act, the permittee shall notify the department of this requirement. The plan shall be filed with all appropriate authorities by the deadline specified by EPA. A certification that this risk management plan is being properly implemented shall be included in the annual compliance certification of this permit. *567 IAC 22.108(6)*

G13. Hazardous Release

The permittee must report any situation involving the actual, imminent, or probable release of a hazardous substance into the atmosphere which, because of the quantity, strength and toxicity of the substance, creates an immediate or potential danger to the public health, safety or to the environment. A verbal report shall be made to the department at (515) 725-8694 and to the local police department or the office of the sheriff of the affected county as soon as possible but not later than six hours after the discovery or onset of the condition. This verbal report must be followed up with a written report as indicated in 567 IAC 131.2(2). *567 IAC Chapter 131-State Only*

G14. Excess Emissions and Excess Emissions Reporting Requirements

1. Excess Emissions. Excess emission during a period of startup, shutdown, or cleaning of control equipment is not a violation of the emission standard if the startup, shutdown or cleaning is accomplished expeditiously and in a manner consistent with good practice for minimizing emissions. Cleaning of control equipment which does not require the shutdown of the process equipment shall be limited to one six-minute period per one-hour period. An incident of excess emission (other than an incident during startup, shutdown or cleaning of control equipment) is a violation. If the owner or operator of a source maintains that the incident of excess emission was due to a malfunction, the owner or operator must show that the conditions which caused the incident of excess emission were not preventable by reasonable maintenance and control measures. Determination of any subsequent enforcement action will be made following review of this report. If excess emissions are occurring, either the control equipment causing the excess emission shall be repaired in an expeditious manner or the process generating the emissions shall be shutdown within a reasonable period of time. An expeditious manner is the time necessary to determine the cause of the excess emissions and to correct it within a reasonable period of time. A reasonable period of time is eight hours plus the period of time required to shut down the process without damaging the process equipment or control equipment. A variance from this subrule may be available as provided for in Iowa Code section 455B.143. In the case of an electric utility, a reasonable period of time is eight hours plus the period of time until comparable generating capacity is available to meet consumer demand with the affected unit out of service, unless, the director shall, upon investigation, reasonably determine that continued operation constitutes an unjustifiable environmental hazard and issue an order that such operation is not in the public interest and require a process shutdown to commence immediately.

2. Excess Emissions Reporting

a. Initial Reporting of Excess Emissions. An incident of excess emission (other than an incident of excess emission during a period of startup, shutdown, or cleaning) shall be reported to the appropriate field office of the department within eight hours of, or at the start of the first working day following the onset of the incident. The reporting exemption for an incident of excess emission during startup, shutdown or cleaning does not relieve the owner or operator of a source with continuous monitoring equipment of the obligation of submitting reports required in 567-subrule 25.1(6). An initial report of excess emission is not required for a source with operational continuous monitoring equipment (as specified in 567-subrule 25.1(1)) if the incident of excess emission continues for less than 30 minutes and does not exceed the applicable emission standard by more than 10 percent or the applicable visible emission standard by more than 10 percent opacity. The initial report may be made by electronic mail (E-mail), in person, or by telephone and shall include as a minimum the following:

- i. The identity of the equipment or source operation from which the excess emission originated and the associated stack or emission point.
- ii. The estimated quantity of the excess emission.
- iii. The time and expected duration of the excess emission.
- iv. The cause of the excess emission.
- v. The steps being taken to remedy the excess emission.
- vi. The steps being taken to limit the excess emission in the interim period.

b. Written Reporting of Excess Emissions. A written report of an incident of excess emission shall be submitted as a follow-up to all required initial reports to the department

within seven days of the onset of the upset condition, and shall include as a minimum the following:

- i. The identity of the equipment or source operation point from which the excess emission originated and the associated stack or emission point.
- ii. The estimated quantity of the excess emission.
- iii. The time and duration of the excess emission.
- iv. The cause of the excess emission.
- v. The steps that were taken to remedy and to prevent the recurrence of the incident of excess emission.
- vi. The steps that were taken to limit the excess emission.
- vii. If the owner claims that the excess emission was due to malfunction, documentation to support this claim. *567 IAC 24.1(1)-567 IAC 24.1(4)*

3. Emergency Defense for Excess Emissions. For the purposes of this permit, an “emergency” means any situation arising from sudden and reasonably unforeseeable events beyond the control of the source, including acts of God, which situation requires immediate corrective action to restore normal operation, and that causes the source to exceed a technology-based emission limitation under the permit due to unavoidable increases in emissions attributable to the emergency. An emergency shall not include non-compliance, to the extent caused by improperly designed equipment, lack of preventive maintenance, careless or improper operation or operator error. An emergency constitutes an affirmative defense to an action brought for non-compliance with technology based limitations if it can be demonstrated through properly signed contemporaneous operating logs or other relevant evidence that:

- a. An emergency occurred and that the permittee can identify the cause(s) of the emergency;
- b. The facility at the time was being properly operated;
- c. During the period of the emergency, the permittee took all reasonable steps to minimize levels of emissions that exceeded the emissions standards or other requirements of the permit; and
- d. The permittee submitted notice of the emergency to the director by certified mail within two working days of the time when the emissions limitations were exceeded due to the emergency. This notice fulfills the requirement of paragraph 22.108(5)"b." – See G15. This notice must contain a description of the emergency, any steps taken to mitigate emissions, and corrective actions taken.

In any enforcement proceeding, the permittee seeking to establish the occurrence of an emergency has the burden of proof. This provision is in addition to any emergency or upset provision contained in any applicable requirement. *567 IAC 22.108(16)*

G15. Permit Deviation Reporting Requirements

A deviation is any failure to meet a term, condition or applicable requirement in the permit. Reporting requirements for deviations that result in a hazardous release or excess emissions have been indicated above (see G13 and G14). Unless more frequent deviation reporting is specified in the permit, any other deviation shall be documented in the semi-annual monitoring report and the annual compliance certification (see G4 and G5). *567 IAC 22.108(5)"b"*

G16. Notification Requirements for Sources That Become Subject to NSPS and NESHAP Regulations

During the term of this permit, the permittee must notify the department of any source that becomes subject to a standard or other requirement under 567-subrule 23.1(2) (standards of

performance of new stationary sources) or section 111 of the Act; or 567-subrule 23.1(3) (emissions standards for hazardous air pollutants), 567-subrule 23.1(4) (emission standards for hazardous air pollutants for source categories) or section 112 of the Act. This notification shall be submitted in writing to the department pursuant to the notification requirements in 40 CFR Section 60.7, 40 CFR Section 61.07, and/or 40 CFR Section 63.9. *567 IAC 23.1(2), 567 IAC 23.1(3), 567 IAC 23.1(4)*

G17. Requirements for Making Changes to Emission Sources That Do Not Require Title V Permit Modification

1. Off Permit Changes to a Source. Pursuant to section 502(b)(10) of the CAAA, the permittee may make changes to this installation/facility without revising this permit if:

- a. The changes are not major modifications under any provision of any program required by section 110 of the Act, modifications under section 111 of the act, modifications under section 112 of the act, or major modifications as defined in 567 IAC Chapter 22.
- b. The changes do not exceed the emissions allowable under the permit (whether expressed therein as a rate of emissions or in terms of total emissions);
- c. The changes are not modifications under any provisions of Title I of the Act and the changes do not exceed the emissions allowable under the permit (whether expressed therein as a rate of emissions or as total emissions);
- d. The changes are not subject to any requirement under Title IV of the Act (revisions affecting Title IV permitting are addressed in rules 567—22.140(455B) through 567 - 22.144(455B));
- e. The changes comply with all applicable requirements.
- f. For each such change, the permitted source provides to the department and the administrator by certified mail, at least 30 days in advance of the proposed change, a written notification, including the following, which must be attached to the permit by the source, the department and the administrator:
 - i. A brief description of the change within the permitted facility,
 - ii. The date on which the change will occur,
 - iii. Any change in emission as a result of that change,
 - iv. The pollutants emitted subject to the emissions trade
 - v. If the emissions trading provisions of the state implementation plan are invoked, then Title V permit requirements with which the source shall comply; a description of how the emissions increases and decreases will comply with the terms and conditions of the Title V permit.
 - vi. A description of the trading of emissions increases and decreases for the purpose of complying with a federally enforceable emissions cap as specified in and in compliance with the Title V permit; and
 - vii. Any permit term or condition no longer applicable as a result of the change.

567 IAC 22.110(1)

2. Such changes do not include changes that would violate applicable requirements or contravene federally enforceable permit terms and conditions that are monitoring (including test methods), record keeping, reporting, or compliance certification requirements. *567 IAC 22.110(2)*

3. Notwithstanding any other part of this rule, the director may, upon review of a notice, require a stationary source to apply for a Title V permit if the change does not meet the requirements of subrule 22.110(1). *567 IAC 22.110(3)*

4. The permit shield provided in subrule 22.108(18) shall not apply to any change made pursuant to this rule. Compliance with the permit requirements that the source will meet using the emissions trade shall be determined according to requirements of the state implementation plan authorizing the emissions trade. *567 IAC 22.110(4)*
5. No permit revision shall be required, under any approved economic incentives, marketable permits, emissions trading and other similar programs or processes, for changes that are provided for in this permit. *567 IAC 22.108(11)*

G18. Duty to Modify a Title V Permit

1. Administrative Amendment.

- a. An administrative permit amendment is a permit revision that does any of the following:
 - i. Correct typographical errors
 - ii. Identify a change in the name, address, or telephone number of any person identified in the permit, or provides a similar minor administrative change at the source;
 - iii. Require more frequent monitoring or reporting by the permittee; or
 - iv. Allow for a change in ownership or operational control of a source where the director determines that no other change in the permit is necessary, provided that a written agreement containing a specific date for transfer of permit responsibility, coverage and liability between the current and new permittee has been submitted to the director.
- b. The permittee may implement the changes addressed in the request for an administrative amendment immediately upon submittal of the request. The request shall be submitted to the director.
- c. Administrative amendments to portions of permits containing provisions pursuant to Title IV of the Act shall be governed by regulations promulgated by the administrator under Title IV of the Act.

2. Minor Title V Permit Modification.

- a. Minor Title V permit modification procedures may be used only for those permit modifications that satisfy all of the following:
 - i. Do not violate any applicable requirement;
 - ii. Do not involve significant changes to existing monitoring, reporting or recordkeeping requirements in the Title V permit;
 - iii. Do not require or change a case by case determination of an emission limitation or other standard, or an increment analysis;
 - iv. Do not seek to establish or change a permit term or condition for which there is no corresponding underlying applicable requirement and that the source has assumed in order to avoid an applicable requirement to which the source would otherwise be subject. Such terms and conditions include any federally enforceable emissions caps which the source would assume to avoid classification as a modification under any provision under Title I of the Act; and an alternative emissions limit approved pursuant to regulations promulgated under section 112(i)(5) of the Act;
 - v. Are not modifications under any provision of Title I of the Act; and
 - vi. Are not required to be processed as significant modification under rule 567 - 22.113(455B).

- b. An application for minor permit revision shall be on the minor Title V modification application form and shall include at least the following:
- i. A description of the change, the emissions resulting from the change, and any new applicable requirements that will apply if the change occurs;
 - ii. The permittee's suggested draft permit;
 - iii. Certification by a responsible official, pursuant to 567 IAC 22.107(4), that the proposed modification meets the criteria for use of minor permit modification procedures and a request that such procedures be used; and
 - iv. Completed forms to enable the department to notify the administrator and the affected states as required by 567 IAC 22.107(7).
- c. The permittee may make the change proposed in its minor permit modification application immediately after it files the application. After the permittee makes this change and until the director takes any of the actions specified in 567 IAC 22.112(4) "a" to "c", the permittee must comply with both the applicable requirements governing the change and the proposed permit terms and conditions. During this time, the permittee need not comply with the existing permit terms and conditions it seeks to modify. However, if the permittee fails to comply with its proposed permit terms and conditions during this time period, the existing permit terms and conditions it seeks to modify may be enforced against the facility.

3. Significant Title V Permit Modification.

Significant Title V modification procedures shall be used for applications requesting Title V permit modifications that do not qualify as minor Title V modifications or as administrative amendments. These include but are not limited to all significant changes in monitoring permit terms, every relaxation of reporting or recordkeeping permit terms, and any change in the method of measuring compliance with existing requirements. Significant Title V modifications shall meet all requirements of 567 IAC Chapter 22, including those for applications, public participation, review by affected states, and review by the administrator, as those requirements that apply to Title V issuance and renewal.

The permittee shall submit an application for a significant permit modification not later than three months after commencing operation of the changed source unless the existing Title V permit would prohibit such construction or change in operation, in which event the operation of the changed source may not commence until the department revises the permit. *567 IAC 22.111-567 IAC 22.113*

G19. Duty to Obtain Construction Permits

Unless exempted in 567 IAC 22.1(2) or to meet the parameters established in 567 IAC 22.1(1)"c", the permittee shall not construct, install, reconstruct or alter any equipment, control equipment or anaerobic lagoon without first obtaining a construction permit, or conditional permit, or permit pursuant to rule 567 IAC 22.8, or permits required pursuant to rules 567 IAC 22.4, 567 IAC 22.5, 567 IAC 31.3, and 567 IAC 33.3 as required in 567 IAC 22.1(1). A permit shall be obtained prior to the initiation of construction, installation or alteration of any portion of the stationary source or anaerobic lagoon. *567 IAC 22.1(1)*

G20. Asbestos

The permittee shall comply with 567 IAC 23.1(3)"a", and 567 IAC 23.2(3)"g" when activities involve asbestos mills, surfacing of roadways, manufacturing operations, fabricating, insulating, waste disposal, spraying applications, demolition and renovation operations (*567 IAC 23.1(3)"a"*); training fires and controlled burning of a demolished building (*567 IAC 23.2*).

G21. Open Burning

The permittee is prohibited from conducting open burning, except as provided in 567 IAC 23.2. *567 IAC 23.2 except 23.2(3)"j"; 567 IAC 23.2(3)"j" - State Only*

G22. Acid Rain (Title IV) Emissions Allowances

The permittee shall not exceed any allowances that it holds under Title IV of the Act or the regulations promulgated there under. Annual emissions of sulfur dioxide in excess of the number of allowances to emit sulfur dioxide held by the owners and operators of the unit or the designated representative of the owners and operators is prohibited. Exceedences of applicable emission rates are prohibited. "Held" in this context refers to both those allowances assigned to the owners and operators by USEPA, and those allowances supplementally acquired by the owners and operators. The use of any allowance prior to the year for which it was allocated is prohibited. Contravention of any other provision of the permit is prohibited. *567 IAC 22.108(7)*

G23. Stratospheric Ozone and Climate Protection (Title VI) Requirements

1. The permittee shall comply with the standards for labeling of products using ozone-depleting substances pursuant to 40 CFR Part 82, Subpart E:
 - a. All containers in which a class I or class II substance is stored or transported, all products containing a class I substance, and all products directly manufactured with a class I substance must bear the required warning statement if it is being introduced into interstate commerce pursuant to § 82.106.
 - b. The placement of the required warning statement must comply with the requirements pursuant to § 82.108.
 - c. The form of the label bearing the required warning statement must comply with the requirements pursuant to § 82.110.
 - d. No person may modify, remove, or interfere with the required warning statement except as described in § 82.112.
2. The permittee shall comply with the standards for recycling and emissions reduction pursuant to 40 CFR Part 82, Subpart F, except as provided for MVACs in Subpart B:
 - a. Persons opening appliances for maintenance, service, repair, or disposal must comply with the required practices pursuant to § 82.156.
 - b. Equipment used during the maintenance, service, repair, or disposal of appliances must comply with the standards for recycling and recovery equipment pursuant to § 82.158.
 - c. Persons performing maintenance, service, repair, or disposal of appliances must be certified by an approved technician certification program pursuant to § 82.161.
 - d. Persons disposing of small appliances, MVACs, and MVAC-like appliances must comply with reporting and recordkeeping requirements pursuant to § 82.166. ("MVAC-like appliance" as defined at § 82.152)
 - e. Persons owning commercial or industrial process refrigeration equipment must comply with the leak repair requirements pursuant to § 82.156.
 - f. Owners/operators of appliances normally containing 50 or more pounds of refrigerant must keep records of refrigerant purchased and added to such appliances pursuant to § 82.166.
3. If the permittee manufactures, transforms, imports, or exports a class I or class II substance, the permittee is subject to all the requirements as specified in 40 CFR part 82, Subpart A, Production and Consumption Controls.
4. If the permittee performs a service on motor (fleet) vehicles when this service involves ozone-depleting substance refrigerant (or regulated substitute substance) in the motor vehicle air

conditioner (MVAC), the permittee is subject to all the applicable requirements as specified in 40 CFR part 82, Subpart B, Servicing of Motor Vehicle Air Conditioners. The term "motor vehicle" as used in Subpart B does not include a vehicle in which final assembly of the vehicle has not been completed. The term "MVAC" as used in Subpart B does not include the air-tight sealed refrigeration system used as refrigerated cargo, or system used on passenger buses using HCFC-22 refrigerant,

5. The permittee shall be allowed to switch from any ozone-depleting substance to any alternative that is listed in the Significant New Alternatives Program (SNAP) promulgated pursuant to 40 CFR part 82, Subpart G, Significant New Alternatives Policy Program. *40 CFR part 82*

G24. Permit Reopenings

1. This permit may be modified, revoked, reopened, and reissued, or terminated for cause. The filing of a request by the permittee for a permit modification, revocation and reissuance, or termination, or of a notification of planned changes or anticipated noncompliance does not stay any permit condition. *567 IAC 22.108(9)"c"*

2. Additional applicable requirements under the Act become applicable to a major part 70 source with a remaining permit term of 3 or more years. Revisions shall be made as expeditiously as practicable, but not later than 18 months after the promulgation of such standards and regulations.

a. Reopening and revision on this ground is not required if the permit has a remaining term of less than three years;

b. Reopening and revision on this ground is not required if the effective date of the requirement is later than the date on which the permit is due to expire, unless the original permit or any of its terms and conditions have been extended pursuant to 40 CFR 70.4(b)(10)(i) or (ii) as amended to May 15, 2001.

c. Reopening and revision on this ground is not required if the additional applicable requirements are implemented in a general permit that is applicable to the source and the source receives approval for coverage under that general permit. *567 IAC 22.108(17)"a"*, *567 IAC 22.108(17)"b"*

3. A permit shall be reopened and revised under any of the following circumstances:

a. The department receives notice that the administrator has granted a petition for disapproval of a permit pursuant to 40 CFR 70.8(d) as amended to July 21, 1992, provided that the reopening may be stayed pending judicial review of that determination;

b. The department or the administrator determines that the Title V permit contains a material mistake or that inaccurate statements were made in establishing the emissions standards or other terms or conditions of the Title V permit;

c. Additional applicable requirements under the Act become applicable to a Title V source, provided that the reopening on this ground is not required if the permit has a remaining term of less than three years, the effective date of the requirement is later than the date on which the permit is due to expire, or the additional applicable requirements are implemented in a general permit that is applicable to the source and the source receives approval for coverage under that general permit. Such a reopening shall be complete not later than 18 months after promulgation of the applicable requirement.

d. Additional requirements, including excess emissions requirements, become applicable to a Title IV affected source under the acid rain program. Upon approval by the administrator, excess emissions offset plans shall be deemed to be incorporated into the

permit.

e. The department or the administrator determines that the permit must be revised or revoked to ensure compliance by the source with the applicable requirements. *567 IAC 22.114(1)*

4. Proceedings to reopen and reissue a Title V permit shall follow the procedures applicable to initial permit issuance and shall effect only those parts of the permit for which cause to reopen exists. *567 IAC 22.114(2)*

5. A notice of intent shall be provided to the Title V source at least 30 days in advance of the date the permit is to be reopened, except that the director may provide a shorter time period in the case of an emergency. *567 IAC 22.114(3)*

G25. Permit Shield

1. The director may expressly include in a Title V permit a provision stating that compliance with the conditions of the permit shall be deemed compliance with any applicable requirements as of the date of permit issuance, provided that:

a. Such applicable requirements are included and are specifically identified in the permit; or

b. The director, in acting on the permit application or revision, determines in writing that other requirements specifically identified are not applicable to the source, and the permit includes the determination or a concise summary thereof.

2. A Title V permit that does not expressly state that a permit shield exists shall be presumed not to provide such a shield.

3. A permit shield shall not alter or affect the following:

a. The provisions of Section 303 of the Act (emergency orders), including the authority of the administrator under that section;

b. The liability of an owner or operator of a source for any violation of applicable requirements prior to or at the time of permit issuance;

c. The applicable requirements of the acid rain program, consistent with Section 408(a) of the Act;

d. The ability of the department or the administrator to obtain information from the facility pursuant to Section 114 of the Act. *567 IAC 22.108 (18)*

G26. Severability

The provisions of this permit are severable and if any provision or application of any provision is found to be invalid by this department or a court of law, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected by such finding. *567 IAC 22.108 (8)*

G27. Property Rights

The permit does not convey any property rights of any sort, or any exclusive privilege. *567 IAC 22.108 (9)"d"*

G28. Transferability

This permit is not transferable from one source to another. If title to the facility or any part of it is transferred, an administrative amendment to the permit must be sought consistent with the requirements of *567 IAC 22.111(1)*. *567 IAC 22.111 (1)"d"*

G29. Disclaimer

No review has been undertaken on the engineering aspects of the equipment or control equipment other than the potential of that equipment for reducing air contaminant emissions. *567 IAC 22.3(3)"c"*

G30. Notification and Reporting Requirements for Stack Tests or Monitor Certification

The permittee shall notify the department's stack test contact in writing not less than 30 days before a required test or performance evaluation of a continuous emission monitor is performed to determine compliance with applicable requirements of 567 – Chapter 23 or a permit condition. Such notice shall include the time, the place, the name of the person who will conduct the test and other information as required by the department. If the owner or operator does not provide timely notice to the department, the department shall not consider the test results or performance evaluation results to be a valid demonstration of compliance with applicable rules or permit conditions. Upon written request, the department may allow a notification period of less than 30 days. At the department's request, a pretest meeting shall be held not later than 15 days prior to conducting the compliance demonstration. A testing protocol shall be submitted to the department no later than 15 days before the owner or operator conducts the compliance demonstration. A representative of the department shall be permitted to witness the tests. Results of the tests shall be submitted in writing to the department's stack test contact in the form of a comprehensive report within six weeks of the completion of the testing. Compliance tests conducted pursuant to this permit shall be conducted with the source operating in a normal manner at its maximum continuous output as rated by the equipment manufacturer, or the rate specified by the owner as the maximum production rate at which the source shall be operated. In cases where compliance is to be demonstrated at less than the maximum continuous output as rated by the equipment manufacturer, and it is the owner's intent to limit the capacity to that rating, the owner may submit evidence to the department that the source has been physically altered so that capacity cannot be exceeded, or the department may require additional testing, continuous monitoring, reports of operating levels, or any other information deemed necessary by the department to determine whether such source is in compliance.

Stack test notifications, reports and correspondence shall be sent to:

Stack Test Review Coordinator
Iowa DNR, Air Quality Bureau
7900 Hickman Road, Suite #1
Windsor Heights, IA 50324
(515) 725-9545

Within Polk and Linn Counties, stack test notifications, reports and correspondence shall also be directed to the supervisor of the respective county air pollution program.

567 IAC 25.1(7)"a", 567 IAC 25.1(9)

G31. Prevention of Air Pollution Emergency Episodes

The permittee shall comply with the provisions of 567 IAC Chapter 26 in the prevention of excessive build-up of air contaminants during air pollution episodes, thereby preventing the occurrence of an emergency due to the effects of these contaminants on the health of persons.

567 IAC 26.1(1)

G32. Contacts List

The current address and phone number for reports and notifications to the EPA administrator is:

Chief of Air Permits
U.S. EPA Region 7
Air Permits and Compliance Branch
11201 Renner Blvd.
Lenexa, KS 66219
(913) 551-7020

The current address and phone number for reports and notifications to the department or the Director is:

Chief, Air Quality Bureau
Iowa Department of Natural Resources
7900 Hickman Road, Suite #1
Windsor Heights, IA 50324
(515) 725-9500

Reports or notifications to the DNR Field Offices or local programs shall be directed to the supervisor at the appropriate field office or local program. Current addresses and phone numbers are:

Field Office 1

909 West Main – Suite 4
Manchester, IA 52057
(563) 927-2640

Field Office 2

2300-15th St., SW
Mason City, IA 50401
(641) 424-4073

Field Office 3

1900 N. Grand Ave.
Spencer, IA 51301
(712) 262-4177

Field Office 4

1401 Sunnyside Lane
Atlantic, IA 50022
(712) 243-1934

Field Office 5

7900 Hickman Road, Suite #200
Windsor Heights, IA 50324
(515) 725-0268

Field Office 6

1023 West Madison Street
Washington, IA 52353-1623
(319) 653-2135

Polk County Public Works Dept.

Air Quality Division
5885 NE 14th St.
Des Moines, IA 50313
(515) 286-3351

Linn County Public Health

Air Quality Branch
501 13th St., NW
Cedar Rapids, IA 52405
(319) 892-6000

V. Appendix

Appendix A. Links to Standards

- A. 40 CFR Part 60 Subpart A- *General Provisions*
<http://www.ecfr.gov/cgi-bin/text-idx?c=ecfr&rgn=div6&view=text&node=40:7.0.1.1.1.1>
- B. 40 CFR Part 60 Subpart Da- Standards of Performance for *Electric Utility Steam Generating Units* for which Construction is Commenced after September 18, 1978
http://www.ecfr.gov/cgi-bin/retrieveECFR?gp=&r=SUBPART&n=sp40.7.60.d_0a
- C. 40 CFR Part 60 Subpart Y - Standards of Performance for *Coal Preparation Plants*
<http://www.ecfr.gov/cgi-bin/retrieveECFR?gp=&r=SUBPART&n=sp40.7.60.y>
- D. 40 CFR 63 Subpart A – *General Provisions*
<http://www.ecfr.gov/cgi-bin/retrieveECFR?gp=&r=SUBPART&n=sp40.10.63.a>
- E. 40 CFR 63 Subpart ZZZZ – National Emission Standard for Hazardous Air Pollutants for *Stationary Reciprocating Internal Combustion Engines*
<http://www.ecfr.gov/cgi-bin/text-idx?c=ecfr&rgn=div6&view=text&node=40:14.0.1.1.1.1>
- F. 40 CFR 63 Subpart DDDDD – National Emission Standards for Hazardous Air Pollutants for *Major Sources: Industrial, Commercial, and Institutional Boilers and Process Heaters*
<http://www.ecfr.gov/cgi-bin/retrieveECFR?gp=&r=SUBPART&n=sp40.14.63.ddddd>
- G. 40 CFR 63 Subpart UUUUU – National Emission Standards for Hazardous Air Pollutants from *Coal and Oil-fired Electric Utility Steam Generating Units (EGU-MATS)*
<http://www.ecfr.gov/cgi-bin/retrieveECFR?gp=&r=SUBPART&n=sp40.15.63.uuuuu>



Phase II Acid Rain Permit

Issued to: Muscatine
Operated by: Muscatine Power and Water
ORIS code: 1167
Effective: November 3, 2015 through November 2, 2020

For the Director of the Department of Natural Resources

Lori Hanson, Supervisor of Operating Permits Section

Date

Acid Rain Permit comprises the following:

- 1) Statement of Basis.
- 2) SO₂ allowances allocated under this permit and NO_x requirements for each affected unit.
- 3) Comments, notes and justifications regarding permit decisions and changes made to the permit application forms during the review process, and any additional requirements or conditions.
- 4) The permit application submitted for this source, as corrected by the Iowa Department of Natural Resources (IDNR), Air Quality Bureau, Operating Permit Section. The owners and operators of the source must comply with the standard requirements and special provisions set forth in the application.

1) Statement of Basis

Statutory and Regulatory Authorities: In accordance with Iowa Code paragraph 455B.133[8"a"], and Titles IV and V of the Clean Air Act, the Iowa Department of Natural Resources (IDNR), Air Quality Bureau, Operating Permit Section issues this permit pursuant to 567 Iowa Administrative Code (IAC) 22.135(455B) to 22.145(455B) and 567 IAC 22.100(455B) to 22.116(455B). The compliance options are approved as proposed in the attached application.

2) SO₂ Allowance Allocations and NO_x Requirements for each affected unit

		2015	2016	2017	2018	2019	2020
Unit 8	SO ₂ allowances, under Table 2 of 40 CFR part 73.	1364*	1364*	1364*	1364*	1364*	1364*

		2015	2016	2017	2018	2019	2020
Unit 9	SO ₂ allowances, under Table 2 of 40 CFR part 73.	2030*	2030*	2030*	2030*	2030*	2030*
	NO _x limit	<p>Pursuant to 40 CFR part 76, The Iowa Department of Natural Resources approves a standard emission limitation compliance plan for Unit 9. The NO_x compliance plan is effective beginning 11/3/2015 through 11/2/2020. Under the NO_x compliance plan, this unit's annual average NO_x emission rate for each year, determined in accordance with 40 CFR part 75, shall not exceed the applicable emission limitation under 40 CFR 76.7(a)(1), which is 0.40 lbs/mmBtu for tangentially fired units.</p> <p>In addition to the described NO_x compliance plan, this unit shall comply with all other applicable requirements of 40 CFR part 76, including the duty to reapply for a NO_x compliance plan and the requirements covering excess emissions.</p>					

* The number of allowances allocated to Phase II affected units by U.S. EPA in 40 CFR part 73 Table 2 (Revised May 12, 2005). In addition, the number of allowances actually held by an affected source in a unit account may differ from the number allocated by U.S. EPA. Neither of the aforementioned conditions necessitate a revision to the unit SO₂ allowance allocations identified in this permit (See 40 CFR 72.84).

3) Comments, Notes and Justifications:

Renewal of the Phase II SO₂ and NO_x permit.

4) Permit Application: Attached.

Facility (Source) Name (from STEP 1) Muscatine Power and Water

Permit Requirements

STEP 3

Read the standard requirements.

- (1) The designated representative of each affected source and each affected unit at the source shall:
 - (i) Submit a complete Acid Rain permit application (including a compliance plan) under 40 CFR part 72 in accordance with the deadlines specified in 40 CFR 72.30; and
 - (ii) Submit in a timely manner any supplemental information that the permitting authority determines is necessary in order to review an Acid Rain permit application and issue or deny an Acid Rain permit;
- (2) The owners and operators of each affected source and each affected unit at the source shall:
 - (i) Operate the unit in compliance with a complete Acid Rain permit application or a superseding Acid Rain permit issued by the permitting authority; and
 - (ii) Have an Acid Rain Permit.

Monitoring Requirements

- (1) The owners and operators and, to the extent applicable, designated representative of each affected source and each affected unit at the source shall comply with the monitoring requirements as provided in 40 CFR part 75.
- (2) The emissions measurements recorded and reported in accordance with 40 CFR part 75 shall be used to determine compliance by the source or unit, as appropriate, with the Acid Rain emissions limitations and emissions reduction requirements for sulfur dioxide and nitrogen oxides under the Acid Rain Program.
- (3) The requirements of 40 CFR part 75 shall not affect the responsibility of the owners and operators to monitor emissions of other pollutants or other emissions characteristics at the unit under other applicable requirements of the Act and other provisions of the operating permit for the source.

Sulfur Dioxide Requirements

- (1) The owners and operators of each source and each affected unit at the source shall:
 - (i) Hold allowances, as of the allowance transfer deadline, in the source's compliance account (after deductions under 40 CFR 73.34(c)), not less than the total annual emissions of sulfur dioxide for the previous calendar year from the affected units at the source; and
 - (ii) Comply with the applicable Acid Rain emissions limitations for sulfur dioxide.
- (2) Each ton of sulfur dioxide emitted in excess of the Acid Rain emissions limitations for sulfur dioxide shall constitute a separate violation of the Act.
- (3) An affected unit shall be subject to the requirements under paragraph (1) of the sulfur dioxide requirements as follows:
 - (i) Starting January 1, 2000, an affected unit under 40 CFR 72.6(a)(2); or
 - (ii) Starting on the later of January 1, 2000 or the deadline for monitor certification under 40 CFR part 75, an affected unit under 40 CFR 72.6(a)(3).

Facility (Source) Name (from STEP 1) Muscatine Power and Water

Sulfur Dioxide Requirements, Cont'd.

STEP 3, Cont'd.

- (4) Allowances shall be held in, deducted from, or transferred among Allowance Tracking System accounts in accordance with the Acid Rain Program.
- (5) An allowance shall not be deducted in order to comply with the requirements under paragraph (1) of the sulfur dioxide requirements prior to the calendar year for which the allowance was allocated.
- (6) An allowance allocated by the Administrator under the Acid Rain Program is a limited authorization to emit sulfur dioxide in accordance with the Acid Rain Program. No provision of the Acid Rain Program, the Acid Rain permit application, the Acid Rain permit, or an exemption under 40 CFR 72.7 or 72.8 and no provision of law shall be construed to limit the authority of the United States to terminate or limit such authorization.
- (7) An allowance allocated by the Administrator under the Acid Rain Program does not constitute a property right.

Nitrogen Oxides Requirements

The owners and operators of the source and each affected unit at the source shall comply with the applicable Acid Rain emissions limitation for nitrogen oxides.

Excess Emissions Requirements

- (1) The designated representative of an affected source that has excess emissions in any calendar year shall submit a proposed offset plan, as required under 40 CFR part 77.
- (2) The owners and operators of an affected source that has excess emissions in any calendar year shall:
- (i) Pay without demand the penalty required, and pay upon demand the interest on that penalty, as required by 40 CFR part 77; and
 - (ii) Comply with the terms of an approved offset plan, as required by 40 CFR part 77.

Recordkeeping and Reporting Requirements

- (1) Unless otherwise provided, the owners and operators of the source and each affected unit at the source shall keep on site at the source each of the following documents for a period of 5 years from the date the document is created. This period may be extended for cause, at any time prior to the end of 5 years, in writing by the Administrator or permitting authority:
- (i) The certificate of representation for the designated representative for the source and each affected unit at the source and all documents that demonstrate the truth of the statements in the certificate of representation, in accordance with 40 CFR 72.24; provided that the certificate and documents shall be retained on site at the source beyond such 5-year period until such documents are superseded because of the

Facility (Source) Name (from STEP 1) Muscatine Power and Water

submission of a new certificate of representation changing the designated representative;

STEP 3, Cont'd.

Recordkeeping and Reporting Requirements, Cont'd.

- (ii) All emissions monitoring information, in accordance with 40 CFR part 75, provided that to the extent that 40 CFR part 75 provides for a 3-year period for recordkeeping, the 3-year period shall apply.
 - (iii) Copies of all reports, compliance certifications, and other submissions and all records made or required under the Acid Rain Program; and,
 - (iv) Copies of all documents used to complete an Acid Rain permit application and any other submission under the Acid Rain Program or to demonstrate compliance with the requirements of the Acid Rain Program.
- (2) The designated representative of an affected source and each affected unit at the source shall submit the reports and compliance certifications required under the Acid Rain Program, including those under 40 CFR part 72 subpart I and 40 CFR part 75.

Liability

- (1) Any person who knowingly violates any requirement or prohibition of the Acid Rain Program, a complete Acid Rain permit application, an Acid Rain permit, or an exemption under 40 CFR 72.7 or 72.8, including any requirement for the payment of any penalty owed to the United States, shall be subject to enforcement pursuant to section 113(c) of the Act.
- (2) Any person who knowingly makes a false, material statement in any record, submission, or report under the Acid Rain Program shall be subject to criminal enforcement pursuant to section 113(c) of the Act and 18 U.S.C. 1001.
- (3) No permit revision shall excuse any violation of the requirements of the Acid Rain Program that occurs prior to the date that the revision takes effect.
- (4) Each affected source and each affected unit shall meet the requirements of the Acid Rain Program.
- (5) Any provision of the Acid Rain Program that applies to an affected source (including a provision applicable to the designated representative of an affected source) shall also apply to the owners and operators of such source and of the affected units at the source.
- (6) Any provision of the Acid Rain Program that applies to an affected unit (including a provision applicable to the designated representative of an affected unit) shall also apply to the owners and operators of such unit.
- (7) Each violation of a provision of 40 CFR parts 72, 73, 74, 75, 76, 77, and 78 by an affected source or affected unit, or by an owner or operator or designated representative of such source or unit, shall be a separate violation of the Act.

Effect on Other Authorities

No provision of the Acid Rain Program, an Acid Rain permit application, an Acid Rain permit, or an exemption under 40 CFR 72.7 or 72.8 shall be construed as:

Facility (Source) Name (from STEP 1)
Muscatine Power and Water

(1) Except as expressly provided in title IV of the Act, exempting or excluding the owners and operators and, to the extent applicable, the designated representative of an affected source or affected unit from compliance with any other provision of the Act, including the provisions of title I of the Act relating

STEP 3, Cont'd.

Effect on Other Authorities, Cont'd.

to applicable National Ambient Air Quality Standards or State Implementation Plans;

(2) Limiting the number of allowances a source can hold; *provided*, that the number of allowances held by the source shall not affect the source's obligation to comply with any other provisions of the Act;

(3) Requiring a change of any kind in any State law regulating electric utility rates and charges, affecting any State law regarding such State regulation, or limiting such State regulation, including any prudence review requirements under such State law;

(4) Modifying the Federal Power Act or affecting the authority of the Federal Energy Regulatory Commission under the Federal Power Act; or,

(5) Interfering with or impairing any program for competitive bidding for power supply in a State in which such program is established.

STEP 4
Read the certification statement, sign, and date.

Certification

I am authorized to make this submission on behalf of the owners and operators of the affected source or affected units for which the submission is made. I certify under penalty of law that I have personally examined, and am familiar with, the statements and information submitted in this document and all its attachments. Based on my inquiry of those individuals with primary responsibility for obtaining the information, I certify that the statements and information are to the best of my knowledge and belief true, accurate, and complete. I am aware that there are significant penalties for submitting false statements and information or omitting required statements and information, including the possibility of fine or imprisonment.

Name <i>Jean Brewster</i>	
Signature <i>Jean Brewster</i>	Date <i>10/31/2014</i>



Acid Rain NO_x Compliance Plan

For more information, see instructions and refer to 40 CFR 76.9

This submission is: New Revised Updated

STEP 1
Indicate plant name, State, and Plant code from the current Certificate of Representation covering the facility.

Plant Name	Muscatine Power and Water	State IA	Plant Code 1167
------------	---------------------------	----------	-----------------

STEP 2

Identify each affected Group 1 and Group 2 boiler using the unit IDs from the current Certificate of Representation covering the facility. Also indicate the boiler type: "CB" for cell burner, "CY" for cyclone, "DBW" for dry bottom wall-fired, "T" for tangentially fired, "V" for vertically fired, and "WB" for wet bottom, and select the compliance option for each unit by making an 'X' in the appropriate row and column.

	ID# 9	ID#	ID#	ID#	ID#	ID#
	Type T	Type	Type	Type	Type	Type
(a) Standard annual average emission limitation of 0.50 lb/mmBtu (for Phase I dry bottom wall-fired boilers)						
(b) Standard annual average emission limitation of 0.45 lb/mmBtu (for Phase I tangentially fired boilers)						
(c) Standard annual average emission limitation of 0.46 lb/mmBtu (for Phase II dry bottom wall-fired boilers)						
(d) Standard annual average emission limitation of 0.40 lb/mmBtu (for Phase II tangentially fired boilers)	X					
(e) Standard annual average emission limitation of 0.68 lb/mmBtu (for cell burner boilers)						
(f) Standard annual average emission limitation of 0.86 lb/mmBtu (for cyclone boilers)						
(g) Standard annual average emission limitation of 0.80 lb/mmBtu (for vertically fired boilers)						
(h) Standard annual average emission limitation of 0.84 lb/mmBtu (for wet bottom boilers)						

STEP 2, cont'd

Plant Name (From Step 1) Muscatine Power and Water

	ID#	ID#	ID#	ID#	ID#	ID#
	Type	Type	Type	Type	Type	Type
(i) NO _x Averaging Plan (Include NO _x Averaging form)						
(j) Common stack pursuant to 40 CFR 75.17(a)(2)(i)(A) (check the standard emission limitation box above for most stringent limitation applicable to any unit utilizing stack)						
(k) Common stack pursuant to 40 CFR 75.17(a)(2)(i)(B) with NO _x Averaging (check the NO _x Averaging Plan box and include NO _x Averaging Form)						
(l) EPA-approved common stack emission method pursuant to 40 CFR 75.17(a)(2)(i)(C), (a)(2)(ii)(B), or (b)(4)						

STEP 3: Identify the first calendar year in which this plan will apply.

January 1, _____ 2015 _____

Title V permit expected to be issued in 2015.

STEP 4: Read the special provisions and certification, enter the name of the designated representative, sign and date.

Special Provisions

General. This source is subject to the standard requirements in 40 CFR 72.9. These requirements are listed in this source's Acid Rain Permit.

Certification

I am authorized to make this submission on behalf of the owners and operators of the affected source or affected units for which the submission is made. I certify under penalty of law that I have personally examined, and am familiar with, the statements and information submitted in this document and all its attachments. Based on my inquiry of those individuals with primary responsibility for obtaining the information, I certify that the statements and information are to the best of my knowledge and belief true, accurate, and complete. I am aware that there are significant penalties for submitting false statements and information or omitting required statements and information, including the possibility of fine or imprisonment.

Name Jean Brewster	
Signature	Date 10/31/2014

Transport Rule (TR) Trading Program Title V Requirements

Description of TR Monitoring Provisions

The TR subject unit(s), and the unit-specific monitoring provisions at this source, are identified in the following table(s). These unit(s) are subject to the requirements for the TR NO_x Annual Trading Program, TR NO_x Ozone Season Trading Program and TR SO₂ Group 1 Trading Program.

Unit ID: 8 (ORIS Code: 1167)					
Parameter	Continuous emission monitoring system or systems (CEMS) requirements pursuant to 40 CFR part 75, subpart B (for SO ₂ monitoring) and 40 CFR part 75, subpart H (for NO _x monitoring)	Excepted monitoring system requirements for gas- and oil-fired units pursuant to 40 CFR part 75, appendix D	Excepted monitoring system requirements for gas- and oil-fired peaking units pursuant to 40 CFR part 75, appendix E	Low Mass Emissions excepted monitoring (LME) requirements for gas- and oil-fired units pursuant to 40 CFR 75.19	EPA-approved alternative monitoring system requirements pursuant to 40 CFR part 75, subpart E
SO ₂	X		-----		
NO _x	X	-----			
Heat input	X		-----		

Unit ID: 9 (ORIS Code: 1167)					
Parameter	Continuous emission monitoring system or systems (CEMS) requirements pursuant to 40 CFR part 75, subpart B (for SO ₂ monitoring) and 40 CFR part 75, subpart H (for NO _x monitoring)	Excepted monitoring system requirements for gas- and oil-fired units pursuant to 40 CFR part 75, appendix D	Excepted monitoring system requirements for gas- and oil-fired peaking units pursuant to 40 CFR part 75, appendix E	Low Mass Emissions excepted monitoring (LME) requirements for gas- and oil-fired units pursuant to 40 CFR 75.19	EPA-approved alternative monitoring system requirements pursuant to 40 CFR part 75, subpart E
SO ₂	X		-----		
NO _x	X	-----			
Heat input	X		-----		

1. The above description of the monitoring used by a unit does not change, create an exemption from, or otherwise affect the monitoring, recordkeeping, and reporting requirements applicable to the unit under 40 CFR 97.430 through 97.435 (TR NO_x Annual Trading Program), 97.530 through 97.535 (TR NO_x Ozone Season Trading Program), and 97.630 through 97.635 (TR SO₂ Group 1 Trading Program). The monitoring, recordkeeping and reporting requirements applicable to each unit are included below in the standard conditions for the applicable TR trading programs.

2. Owners and operators must submit to the Administrator a monitoring plan for each unit in accordance with 40 CFR 75.53, 75.62 and 75.73, as applicable. The monitoring plan for each unit is available at the EPA's website at <http://www.epa.gov/airmarkets/emissions/monitoringplans.html>.

3. Owners and operators that want to use an alternative monitoring system must submit to the Administrator a petition requesting approval of the alternative monitoring system in accordance with 40 CFR part 75, subpart E and 40 CFR 75.66 and 97.435 (TR NO_x Annual Trading Program), 97.535 (TR NO_x Ozone Season Trading Program) and/or 97.635 (TR SO₂ Group 1 Trading Program). The Administrator's response approving or disapproving any petition for an alternative monitoring system is available on the EPA's website at <http://www.epa.gov/airmarkets/emissions/petitions.html>.

4. Owners and operators that want to use an alternative to any monitoring, recordkeeping, or reporting requirement under 40 CFR 97.430 through 97.434 (TR NO_x Annual Trading Program), 97.530 through 97.534 (TR NO_x Ozone Season Trading Program) and/or 97.630 through 97.634 (TR SO₂ Group 1 Trading Program) must submit to the Administrator a petition requesting approval of the alternative in accordance with 40 CFR 75.66 and 97.435 (TR NO_x Annual Trading Program), 97.535 (TR NO_x Ozone Season Trading Program) and/or 97.635 (TR SO₂ Group 1 Trading Program). The Administrator's response approving or disapproving any petition for an alternative to a monitoring, recordkeeping, or reporting requirement is available on EPA's website at <http://www.epa.gov/airmarkets/emissions/petitions.html>.

5. The descriptions of monitoring applicable to the unit included above meet the requirement of 40 CFR 97.430 through 97.434 (TR NO_x Annual Trading Program), 97.530 through 97.534 (TR NO_x Ozone Season Trading Program) and 97.630 through 97.634 (TR SO₂ Group 1 Trading Program), and therefore minor permit modification procedures, in accordance with 40 CFR 70.7(e)(2)(i)(B) or 71.7(e)(1)(i)(B), may be used to add to or change this unit's monitoring system description.

TR NO_x Annual Trading Program requirements (40 CFR 97.406)

(a) Designated representative requirements.

The owners and operators shall comply with the requirement to have a designated representative, and may have an alternate designated representative, in accordance with 40 CFR 97.413 through 97.418.

(b) Emissions monitoring, reporting, and recordkeeping requirements.

(1) The owners and operators, and the designated representative, of each TR NO_x Annual source and each TR NO_x Annual unit at the source shall comply with the monitoring, reporting, and recordkeeping requirements of 40 CFR 97.430 (general requirements, including installation, certification, and data accounting, compliance deadlines, reporting data, prohibitions, and long-term cold storage), 97.431 (initial monitoring system certification and recertification procedures), 97.432 (monitoring system out-of-control periods), 97.433 (notifications concerning monitoring), 97.434 (recordkeeping and reporting, including monitoring plans, certification applications, quarterly reports, and compliance certification), and 97.435 (petitions for alternatives to monitoring, recordkeeping, or reporting requirements).

(2) The emissions data determined in accordance with 40 CFR 97.430 through 97.435 shall be used to calculate allocations of TR NO_x Annual allowances under 40 CFR 97.411(a)(2) and (b) and 97.412 and to determine compliance with the TR NO_x Annual emissions limitation and assurance provisions under paragraph (c) below, provided that, for each monitoring location from which mass emissions are reported, the mass emissions amount used in calculating such allocations and determining such compliance shall be the mass emissions amount for the monitoring location determined in accordance with 40 CFR 97.430 through 97.435 and rounded to the nearest ton, with any fraction of a ton less than 0.50 being deemed to be zero.

(c) NO_x emissions requirements.

(1) TR NO_x Annual emissions limitation.

- (i). As of the allowance transfer deadline for a control period in a given year, the owners and operators of each TR NO_x Annual source and each TR NO_x Annual unit at the source shall hold, in the source's compliance account, TR NO_x Annual allowances available for deduction for such control period under 40 CFR 97.424(a) in an amount not less than the tons of total NO_x emissions for such control period from all TR NO_x Annual units at the source.
- (ii). If total NO_x emissions during a control period in a given year from the TR NO_x Annual units at a TR NO_x Annual source are in excess of the TR NO_x Annual emissions limitation set forth in paragraph (c)(1)(i) above, then:
 - (A). The owners and operators of the source and each TR NO_x Annual unit at the source shall hold the TR NO_x Annual allowances required for deduction under 40 CFR 97.424(d); and
 - (B). The owners and operators of the source and each TR NO_x Annual unit at the source shall pay any fine, penalty, or assessment or comply with any other remedy imposed, for the same violations, under the Clean Air Act, and each ton of such excess emissions and each day of such control period shall constitute a separate violation of 40 CFR part 97, subpart AAAAA and the Clean Air Act.

(2) TR NO_x Annual assurance provisions.

- (i). If total NO_x emissions during a control period in a given year from all TR NO_x Annual units at TR NO_x Annual sources in the state exceed the state assurance level, then the owners and operators of such sources and units in each group of one or more sources and units having a common designated representative for such control period, where the common designated representative's share of such NO_x emissions during such control period exceeds the common designated representative's assurance level for the state and such control period, shall hold (in the assurance account established for the owners and operators of such group) TR NO_x Annual allowances available for deduction for such control period under 40 CFR 97.425(a) in an amount equal to two times the product (rounded to the nearest whole number), as determined by the Administrator in accordance with 40 CFR 97.425(b), of multiplying— (A) The quotient of the amount by which the common designated representative's share of such NO_x emissions exceeds the common designated representative's assurance level divided by the sum of the amounts, determined for all common designated representatives for such sources and units in the state for such control period, by which each common designated representative's share of such NO_x emissions exceeds the respective common designated representative's assurance level; and (B) The amount by which total NO_x emissions from all TR NO_x Annual units at TR NO_x Annual sources in the state for such control period exceed the state assurance level.
- (ii). The owners and operators shall hold the TR NO_x Annual allowances required under paragraph (c)(2)(i) above, as of midnight of November 1 (if it is a business day), or

midnight of the first business day thereafter (if November 1 is not a business day), immediately after such control period.

- (iii). Total NO_x emissions from all TR NO_x Annual units at TR NO_x Annual sources in the State during a control period in a given year exceed the state assurance level if such total NO_x emissions exceed the sum, for such control period, of the state NO_x Annual trading budget under 40 CFR 97.410(a) and the state's variability limit under 40 CFR 97.410(b).
 - (iv). It shall not be a violation of 40 CFR part 97, subpart AAAAA or of the Clean Air Act if total NO_x emissions from all TR NO_x Annual units at TR NO_x Annual sources in the State during a control period exceed the state assurance level or if a common designated representative's share of total NO_x emissions from the TR NO_x Annual units at TR NO_x Annual sources in the state during a control period exceeds the common designated representative's assurance level.
 - (v). To the extent the owners and operators fail to hold TR NO_x Annual allowances for a control period in a given year in accordance with paragraphs (c)(2)(i) through (iii) above,
 - (A). The owners and operators shall pay any fine, penalty, or assessment or comply with any other remedy imposed under the Clean Air Act; and
 - (B). Each TR NO_x Annual allowance that the owners and operators fail to hold for such control period in accordance with paragraphs (c)(2)(i) through (iii) above and each day of such control period shall constitute a separate violation of 40 CFR part 97, subpart AAAAA and the Clean Air Act.
- (3) Compliance periods.
- (i). A TR NO_x Annual unit shall be subject to the requirements under paragraph (c)(1) above for the control period starting on the later of January 1, 2015, or the deadline for meeting the unit's monitor certification requirements under 40 CFR 97.430(b) and for each control period thereafter.
 - (ii). A TR NO_x Annual unit shall be subject to the requirements under paragraph (c)(2) above for the control period starting on the later of January 1, 2017 or the deadline for meeting the unit's monitor certification requirements under 40 CFR 97.430(b) and for each control period thereafter.
- (4) Vintage of allowances held for compliance.
- (i). A TR NO_x Annual allowance held for compliance with the requirements under paragraph (c)(1)(i) above for a control period in a given year must be a TR NO_x Annual allowance that was allocated for such control period or a control period in a prior year.
 - (ii). A TR NO_x Annual allowance held for compliance with the requirements under paragraphs (c)(1)(ii)(A) and (2)(i) through (iii) above for a control period in a given year must be a TR NO_x Annual allowance that was allocated for a control period in a prior year or the control period in the given year or in the immediately following year.
- (5) Allowance Management System requirements. Each TR NO_x Annual allowance shall be held in, deducted from, or transferred into, out of, or between Allowance Management System accounts in accordance with 40 CFR part 97, subpart AAAAA.
- (6) Limited authorization. A TR NO_x Annual allowance is a limited authorization to emit one ton of NO_x during the control period in one year. Such authorization is limited in its use and duration as follows:
- (i). Such authorization shall only be used in accordance with the TR NO_x Annual Trading Program; and
 - (ii). Notwithstanding any other provision of 40 CFR part 97, the Administrator has the authority to terminate or limit the use and duration of such authorization to the extent the Administrator determines is necessary or appropriate to implement any provision of the Clean Air Act.

(7) Property right. A TR NO_x Annual allowance does not constitute a property right.

(d) Title V permit revision requirements.

- (1) No title V permit revision shall be required for any allocation, holding, deduction, or transfer of TR NO_x Annual allowances in accordance with 40 CFR part 97, subpart AAAAA.
- (2) This permit incorporates the TR emissions monitoring, recordkeeping and reporting requirements pursuant to 40 CFR 97.430 through 97.435, and the requirements for a continuous emission monitoring system (pursuant to 40 CFR part 75, subparts B and H), an excepted monitoring system (pursuant to 40 CFR part 75, appendices D and E), a low mass emissions excepted monitoring methodology (pursuant to 40 CFR 75.19), and an alternative monitoring system (pursuant to 40 CFR part 75, subpart E). Therefore, the Description of TR Monitoring Provisions table for units identified in this permit may be added to, or changed, in this title V permit using minor permit modification procedures in accordance with 40 CFR 97.406(d)(2) and 70.7(e)(2)(i)(B) or 71.7(e)(1)(i)(B).

(e) Additional recordkeeping and reporting requirements.

- (1) Unless otherwise provided, the owners and operators of each TR NO_x Annual source and each TR NO_x Annual unit at the source shall keep on site at the source each of the following documents (in hardcopy or electronic format) for a period of 5 years from the date the document is created. This period may be extended for cause, at any time before the end of 5 years, in writing by the Administrator.
 - (i). The certificate of representation under 40 CFR 97.416 for the designated representative for the source and each TR NO_x Annual unit at the source and all documents that demonstrate the truth of the statements in the certificate of representation; provided that the certificate and documents shall be retained on site at the source beyond such 5-year period until such certificate of representation and documents are superseded because of the submission of a new certificate of representation under 40 CFR 97.416 changing the designated representative.
 - (ii). All emissions monitoring information, in accordance with 40 CFR part 97, subpart AAAAA.
 - (iii). Copies of all reports, compliance certifications, and other submissions and all records made or required under, or to demonstrate compliance with the requirements of, the TR NO_x Annual Trading Program.
- (2) The designated representative of a TR NO_x Annual source and each TR NO_x Annual unit at the source shall make all submissions required under the TR NO_x Annual Trading Program, except as provided in 40 CFR 97.418. This requirement does not change, create an exemption from, or otherwise affect the responsible official submission requirements under a title V operating permit program in 40 CFR parts 70 and 71.

(f) Liability.

- (1) Any provision of the TR NO_x Annual Trading Program that applies to a TR NO_x Annual source or the designated representative of a TR NO_x Annual source shall also apply to the owners and operators of such source and of the TR NO_x Annual units at the source.
- (2) Any provision of the TR NO_x Annual Trading Program that applies to a TR NO_x Annual unit or the designated representative of a TR NO_x Annual unit shall also apply to the owners and operators of such unit.

(g) Effect on other authorities.

No provision of the TR NO_x Annual Trading Program or exemption under 40 CFR 97.405 shall be construed as exempting or excluding the owners and operators, and the designated representative, of a TR NO_x Annual source or TR NO_x Annual unit from compliance with any other provision of the applicable, approved state implementation plan, a federally enforceable permit, or the Clean Air Act.

TR NO_x Ozone Season Trading Program Requirements (40 CFR 97.506)

(a) Designated representative requirements.

The owners and operators shall comply with the requirement to have a designated representative, and may have an alternate designated representative, in accordance with 40 CFR 97.513 through 97.518.

(b) Emissions monitoring, reporting, and recordkeeping requirements.

- (1) The owners and operators, and the designated representative, of each TR NO_x Ozone Season source and each TR NO_x Ozone Season unit at the source shall comply with the monitoring, reporting, and recordkeeping requirements of 40 CFR 97.530 (general requirements, including installation, certification, and data accounting, compliance deadlines, reporting data, prohibitions, and long-term cold storage), 97.531 (initial monitoring system certification and recertification procedures), 97.532 (monitoring system out-of-control periods), 97.533 (notifications concerning monitoring), 97.534 (recordkeeping and reporting, including monitoring plans, certification applications, quarterly reports, and compliance certification), and 97.535 (petitions for alternatives to monitoring, recordkeeping, or reporting requirements).
- (2) The emissions data determined in accordance with 40 CFR 97.530 through 97.535 shall be used to calculate allocations of TR NO_x Ozone Season allowances under 40 CFR 97.511(a)(2) and (b) and 97.512 and to determine compliance with the TR NO_x Ozone Season emissions limitation and assurance provisions under paragraph (c) below, provided that, for each monitoring location from which mass emissions are reported, the mass emissions amount used in calculating such allocations and determining such compliance shall be the mass emissions amount for the monitoring location determined in accordance with 40 CFR 97.530 through 97.535 and rounded to the nearest ton, with any fraction of a ton less than 0.50 being deemed to be zero.

(c) NO_x emissions requirements.

- (1) TR NO_x Ozone Season emissions limitation.
 - (i). As of the allowance transfer deadline for a control period in a given year, the owners and operators of each TR NO_x Ozone Season source and each TR NO_x Ozone Season unit at the source shall hold, in the source's compliance account, TR NO_x Ozone Season allowances available for deduction for such control period under 40 CFR 97.524(a) in an amount not less than the tons of total NO_x emissions for such control period from all TR NO_x Ozone Season units at the source.
 - (ii). If total NO_x emissions during a control period in a given year from the TR NO_x Ozone Season units at a TR NO_x Ozone Season source are in excess of the TR NO_x Ozone Season emissions limitation set forth in paragraph (c)(1)(i) above, then:
 - (A). The owners and operators of the source and each TR NO_x Ozone Season unit at the source shall hold the TR NO_x Ozone Season allowances required for deduction under 40 CFR 97.524(d); and
 - (B). The owners and operators of the source and each TR NO_x Ozone Season unit at the source shall pay any fine, penalty, or assessment or comply with any other remedy imposed, for the same violations, under the Clean Air Act, and each ton of such excess emissions and each day of such control period shall constitute a separate violation of 40 CFR part 97, subpart BBBB and the Clean Air Act.
- (2) TR NO_x Ozone Season assurance provisions.
 - (i). If total NO_x emissions during a control period in a given year from all TR NO_x Ozone Season units at TR NO_x Ozone Season sources in the state exceed the state assurance level, then the owners and operators of such sources and units in each group of one or more sources and units having a common designated representative for such control period, where the common designated representative's share of such NO_x emissions during such control period exceeds the common designated representative's assurance level for the state

and such control period, shall hold (in the assurance account established for the owners and operators of such group) TR NO_x Ozone Season allowances available for deduction for such control period under 40 CFR 97.525(a) in an amount equal to two times the product (rounded to the nearest whole number), as determined by the Administrator in accordance with 40 CFR 97.525(b), of multiplying—

- (A). The quotient of the amount by which the common designated representative's share of such NO_x emissions exceeds the common designated representative's assurance level divided by the sum of the amounts, determined for all common designated representatives for such sources and units in the state for such control period, by which each common designated representative's share of such NO_x emissions exceeds the respective common designated representative's assurance level; and
 - (B). The amount by which total NO_x emissions from all TR NO_x Ozone Season units at TR NO_x Ozone Season sources in the state for such control period exceed the state assurance level.
- (ii). The owners and operators shall hold the TR NO_x Ozone Season allowances required under paragraph (c)(2)(i) above, as of midnight of November 1 (if it is a business day), or midnight of the first business day thereafter (if November 1 is not a business day), immediately after such control period.
 - (iii). Total NO_x emissions from all TR NO_x Ozone Season units at TR NO_x Ozone Season sources in the state during a control period in a given year exceed the state assurance level if such total NO_x emissions exceed the sum, for such control period, of the State NO_x Ozone Season trading budget under 40 CFR 97.510(a) and the state's variability limit under 40 CFR 97.510(b).
 - (iv). It shall not be a violation of 40 CFR part 97, subpart BBBBBB or of the Clean Air Act if total NO_x emissions from all TR NO_x Ozone Season units at TR NO_x Ozone Season sources in the state during a control period exceed the state assurance level or if a common designated representative's share of total NO_x emissions from the TR NO_x Ozone Season units at TR NO_x Ozone Season sources in the state during a control period exceeds the common designated representative's assurance level.
 - (v). To the extent the owners and operators fail to hold TR NO_x Ozone Season allowances for a control period in a given year in accordance with paragraphs (c)(2)(i) through (iii) above,
 - (A). The owners and operators shall pay any fine, penalty, or assessment or comply with any other remedy imposed under the Clean Air Act; and
 - (B). Each TR NO_x Ozone Season allowance that the owners and operators fail to hold for such control period in accordance with paragraphs (c)(2)(i) through (iii) above and each day of such control period shall constitute a separate violation of 40 CFR part 97, subpart BBBBBB and the Clean Air Act.
- (3) Compliance periods.
- (i). A TR NO_x Ozone Season unit shall be subject to the requirements under paragraph (c)(1) above for the control period starting on the later of May 1, 2015 or the deadline for meeting the unit's monitor certification requirements under 40 CFR 97.530(b) and for each control period thereafter.
 - (ii). A TR NO_x Ozone Season unit shall be subject to the requirements under paragraph (c)(2) above for the control period starting on the later of May 1, 2017 or the deadline for meeting the unit's monitor certification requirements under 40 CFR 97.530(b) and for each control period thereafter.
- (4) Vintage of allowances held for compliance.
- (i). A TR NO_x Ozone Season allowance held for compliance with the requirements under paragraph (c)(1)(i) above for a control period in a given year must be a TR NO_x Ozone

Season allowance that was allocated for such control period or a control period in a prior year.

- (ii). A TR NO_x Ozone Season allowance held for compliance with the requirements under paragraphs (c)(1)(ii)(A) and (2)(i) through (iii) above for a control period in a given year must be a TR NO_x Ozone Season allowance that was allocated for a control period in a prior year or the control period in the given year or in the immediately following year.
- (5) Allowance Management System requirements. Each TR NO_x Ozone Season allowance shall be held in, deducted from, or transferred into, out of, or between Allowance Management System accounts in accordance with 40 CFR part 97, subpart BBBBB.
- (6) Limited authorization. A TR NO_x Ozone Season allowance is a limited authorization to emit one ton of NO_x during the control period in one year. Such authorization is limited in its use and duration as follows:
- (i). Such authorization shall only be used in accordance with the TR NO_x Ozone Season Trading Program; and
 - (ii). Notwithstanding any other provision of 40 CFR part 97, subpart BBBBB, the Administrator has the authority to terminate or limit the use and duration of such authorization to the extent the Administrator determines is necessary or appropriate to implement any provision of the Clean Air Act.
- (7) Property right. A TR NO_x Ozone Season allowance does not constitute a property right.

(d) Title V permit revision requirements.

- (1) No title V permit revision shall be required for any allocation, holding, deduction, or transfer of TR NO_x Ozone Season allowances in accordance with 40 CFR part 97, subpart BBBBB.
- (2) This permit incorporates the TR emissions monitoring, recordkeeping and reporting requirements pursuant to 40 CFR 97.530 through 97.535, and the requirements for a continuous emission monitoring system (pursuant to 40 CFR part 75, subparts B and H), an excepted monitoring system (pursuant to 40 CFR part 75, appendices D and E), a low mass emissions excepted monitoring methodology (pursuant to 40 CFR 75.19), and an alternative monitoring system (pursuant to 40 CFR part 75, subpart E). Therefore, the Description of TR Monitoring Provisions table for units identified in this permit may be added to, or changed, in this title V permit using minor permit modification procedures in accordance with 40 CFR 97.506(d)(2) and 70.7(e)(2)(i)(B) or 71.7(e)(1)(i)(B).

(e) Additional recordkeeping and reporting requirements.

- (1) Unless otherwise provided, the owners and operators of each TR NO_x Ozone Season source and each TR NO_x Ozone Season unit at the source shall keep on site at the source each of the following documents (in hardcopy or electronic format) for a period of 5 years from the date the document is created. This period may be extended for cause, at any time before the end of 5 years, in writing by the Administrator.
 - (i). The certificate of representation under 40 CFR 97.516 for the designated representative for the source and each TR NO_x Ozone Season unit at the source and all documents that demonstrate the truth of the statements in the certificate of representation; provided that the certificate and documents shall be retained on site at the source beyond such 5-year period until such certificate of representation and documents are superseded because of the submission of a new certificate of representation under 40 CFR 97.516 changing the designated representative.
 - (ii). All emissions monitoring information, in accordance with 40 CFR part 97, subpart BBBBB.
 - (iii). Copies of all reports, compliance certifications, and other submissions and all records made or required under, or to demonstrate compliance with the requirements of, the TR NO_x Ozone Season Trading Program.

- (2) The designated representative of a TR NO_x Ozone Season source and each TR NO_x Ozone Season unit at the source shall make all submissions required under the TR NO_x Ozone Season Trading Program, except as provided in 40 CFR 97.518. This requirement does not change, create an exemption from, or otherwise affect the responsible official submission requirements under a title V operating permit program in 40 CFR parts 70 and 71.

(f) Liability.

- (1) Any provision of the TR NO_x Ozone Season Trading Program that applies to a TR NO_x Ozone Season source or the designated representative of a TR NO_x Ozone Season source shall also apply to the owners and operators of such source and of the TR NO_x Ozone Season units at the source.
- (2) Any provision of the TR NO_x Ozone Season Trading Program that applies to a TR NO_x Ozone Season unit or the designated representative of a TR NO_x Ozone Season unit shall also apply to the owners and operators of such unit.

(g) Effect on other authorities.

No provision of the TR NO_x Ozone Season Trading Program or exemption under 40 CFR 97.505 shall be construed as exempting or excluding the owners and operators, and the designated representative, of a TR NO_x Ozone Season source or TR NO_x Ozone Season unit from compliance with any other provision of the applicable, approved state implementation plan, a federally enforceable permit, or the Clean Air Act.

TR SO₂ Group 1 Trading Program requirements (40 CFR 97.606)

(a) Designated representative requirements.

The owners and operators shall comply with the requirement to have a designated representative, and may have an alternate designated representative, in accordance with 40 CFR 97.613 through 97.618.

(b) Emissions monitoring, reporting, and recordkeeping requirements.

- (1) The owners and operators, and the designated representative, of each TR SO₂ Group 1 source and each TR SO₂ Group 1 unit at the source shall comply with the monitoring, reporting, and recordkeeping requirements of 40 CFR 97.630 (general requirements, including installation, certification, and data accounting, compliance deadlines, reporting data, prohibitions, and long-term cold storage), 97.631 (initial monitoring system certification and recertification procedures), 97.632 (monitoring system out-of-control periods), 97.633 (notifications concerning monitoring), 97.634 (recordkeeping and reporting, including monitoring plans, certification applications, quarterly reports, and compliance certification), and 97.635 (petitions for alternatives to monitoring, recordkeeping, or reporting requirements).
- (2) The emissions data determined in accordance with 40 CFR 97.630 through 97.635 shall be used to calculate allocations of TR SO₂ Group 1 allowances under 40 CFR 97.611(a)(2) and (b) and 97.612 and to determine compliance with the TR SO₂ Group 1 emissions limitation and assurance provisions under paragraph (c) below, provided that, for each monitoring location from which mass emissions are reported, the mass emissions amount used in calculating such allocations and determining such compliance shall be the mass emissions amount for the monitoring location determined in accordance with 40 CFR 97.630 through 97.635 and rounded to the nearest ton, with any fraction of a ton less than 0.50 being deemed to be zero.

(c) SO₂ emissions requirements.

- (1) TR SO₂ Group 1 emissions limitation.
 - (i) As of the allowance transfer deadline for a control period in a given year, the owners and operators of each TR SO₂ Group 1 source and each TR SO₂ Group 1 unit at the source shall hold, in the source's compliance account, TR SO₂ Group 1 allowances available for deduction for such control period under 40 CFR 97.624(a) in an amount not less than the

tons of total SO₂ emissions for such control period from all TR SO₂ Group 1 units at the source.

- (ii). If total SO₂ emissions during a control period in a given year from the TR SO₂ Group 1 units at a TR SO₂ Group 1 source are in excess of the TR SO₂ Group 1 emissions limitation set forth in paragraph (c)(1)(i) above, then:
 - (A). The owners and operators of the source and each TR SO₂ Group 1 unit at the source shall hold the TR SO₂ Group 1 allowances required for deduction under 40 CFR 97.624(d); and
 - (B). The owners and operators of the source and each TR SO₂ Group 1 unit at the source shall pay any fine, penalty, or assessment or comply with any other remedy imposed, for the same violations, under the Clean Air Act, and each ton of such excess emissions and each day of such control period shall constitute a separate violation 40 CFR part 97, subpart CCCCC and the Clean Air Act.
- (2) TR SO₂ Group 1 assurance provisions.
- (i). If total SO₂ emissions during a control period in a given year from all TR SO₂ Group 1 units at TR SO₂ Group 1 sources in the state exceed the state assurance level, then the owners and operators of such sources and units in each group of one or more sources and units having a common designated representative for such control period, where the common designated representative's share of such SO₂ emissions during such control period exceeds the common designated representative's assurance level for the state and such control period, shall hold (in the assurance account established for the owners and operators of such group) TR SO₂ Group 1 allowances available for deduction for such control period under 40 CFR 97.625(a) in an amount equal to two times the product (rounded to the nearest whole number), as determined by the Administrator in accordance with 40 CFR 97.625(b), of multiplying—
 - (A). The quotient of the amount by which the common designated representative's share of such SO₂ emissions exceeds the common designated representative's assurance level divided by the sum of the amounts, determined for all common designated representatives for such sources and units in the state for such control period, by which each common designated representative's share of such SO₂ emissions exceeds the respective common designated representative's assurance level; and
 - (B). The amount by which total SO₂ emissions from all TR SO₂ Group 1 units at TR SO₂ Group 1 sources in the state for such control period exceed the state assurance level.
 - (ii). The owners and operators shall hold the TR SO₂ Group 1 allowances required under paragraph (c)(2)(i) above, as of midnight of November 1 (if it is a business day), or midnight of the first business day thereafter (if November 1 is not a business day), immediately after such control period.
 - (iii). Total SO₂ emissions from all TR SO₂ Group 1 units at TR SO₂ Group 1 sources in the state during a control period in a given year exceed the state assurance level if such total SO₂ emissions exceed the sum, for such control period, of the state SO₂ Group 1 trading budget under 40 CFR 97.610(a) and the state's variability limit under 40 CFR 97.610(b).
 - (iv). It shall not be a violation of 40 CFR part 97, subpart CCCCC or of the Clean Air Act if total SO₂ emissions from all TR SO₂ Group 1 units at TR SO₂ Group 1 sources in the state during a control period exceed the state assurance level or if a common designated representative's share of total SO₂ emissions from the TR SO₂ Group 1 units at TR SO₂ Group 1 sources in the state during a control period exceeds the common designated representative's assurance level.
 - (v). To the extent the owners and operators fail to hold TR SO₂ Group 1 allowances for a control period in a given year in accordance with paragraphs (c)(2)(i) through (iii) above,

- (A). The owners and operators shall pay any fine, penalty, or assessment or comply with any other remedy imposed under the Clean Air Act; and
- (B). Each TR SO₂ Group 1 allowance that the owners and operators fail to hold for such control period in accordance with paragraphs (c)(2)(i) through (iii) above and each day of such control period shall constitute a separate violation of 40 CFR part 97, subpart CCCCC and the Clean Air Act.

(3) Compliance periods.

- (i). A TR SO₂ Group 1 unit shall be subject to the requirements under paragraph (c)(1) above for the control period starting on the later of January 1, 2015 or the deadline for meeting the unit's monitor certification requirements under 40 CFR 97.630(b) and for each control period thereafter.
- (ii). A TR SO₂ Group 1 unit shall be subject to the requirements under paragraph (c)(2) above for the control period starting on the later of January 1, 2017 or the deadline for meeting the unit's monitor certification requirements under 40 CFR 97.630(b) and for each control period thereafter.

(4) Vintage of allowances held for compliance.

- (i). A TR SO₂ Group 1 allowance held for compliance with the requirements under paragraph (c)(1)(i) above for a control period in a given year must be a TR SO₂ Group 1 allowance that was allocated for such control period or a control period in a prior year.
- (ii). A TR SO₂ Group 1 allowance held for compliance with the requirements under paragraphs (c)(1)(ii)(A) and (2)(i) through (iii) above for a control period in a given year must be a TR SO₂ Group 1 allowance that was allocated for a control period in a prior year or the control period in the given year or in the immediately following year.

(5) Allowance Management System requirements. Each TR SO₂ Group 1 allowance shall be held in, deducted from, or transferred into, out of, or between Allowance Management System accounts in accordance with 40 CFR part 97, subpart CCCCC.

(6) Limited authorization. A TR SO₂ Group 1 allowance is a limited authorization to emit one ton of SO₂ during the control period in one year. Such authorization is limited in its use and duration as follows:

- (i). Such authorization shall only be used in accordance with the TR SO₂ Group 1 Trading Program; and
- (ii). Notwithstanding any other provision of 40 CFR part 97, subpart CCCCC, the Administrator has the authority to terminate or limit the use and duration of such authorization to the extent the Administrator determines is necessary or appropriate to implement any provision of the Clean Air Act.

(7) Property right. A TR SO₂ Group 1 allowance does not constitute a property right.

(d) Title V permit revision requirements.

- (1) No title V permit revision shall be required for any allocation, holding, deduction, or transfer of TR SO₂ Group 1 allowances in accordance with 40 CFR part 97, subpart CCCCC.
- (2) This permit incorporates the TR emissions monitoring, recordkeeping and reporting requirements pursuant to 40 CFR 97.630 through 97.635, and the requirements for a continuous emission monitoring system (pursuant to 40 CFR part 75, subparts B and H), an excepted monitoring system (pursuant to 40 CFR part 75, appendices D and E), a low mass emissions excepted monitoring methodology (pursuant to 40 CFR part 75.19), and an alternative monitoring system (pursuant to 40 CFR part 75, subpart E), Therefore, the Description of TR Monitoring Provisions table for units identified in this permit may be added to, or changed, in this title V permit using minor permit modification procedures in accordance with 40 CFR 97.606(d)(2) and 70.7(e)(2)(i)(B) or 71.7(e)(1)(i)(B).

(e) Additional recordkeeping and reporting requirements.

- (1) Unless otherwise provided, the owners and operators of each TR SO₂ Group 1 source and each TR SO₂ Group 1 unit at the source shall keep on site at the source each of the following documents (in hardcopy or electronic format) for a period of 5 years from the date the document is created. This period may be extended for cause, at any time before the end of 5 years, in writing by the Administrator.
 - (i). The certificate of representation under 40 CFR 97.616 for the designated representative for the source and each TR SO₂ Group 1 unit at the source and all documents that demonstrate the truth of the statements in the certificate of representation; provided that the certificate and documents shall be retained on site at the source beyond such 5-year period until such certificate of representation and documents are superseded because of the submission of a new certificate of representation under 40 CFR 97.616 changing the designated representative.
 - (ii). All emissions monitoring information, in accordance with 40 CFR part 97, subpart CCCCC.
 - (iii). Copies of all reports, compliance certifications, and other submissions and all records made or required under, or to demonstrate compliance with the requirements of, the TR SO₂ Group 1 Trading Program.
- (2) The designated representative of a TR SO₂ Group 1 source and each TR SO₂ Group 1 unit at the source shall make all submissions required under the TR SO₂ Group 1 Trading Program, except as provided in 40 CFR 97.618. This requirement does not change, create an exemption from, or otherwise affect the responsible official submission requirements under a title V operating permit program in 40 CFR parts 70 and 71.

(f) Liability.

- (1) Any provision of the TR SO₂ Group 1 Trading Program that applies to a TR SO₂ Group 1 source or the designated representative of a TR SO₂ Group 1 source shall also apply to the owners and operators of such source and of the TR SO₂ Group 1 units at the source.
- (2) Any provision of the TR SO₂ Group 1 Trading Program that applies to a TR SO₂ Group 1 unit or the designated representative of a TR SO₂ Group 1 unit shall also apply to the owners and operators of such unit.

(g) Effect on other authorities.

No provision of the TR SO₂ Group 1 Trading Program or exemption under 40 CFR 97.605 shall be construed as exempting or excluding the owners and operators, and the designated representative, of a TR SO₂ Group 1 source or TR SO₂ Group 1 unit from compliance with any other provision of the applicable, approved state implementation plan, a federally enforceable permit, or the Clean Air Act.